

## CONSTRUCTION DOCUMENTS PROJECT MANUAL

## DANE COUNTY DEPARTMENT OF WASTE & RENEWABLES

1919 ALLIANT ENERGY CENTER WAY MADISON, WISCONSIN 53713

# REQUEST FOR BIDS NO. 319006 PERIMETER GAS MITIGATION SYSTEM DANE COUNTY LANDFILL SITE NO. 1 4650 MAPLE GROVE ROAD VERONA, WISCONSIN

Due Date / Time: TUESDAY, APRIL 9, 2019 / 2:00 P.M. Location: WASTE & RENEWABLES OFFICE

Performance / Payment Bond: 100% OF CONTRACT AMOUNT Bid Deposit: 5% OF BID AMOUNT

FOR INFORMATION ON THIS REQUEST FOR BIDS, PLEASE CONTACT:

ABDULLAH YOUNES, PROJECT MANAGER
TELEPHONE NO.: 608/516-6228
FAX NO.: 608/267-1533
E-MAIL: YOUNES@COUNTYOFDANE.COM

#### TABLE OF CONTENTS FOR RFB NO. 319006

#### **DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS**

Project Manual Cover Page

**Table of Contents** 

Advertisement for Bids (Legal Notice)

Best Value Contracting Application

Instructions to Bidders

Bid Form

Fair Labor Practices Certification

Sample Waste and Renewables Construction Contract

Sample Bid Bond

Sample Performance Bond

Sample Payment Bond

General Conditions of Contract

**Supplementary Conditions** 

#### **DIVISION 01**

Section 01001 - Basic Requirements

Section 01010 - Summary of Work

Section 01016 - Safety Requirements and Protection of Property

Section 01200 - Measurement and Payment

Section 01650 - System Startup

#### **DIVISION 02**

Section 02200 - Earthwork, Trenching, and Backfilling

Section 02270 - Erosion Control

Section 02665 – Gas Monitoring Probes

Section 02693 - Gas Control Wells

#### **DIVISION 15**

Section 15051 - PVC Pipe

Section 15067 - Polyethylene Pipe

#### **DIVISION 16**

Section 16050 - General Electrical Requirements

Section 16912 - Field Instruments

#### **DRAWINGS**

Sheet No. 1 - Title Sheet

Sheet No. 2 - Existing Conditions

Sheet No. 3 - Documentation Tables

Sheet No. 4 - Perimeter Gas Mitigation System Layout

Sheet No. 5 - Details and P&ID

Sheet No. 6 - Details

Sheet No. 7 - Blower Area Piping

Sheet No. 8 - One-line Diagram

#### LEGAL NOTICE

#### **INVITATION TO BID**

Dane County Dept. of Waste and Renewables, 1919 Alliant Energy Center Way, Madison, WI 53713, will receive sealed Bids until:

2:00 P.M., TUESDAY, APRIL 9, 2019

## RFB NO. 319006 PERIMETER GAS MITIGATION SYSTEM DANE COUNTY LANDFILL SITE NO. 1 4650 MAPLE GROVE ROAD VERONA, WI

Dane County is inviting Bids for construction services for a standalone perimeter gas mitigation system consisting of 900 LF of header pipe, gas control wells, gas probes, and supplemental control instrumentation. Only firms with capabilities, experience & expertise with similar projects should obtain this Request for Bids document & submit Bids.

Request for Bids document may be obtained after **2:00 p.m. on Tuesday, March 12, 2019** by downloading it from <u>bids-pwht.countyofdane.com</u>. Please call Abdullah Younes, Project Manager, at 608/516-6228, or our office at 608/266-4018, for any questions or additional information.

All Bidders must be pre-qualified as a Best Value Contractor before award of Contract. Complete Pre-qualification Application for Contractors at <a href="mailto:countyofdane.com/pwht/BVC\_Application.aspx">countyofdane.com/pwht/BVC\_Application.aspx</a> or obtain one by calling 608/267-0119.

A pre-bid site tour will be held Wednesday, March 27, 2019 at 1 p.m. at Dane County Landfill Site No. 1, starting at the Generator Building. Bidders are strongly encouraged to attend this optional tour.

PUBLISH: MARCH 12 & 19, 2019 - WISCONSIN STATE JOURNAL MARCH 12 & 19, 2019 - THE DAILY REPORTER

RFB No. 319006 rev. 02/18



## DANE COUNTY DEPARTMENT OF WASTE & RENEWABLES

County Executive Joseph T. Parisi 1919 Alliant Energy Center Way • Madison, Wisconsin 53713 Phone: (608) 266-4018 • FAX: (608) 267-1533

**Director** John Welch

#### BEST VALUE CONTRACTING APPLICATION

#### **CONTRACTORS / LICENSURE APPLICANTS**

The Dane County Department of Waste & Renewables requires all contractors to be pre-qualified as a best value contractor with the County prior to being awarded a contract. In addition, the County pre-qualifies potential contractors and sub-contractors who wish to work on County contracts. Subcontractors must become pre-qualified ten (10) days prior to commencing work under any Dane County Waste & Renewables Contract. Potential subcontractors are urged to become pre-qualified as early as possible. This document shall be completed, properly executed, along with the necessary attachments and additional information that the County requires for the protection and welfare of the public in the performance of a County contract.

Contractors or subcontractors of any tier who attain pre-qualification status will retain that status for a period of two (2) years from the date of qualification. Contractors shall notify the Dane County Department of Waste & Renewables within fifteen (15) days of any changes to its business or operations that are relevant to the pre-qualification application. Failure to do so could result in suspension, revocation of the contractor's pre-qualification, debarment from County contracts for up to three (3) years and / or other sanctions available under the law.

No contracts will be awarded for construction work performed on Dane County projects unless the contractor is currently approved as a Wisconsin Trade Trainer or has applied for approval as an Apprenticeship Trade Trainer to the Wisconsin Department of Workforce Development and agrees to an acceptable apprenticeship program. If you are not currently approved as a Wisconsin Trade Trainer, or have not applied for approval as an Apprenticeship Trade Trainer, please contact the Department of Workforce Development - Bureau of Apprenticeship Standards at 608/266-3133 or visit their web site at: <a href="dwd.wisconsin.gov/apprenticeship/">dwd.wisconsin.gov/apprenticeship/</a>.

#### **EXEMPTIONS**

- Contractors who employ less than five (5) apprenticeable trade workers are not required to pre-qualify.
- Contractors performing work that does not apply to an apprenticeable trade, as outlined in Appendix A.
- The contractor / subcontractor provides sufficient documentation to demonstrate one or more of the following:
  - o apprentices are not available in a specific geographic area;
  - o the applicable apprenticeship program is unsuitable or unavailable; or
  - o there is a documented depression of the local construction market which prevents compliance.

BVCA - 1 ver. 06/12

SEC.	PROOF OF RESPONSIBILITY	CHECK IF APPLICABLE
1	Does your firm possesses all technical qualifications and resources,	
	including equipment, personnel and financial resources, necessary to	Yes: No:
	perform the work required for any project or obtain the same through	
	the use of responsible, pre-qualified subcontractors?	
2	Will your firm possess all valid, effective licenses, registrations or	X D N D
	certificates required by federal, state, county, or local law, which are	Yes: No:
	necessary for the type of work to be performed including, but not limited to, those for any type of trade work or specialty work?	
3	Will your firm meet all bonding requirements as required by applicable	Yes: No:
	law or contract specifications?	163.
4	Will your firm meet all insurance requirements as required by	Yes: No: No:
	applicable law or specifications, including general liability insurance,	
	workers compensation insurance and unemployment insurance	
	requirements?	
5	Will your firm maintain a substance abuse policy for employees hired	Yes: No:
	for public works contracts that comply with Wis. Stats. Sec. 103.503?	
6	Does your firm acknowledge that it must pay all craft employees on	Yes: No:
	public works projects the wage rates and benefits required under	
7	Section 66.0903 of the Wisconsin Statutes?  Will your firm fully abide by the equal opportunity and affirmative	Yes: No: No
/	action requirements of all applicable laws, including County	Yes: No:
	ordinances?	
8	In the past three (3) years, has your firm had control or has another	Yes: No: N
	corporation, partnership or other business entity operating in the	If Yes, attach details.
	construction industry controlled it? If so, please attach a statement	,
	explaining the nature of the firm relationship?	
9	In the past three (3) years, has your firm had any type of business,	Yes: No:
	contracting or trade license, certification or registration revoked or	If Yes, attach details.
1.0	suspended?	
10	In the past three (3) years, has your firm been debarred by any federal,	Yes: No:
11	state or local government agency?  In the past three (3) years, has your firm defaulted or failed to complete	If Yes, attach details.  Yes: No:
11	any contract?	If Yes, attach details.
12	In the past three (3) years, has your firm committed a willful violation	Yes: No: No:
12	of federal, state or local government safety laws as determined by a	If Yes, attach details.
	final decision of a court or government agency authority.	11 103, 404011 3044113
13	In the past three (3) years, has your firm been in violation of any law	Yes: No:
	relating to your contracting business where the penalty for such	
	violation resulted in the imposition of a penalty greater than \$10,000?	If Yes, attach details.
14	Is your firm Executive Order 108 pre-certified with the State of	Yes: No:
1.5	Wisconsin?	X
15	Is your firm an active Wisconsin Trade Trainer as determined by the	Yes: No:
16	Wisconsin Bureau of Apprenticeship Standards?  Is your firm exempt from being pre-qualified with Dane County?	Yes: No: N
16	is your firm exempt from being pre-quaimed with Dane County?	Yes: No: If Yes, attach reason for exemption.
17	Does your firm acknowledge that in doing work under any County	Yes: No:
	Waste & Renewables Contract, it will be required to use as	
	subcontractors only those contractors that are also pre-qualified with	
	the County or become so ten days prior to commencing work?	
18	Contractor has been in business less than one year?	Yes: No:
19	Is your firm a first time Contractor requesting a one time exemption,	Yes: No:
	but, intend to comply on all future contracts and are taking steps	
20	typical of a "good faith" effort?	<b>7</b>
20	Not applicable. My firm does not intend to work on Best Value	Yes: No:
	Contracts. Note: Best Value Contracting is required to bid on most	
	Waste & Renewable Contracts (if unclear, please call Todd Draper at 608-267-0119).	
	000-207-0117).	

BVCA - 2 ver. 03/19

#### SIGNATURE SECTION

#### REMEMBER!

RETURN ALL TO FORMS AND ATTACHMENTS, OR QUESTIONS TO:

TODD DRAPER EMAIL: DRAPER@COUNTYOFDANE.COM OFFICE: (608)267-0119, FAX: (608)267-1533

DANE COUNTY DEPARTMENT OF WASTE & RENEWABLES 1919 ALLIANT ENERGY CENTER WAY MADISON, WI 53713

BVCA - 3 ver. 03/19

#### APPENDIX A

#### APPRENTICEABLE TRADES

Bricklayer

Carpenter

Cement Mason (Concrete Finisher)

Cement Mason (Heavy Highway)

Construction Craft Laborer

**Data Communications Installer** 

Electrician

Elevator Mechanic / Technician

Environmental Systems Technician / HVAC Service Technician / HVAC Install & Service

Glazier

Heavy Equipment Operator / Operating Engineer

Insulation Worker (Heat & Frost)

Iron Worker (Assembler, Metal Buildings)

Painter / Decorator

Plasterer

Plumber

Roofer / Waterproofer

Sheet Metal Worker

Sprinkler Fitter

Steamfitter (Service & Refrigeration)

Taper & Finisher

Telecommunications (Voice, Data & Video) Installer / Technician

Tile Setter

BVCA - 4 ver. 03/19

#### INSTRUCTIONS TO BIDDERS

#### **TABLE OF CONTENTS**

1. UENERAL	1
2. DRAWINGS AND SPECIFICATIONS	1
3. INTERPRETATION	2
4. QUALIFICATIONS OF BIDDER (CONTRACTOR AND SUBCONTRACTOR)	2
5. BID GUARANTEE	3
6. WITHDRAWAL OF BIDS	
7. CONTRACT FORM	3
8. CONTRACT INTERESTS BY COUNTY PUBLIC OFFICIALS	3
9. EMERGING SMALL BUSINESS PROVISIONS	
10. METHOD OF AWARD - RESERVATIONS	
11. SECURITY FOR PERFORMANCE AND PAYMENTS	6
12. TAXES	6
13. SUBMISSION OF BIDS	
14. SUBCONTRACTOR LISTING	
15. ALTERNATE BIDS	7
16. INFORMATIONAL BIDS	
17. UNIT PRICES	
18. COMMENCEMENT AND COMPLETION	
19. WORK BY OWNER	
20. SPECIAL HAZARDS COVERAGE	9
FORM A	10
FORM B	
FORM C	12
FORM D	13

#### 1. GENERAL

CENEDAL

- A. Before submitting Bid, bidder shall thoroughly examine all Construction Documents. Successful Bidder shall be required to provide all the Work that is shown on Drawings, set forth in Specifications, or reasonably implied as necessary to complete Contract for this project.
- B. Bidder shall visit site to become acquainted with adjacent areas, means of approach to site, conditions of actual site and facilities for delivering, storing, placing, and handling of materials and equipment.
- C. Pre-bid meeting is scheduled on Wednesday, March 27, 2019 at 1 p.m. at Dane County Landfill Site No. 1, starting at the Generator Building. Attendance by all bidders is optional, however bidders and subcontractors are strongly encouraged to attend.
- D. Failure to visit site or failure to examine any and all Construction Documents will in no way relieve successful Bidder from necessity of furnishing any necessary materials or equipment, or performing any work, that may be required to complete the Work in accordance with Drawings and Specifications. Neglect of above requirements will not be accepted as reason for delay in the Work or additional compensation.

#### 2. DRAWINGS AND SPECIFICATIONS

A. Drawings and Specifications that form part of this Contract, as stated in Article 1 of General Conditions of Contact, are enumerated in Document Index of these Construction Documents.

B. Complete sets of Drawings and Specifications for all trades will be available to all Bidders, irrespective of category of work to be bid on, in order that all Bidders may be familiar with work of other trades as they affect their bid.

#### 3. INTERPRETATION

- A. No verbal explanation or instructions will be given in regard to meaning of Drawings or Specifications before Bid Due Date. Bidders shall bring inadequacies, omissions or conflicts to Owner or Architect / Engineer's attention at least ten (10) calendar days before Bid Due Date. Prompt clarification will be available to all bidders by Addendum.
- B. Failure to so request clarification or interpretation of Drawings and Specifications will not relieve successful Bidder of responsibility. Signing of Contract will be considered as implicitly denoting that Contractor has thorough understanding of scope of the Work and comprehension of Construction Documents.
- C. Owner or Architect / Engineer will not be responsible for verbal instructions.

#### 4. QUALIFICATIONS OF BIDDER (CONTRACTOR AND SUBCONTRACTOR)

- A. Before award of Contract can be approved, Owner shall be satisfied that Bidder involved meets following requirements:
  - 1. Has completed at least one (1) project of at least fifty percent (50%) of size or value of Division of work being bid and type of work completed is similar to that being bid. If greater magnitude of experience is deemed necessary, other than size or value of work, such requirements will be described in appropriate section of Specifications.
  - 2. Maintains permanent place of business.
  - 3. Can be bonded for terms of proposed Contract.
  - 4. Has record of satisfactorily completing past projects. Criteria which will be considered in determining satisfactory completion of projects by bidder will include:
    - a. Completed contracts in accordance with drawings and specifications.
    - b. Diligently pursued execution of work and completed contracts according to established time schedule unless Owner grants extensions.
    - c. Fulfilled guarantee requirements of construction documents.
    - d. Is not presently on ineligible list maintained by County's Department of Administration for noncompliance with equal employment opportunities and affirmative action requirements.
    - e. Authorized to conduct business in Wisconsin. By submitting Bid, bidder warrants that it has: complied with all necessary requirements to do business in State of Wisconsin; that persons executing contract on its behalf are authorized to do so; and, if corporation, that name and address of bidder's registered agent are as set forth in Contract. Bidder shall notify Owner immediately, in writing, of any change in its registered agent, their address, and bidder's legal status. For partnership, term "registered agent" shall mean general partner.
- B. County's Waste & Renewables Project Manager will make such investigations as are deemed necessary to determine ability of bidder to perform the Work, and bidder shall furnish to County's Waste & Renewables Project Manager or designee all such information and data for this purpose as County's Waste & Renewables Project Manager may request. Owner reserves right to reject Bid if evidence submitted by, or investigation of, bidder fails to satisfy

Owner that bidder is responsible and qualified to carry out obligations of Contract and to complete the Work contemplated therein.

#### 5. BID GUARANTEE

- A. Bank certified check, cashier's check or Bid Bond, payable to County in amount not less than five percent (5%) of maximum bid, shall accompany each Bid as guarantee that if Bid is accepted, Bidder will execute and return proposed Contract and Performance and Payment Bonds within ten (10) business days after being notified of acceptance of Bid. Company issuing bonds must be licensed to do business in Wisconsin.
- B. Any bid, which is not accompanied by bid guarantee, will be considered "No Bid" and will not be read at Bid Due Date.
- C. If successful Bidder so delivers Contract, Certificate of Insurance, and Performance and Payment Bonds, check will be returned to Bidder. In case Bidder fails to deliver such Contract, insurance, and bond, amount of bid guarantee will be forfeited to County as liquidated damages.
- D. All checks tendered as bid guarantee, except those of three (3) lowest qualified, responsible bidders, will be returned to their makers within three (3) business days after Bid Due Date. All such retained checks will be returned immediately upon signing of Contract and Performance and Payment Bonds by successful Bidder.

#### 6. WITHDRAWAL OF BIDS

- A. Bids may be withdrawn by written request received from bidder or authorized representative thereof prior to time fixed for Bid Due Date, without prejudice to right of bidder to file new Bid. Withdrawn Bids will be returned unopened. Negligence on part of bidder in preparing their Bid confers no right for withdrawal of Bid after it has been opened.
- B. No Bid may be withdrawn for period of sixty (60) calendar days after Bid Due Date.
- C. If Bid contains error, omission or mistake, bidder may limit liability to amount of bidder's guarantee by giving written Notice of Intent not to execute Contract to Owner within seventy-two (72) hours of Bid Due Date.

#### 7. CONTRACT FORM

A. Sample copy of contract that successful Bidder will be required to enter into is included in these Construction Documents and bidders are required to familiarize themselves with all conditions contained therein.

#### 8. CONTRACT INTERESTS BY COUNTY PUBLIC OFFICIALS

A. In accordance with Wisconsin Statute 946.13, county official may not bid for or enter into any contract involving receipts or disbursements of more than \$15,000.00 in a year, in which they have private pecuniary interest, direct or indirect if at same time they are authorized to take official action with respect to making of this Contract. Any contract entered into in violation of this Statute is void and County incurs no liability thereon. This subsection does not affect application and enforcement of Wisconsin Statute 946.13 by state prosecutors in criminal courts of this state.

#### 9. EMERGING SMALL BUSINESS PROVISIONS

- A. Emerging Small Business Definition. For purposes of this provision, ESB is defined as:
  - 1. Independent business concern that has been in business minimum of one year;
  - 2. Business located in State of Wisconsin;
  - 3. Business comprised of less than twenty-five (25) employees;
  - 4. Business must not have gross sales in excess of three million dollars (\$3,000,000.00) over past three years; and
  - 5. Business does not have history of failing to complete projects.
- B. Emerging Small Business (ESB) Involvement. Bidder shall make good faith effort to award minimum of ten percent (10%) of the Work to ESBs. Bidder shall submit report to Dane County Contract Compliance Officer within ten (10) business days of Bid Due Date demonstrating such efforts. Good faith efforts means significant contact with ESBs for purposes of soliciting bids from them. Failure to make or demonstrate good faith efforts will be grounds for disqualification.
- C. **Emerging Small Business Report.** Emerging Small Business Enterprise Report is to be submitted by Bidder in separate envelope marked "Emerging Small Business Report". This report is due by 2:00 p.m. following specified ten (10) business days after Bid Due Date. Bidder who fails to submit Emerging Small Business Report shall be deemed not responsive.
- D. **ESB Goal.** Goal of this project is ten percent (10%) ESB participation. ESB utilizations are shown as percentage of total Bid. If Bidder meets or exceeds specified goal, Bidder is only required to submit Form A Certification, and Form B Involvement. Goal shall be met if Bidder qualifies as ESB.
- E. **Report Contents.** Following award of Contract, Bidder shall submit copies of executed contracts for all Emerging Small Businesses. Emerging Small Business Report shall consist of these:
  - 1. Form A Certification;
  - 2. Form B Involvement;
  - 3. Form C Contacts;
  - 4. Form D Certification Statement (if appropriate); and
  - 5. Supportive documentation (i.e., copies of correspondence, telephone logs, copies of advertisements).
- F. ESB Listing. Bidders may solicit bids from this ESB listing: pdf.countyofdane.com/commissions/2013-2015\_Targeted\_Business\_Directory.pdf.
- G. **ESB Certification.** All contractors, subcontractors and suppliers seeking ESB certification must complete and submit Emerging Small Business Report to Dane County Contract Compliance Program.
- H. **Certification Statement.** If ESB firm has not been certified by County as ESB prior to submittal of this Bid, ESB Report cannot be used to fulfill ESB goal for this project unless firm provides "Form D Certification Statement". Certification statement must be completed and signed by ESB firm.

I. Questions. Questions concerning Emerging Small Business provisions shall be directed to:

Dane County Contract Compliance Officer City-County Building, Room 421 210 Martin Luther King, Jr. Blvd. Madison, WI 53703 608/266-5623

- J. Substituting ESBs. In event of any significant changes in subcontract arrangements or if need arises to substitute ESBs, Bidder shall report such proposed changes to Contract Compliance Officer to making any official changes and request authorization to substitute ESB firm. Bidder further agrees to make every possible effort to replace ESB firm with another qualified ESB firm.
- K. **Good Faith Efforts.** Good faith efforts can be demonstrated by meeting all of these obligations:
  - 1. Selecting portions of the Work to be performed by ESBs in order to increase likelihood of meeting ESB goal including, where appropriate, breaking down Contract into smaller units to facilitate ESB participation.
  - 2. Advertising in general circulation, trade associations and women / minority focus media concerning subcontracting opportunities.
  - 3. Providing written notices to reasonable number of specific ESBs that their interest in Contract was being solicited in sufficient time to allow ESBs to participate effectively.
  - 4. Following up on initial solicitations of interest by contacting ESBs within five (5) business days prior to Bid Due Date to determine with certainty whether ESB were interested, to allow ESBs to prepare bids.
  - 5. Providing interested ESB with adequate information about Drawings, Specifications and requirements of Contract.
  - 6. Using services of available minority, women and small business organizations and other organizations that provide assistance in recruitment of MBEs / WBEs / ESBs.
  - 7. Negotiating in good faith with interested ESBs, not rejecting ESBs as unqualified without sound reason based on thorough investigation of their capabilities.
  - 8. Submitting required project reports and accompanying documents to County's Contract Compliance Officer within twenty-four (24) hours after Bid Due Date.
- L. **Appeals Disqualification of Bid.** Bidder who is disqualified may appeal to Public Works & Transportation Committee and Equal Opportunity Commission.

#### 10. METHOD OF AWARD - RESERVATIONS

- A. Following will be basis of award of Contract, providing cost does not exceed amount of funds then estimated by County as available to finance Contract(s):
  - 1. Lowest dollar amount submitted by qualified responsible bidder on Base Bid for all work comprising project, combined with such additive Owner accepted alternates.

- 2. Owner reserves right to reject all bids or any bid, to waive any informality in any bid, and to accept any bid that will best serve interests of County.
- 3. Unit Prices and Informational Bids will not be considered in establishing low bidder.

#### 11. SECURITY FOR PERFORMANCE AND PAYMENTS

- A. Simultaneous with delivery of signed Contract, Bidder shall be required to furnish Performance and Payment Bonds as specified in Article 29 of General Conditions of Contract, "Contract Security". Surety Company shall be licensed to do business in Wisconsin. Performance and Payment Bonds must be dated same date or subsequent to date of Contract. Performance and Payment Bonds must emulate information in Sample Performance and Payment Bonds in Construction Documents.
- B. Provide certified copy of power of attorney from Surety Company showing that agent who signs Bond has power of attorney to sign for Surety Company. Secretary or Assistant Secretary of company must sign this certification, not attorney-in-fact. Certification must bear same or later date as Bond. Power of Attorney must emulate model power of attorney information detailed in Sample Performance and Payment Bonds.
- C. If Bidder is partnership or joint venture, State certified list, providing names of individuals constituting partnership or joint venture must be furnished. Contract itself may be signed by one partner of partnership, or one partner of each firm comprising joint venture, but Performance and Payment Bonds must be signed by all partners.
- D. If Bidder is corporation, it is necessary that current certified copy of resolution or other official act of directors of corporation be submitted showing that person who signs Contract is authorized to sign contracts for corporation. It is also necessary that corporate seal be affixed to resolution, contract, and performance and payment bonds. If your corporation has no seal, it is required that above documents include statement or notation to effect that corporation has no seal.

#### 12. TAXES

- A. Wisconsin Statute 77.54 (9m) allows building materials that become part of local unit government facilities to be exempt from sales & use tax. Vendors & materials suppliers may not charge Bidders sales & use tax on these purchases. This does not include highways, streets or roads. Any other Sales, Consumer, Use & other similar taxes or fees required by law shall be included in Bid.
- B. In accordance with Wisconsin Statute 71.80(16)(a), successful nonresident bidder, whether incorporated or not, and not otherwise regularly engaged in business in this state, shall file surety bond with State of Wisconsin Department of Revenue payable to Department of Revenue, to guarantee payment of income taxes, required unemployment compensation contributions, sales and use taxes and income taxes withheld from wages of employees, together with any penalties and interest thereon. Amount of bond shall be three percent (3%) of Contract or subcontract price on all contracts of \$50,000 or more.

#### 13. SUBMISSION OF BIDS

A. All Bids shall be submitted on standard Bid Form bound herein and only Bids that are made on this Bid Form will be considered. Entire Bid Form and other supporting documents, if any, shall be removed or copied from Construction Documents, filled out, and submitted in manner specified hereinafter. Submit completed Bid Bond with Bid as well.

- B. No bids for any subdivision or any sub-classification of this Work, except as indicated, will be accepted. Any conditional Bid, amendment to Bid Form or appended item thereto, or inclusion of any correspondence, written or printed matter, or details of any nature other than that specifically called for, which would alter any essential provision of Construction Documents, or require consideration of unsolicited material or data in determining award of Contract, will disqualify Bid. Telecommunication alterations to Bid will not be accepted.
- C. Bidders must submit single Bid for all the Work.
- D. Bid amounts shall be inserted in words and in figures in spaces provided on Bid Form; in case of conflict, written word amounts will govern.
- E. Addenda issued after Bid Letting shall become part of Construction Documents. Bidders shall acknowledge receipt of such addenda in appropriate space provided on Bid Form. Bid may be rejected if receipt of any particular addendum applicable to award of Contract has not been acknowledged on Bid Form.
- F. Bids shall be signed, placed in envelope, sealed and delivered before due time to place designated in Invitation to Bid, and identified with project name, bid number, location, category of work being bid upon, Bid Due Date, name and address of bidder.
- G. Bidder shall be responsible for sealed Bid being delivered to place designated for Bid Due Date on or before date and time specified. Bids received after time of closing will be rejected and returned to bidder unopened.
- H. Bid will be considered invalid and will be rejected if bidder has not signed it.
- I. Faxed or emailed Bids will not be accepted.
- J. Bidder's organization shall submit completed with Bid, Fair Labor Practices Certification form, included in these Construction Documents.

#### 14. SUBCONTRACTOR LISTING

A. Bidders shall be required to submit list of major subcontractors for General Construction, Plumbing, HVAC, and Electrical work proposed for this project to include committed prices for each subcontractor. List shall be placed in separate sealed envelope that must be clearly identified as "Major Subcontractor List", for named project and name of Bidder submitting it. County must receive envelope no later than date by which successful Bidder is required to submit his or her signed Contract, as established in Construction Documents.

#### 15. ALTERNATE BIDS

- A. Bidder shall carefully read requests for Alternate Bids, and thoroughly examine Drawings and Specifications to determine extent various changes and conditions will affect Bid.
- B. Space is provided in Bid Form for requested Alternate Bids. Failure to submit bid for any requested Alternate Bids may result in rejection of entire Bid.
- C. Bidder shall state amount to be added / subtracted to Base Bid for providing alternates, including all incidentals, omissions, additions, and adjustments as may be necessary or required by such changes. If there is no difference in price, Bidder shall state, "No Change".
- D. Descriptions of requested Alternate Bids are as set forth in Construction Documents.

#### 16. INFORMATIONAL BIDS

A. Not Applicable.

#### 17. UNIT PRICES

- A. Provide unit prices where requested on Bid Form. Unit prices will include all costs for materials, labor, insurance, taxes, overhead and profit necessary to perform specified work. Estimated quantities are approximate only. Payment will be based upon actual quantities placed, provided or installed. Failure to provide requested unit prices may result in rejection of entire Bid.
- B. Owner reserves right to accept or reject any unit prices as given in Bid.
- C. Bidder shall refer to Bid Form and applicable specification section to determine basis of unit measure and detailed information related to each unit price item requested.

#### 18. COMMENCEMENT AND COMPLETION

- A. Successful Bidder shall commence work when schedule and weather permit, but no later than stated in Bid Form. Contractor shall pursue the Work regularly and continuously at reasonable rate to insure completion of the Work within time stated in Bid.
- B. Should it be found impossible to complete the Work on or before time specified for completion, written request may be submitted for extension of time setting forth reasons believed to justify granting of such request. Written extension requests shall be submitted to the County's Waste and Renewables Project Manager. Refer to Article 20 of General Conditions of Contract, titled "Time for Completion".

#### 19. WORK BY OWNER

- A. This work will be accomplished by Owner or will be let under separate contracts and will not be included under this Contract:
  - 1. Owner shall provide erosion control permitting, marking of private utility locations, construction oversight, and soil laboratory testing services.
  - 2. Owner shall procure blower (Manufacturer: Twin City Fan & Blower, Model #:TBNA 30508, or equivalent). Contractor to unload, install, commission, start-up, and test blower.
  - 3. Owner shall provide the following regarding controls:
    - a) Endress & Hauser pressure transmitter PMP71 series (installed by Contractor),
    - b) Endress & Hauser thermal flow meter 65I series (installed by Contractor),
    - c) Power Flex 525 Variable Frequency Drive (installed by Contractor)
    - d) 48" H x 38" outdoor control panel and components (installed by Contractor),
    - e) Allen Bradley Compact Logix PLC rack (installed by Contractor),
    - f) Allen Bradley PanelView plus HMI (installed by Contractor), and
    - g) Assistance during start-up and testing of system.

#### 20. SPECIAL HAZARDS COVERAGE

A. Not Applicable.

#### FORM A

## DANE COUNTY EMERGING SMALL BUSINESS REPORT - CERTIFICATION

In accordance with General Conditions of Contract, submit this Emerging Small Business Report within ten (10) days after Bid Due Date.

PROJECT NAME:				
BID NO.:	BID DUE DATE:			
BIDDER INFORMATION				
COMPANY NAME:				
ADDRESS:				
CONTACT PERSON:				
EMAIL ADDRESS:				

FORM B	
DANE COUNTY EMERGING SMALL BUSINESS REPORT	Page of (Copy this Form as necessary to provide complete information) $\Gamma$ - INVOLVEMENT
COMPANY NAME:	
PROJECT NAME:	
BID NO.:	BID DUE DATE:
ESB NAME:	

ESB NAME:

CONTACT PERSON:

ADDRESS:

PHONE NO & EMAIL.:

Indicate percentage of financial commitment to this ESB:

ESB NAME:

CONTACT PERSON:

ADDRESS:

PHONE NO & EMAIL.:

PHONE NO & EMAIL.:

#### FORM C

ъ	c
Page	ot

### DANE COUNTY (Copy this Form as necessary to provide complete information) **EMERGING SMALL BUSINESS REPORT - CONTACTS** COMPANY NAME: PROJECT NAME: BID NO.: \_\_\_\_\_ BID DUE DATE: \_\_\_\_ DID ACC-PERSON ESB FIRM NAME CONTACTED DATE EPT BID? ESB REASON FOR CONTACTED BID? REJECTION 3) \_\_\_\_\_\_

#### FORM D

## DANE COUNTY EMERGING SMALL BUSINESS REPORT - CERTIFICATION STATEMENT

I,	,	of
Name	Title	
Company	certify to best of m	ny knowledge and
belief that this business meets Emerging	g Small Business definition as indicated i	n Article 9 and
that information contained in this Emer	rging Small Business Report is true and co	orrect.
Bidder's Signature	Date	

#### **BID FORM**

BID NO.: 319006

PROJECT: PERIMETER GAS MITIGATION SYSTEM

DANE COUNTY LANDFILL SITE NO. 1

TO: DANE COUNTY DEPARTMENT OF WASTE & RENEWABLES

1919 ALLIANT ENERGY CENTER WAY

MADISON, WISCONSIN 53713

NOTE: WISCONSIN STATUTE 77.54 (9M) ALLOWS FOR NO SALES & USE TAX ON THE PURCHASE OF MATERIALS FOR COUNTY PUBLIC WORKS PROJECTS.

#### **BASE BID - UNIT PRICING:**

Dane County is inviting Bids for construction services for a standalone perimeter gas mitigation system consisting of 900 LF of header pipe, gas control wells, gas probes, and supplemental control instrumentation. The undersigned, having examined the site where the Work is to be executed and having become familiar with local conditions affecting the cost of the Work and having carefully examined the Drawings and Specifications, all other Construction Documents and Addenda thereto prepared by Dane County Department of Waste & Renewables hereby agrees to provide all labor, materials, equipment and services necessary for the complete and satisfactory execution of the entire Work, as specified in the Construction Documents, for the Base Bid unit pricing as follows:

Item No.	Description	Unit	Quantity	Unit Price	Total Price
1	Mobilization/Demobilization	LS	1		
2	Site preparation and erosion control installation	LS	1		
3		Gas We	ells		
3.1	Gas well drilling and installation (borehole depth)	VF	274		
3.2	Wellheads (wellhead, flex hose, vault with cover and chain/lock)	EA	10		
4		Pipin	g		
4.1	4" HDPE lateral piping, 6" HDPE header piping, condensate drains, valves	LS	1		
5		Gas Pro	bes		
5.1	Gas probe drilling and installation (borehole depth)	VF	126		
5.2	Methane sensors (MSA Ultima X Series)	EA	5		
6	Blower				
6.1	Blower and control panel installation, wiring, sensors, bumper posts.	LS	1		
7		Other	r		
7.1	Site Restoration	LS	1		

	Total: \$		
	Numeric Price		•
	_		
Written Price	and,	/100	Dollars
written Price			
ALTERNATE BID 1 - UNIT PRICING:			
	line and unleading waste metarials that me		
Unit price for separating, stockpiling, loading, haud be encountered during excavation, trenching, or dri		ıy	
be encountered during excavation, treneming, of di-	nning per Drawings and Specifications.		
Cost for waste material handling =		/ton	
	N		
	Numeric Price (circle: Add or Deduct)		
Written price (circle:	Add or Deduct)		
ALTERNATE BID 2 - UNIT PRICING:			
Unit price for ripping, excavating, and offsite dispo	osal of encountered competent bedrock to		
required depths and locations per Drawings and Sp			
required depend and recurrent per 214 miles and 5p			
Cost for rock excavation =		<u>/ton</u>	
	Numeric Price (circle: Add or Deduct)		
	Numeric Price (circle: Plat of Beddet)		
Written price (circle:	Add or Deduct)		
Receipt of the following addenda and inclusion of	their provisions in this Bid is hereby		
acknowledged:			
5			
Addendum No(s) through _			
Dated			
Dana County Department of Wests & Benevichles	must have this project completed by June	20	
Dane County Department of Waste & Renewables 2019. Assuming this Work can be started by May			
• • •	o, 2019, what dates can you commence and	u	
complete this job?			
Commencement Date:	Completion Date: _		
	(final, not substantial)		•

(Name of Corporation, Partnership or Person submitting Bid) Select one of the following: 1. A corporation organized and existing under the laws of the State of , or 2. A partnership consisting of , or 3. A person conducting business as \_\_\_\_\_; Of the City, Village, or Town of \_\_\_\_\_\_ of the State of \_\_\_\_\_. I have examined and carefully prepared this Bid from the associated Construction Documents and have checked the same in detail before submitting this Bid; that I have full authority to make such statements and submit this Bid in (its) (their) (my) behalf; and that the said statements are true and correct. In signing this Bid, we also certify that we have not, either directly or indirectly, entered into any agreement or participated in any collusion or otherwise taken any action in restraint of free competition; that no attempt has been made to induce any other person or firm to submit or not to submit a Bid; that this Bid has been independently arrived at without collusion with any other bidder, competitor, or potential competitor; that this Bid has not been knowingly disclosed prior to the Bids Due Date to another bidder or competitor; that the above statement is accurate under penalty of perjury. The undersigned further agrees to honor the Base Bid and the Alternate Bid(s) for sixty (60) calendar days from date of Award of Contract. SIGNATURE: \_\_\_\_\_\_(Bid is invalid without signature) Print Name: \_\_\_\_\_ Date: \_\_\_\_\_ Address: Telephone No.: \_\_\_\_\_ Fax No.: \_\_\_\_ Email Address:

I hereby certify that all statements herein are made on behalf of:

Contact Person:

### THIS PAGE IS FOR BIDDERS' REFERENCE AND NEED NOT BE SUBMITTED WITH BID FORM.

BID CHECK LIST:			
These items <b>must</b> be included with Bid:			
☐ Bid Form	☐ Bid Bond	☐ Fair Labor Practices Certification	

#### BIDDERS SHOULD BE AWARE OF THE FOLLOWING:

#### DANE COUNTY VENDOR REGISTRATION PROGRAM

All bidders are strongly encouraged to be a registered vendor with Dane County. Registering allows vendors an opportunity to receive notifications for RFBs & RFPs issued by the County and provides the County with up-to-date company contact information. Complete a new form or renewal online at:

danepurchasing.com/Account/Login?

#### DANE COUNTY BEST VALUE CONTRACTING PRE-QUALIFICATION

Contractors must be pre-qualified as a Best Value Contractor with Dane County Department of Waste & Renewables before the award of contract. Obtain a *Best Value Contracting Application* by calling 608/266-4018 or complete one online at: countyofdane.com/pwht/BVC\_Application.aspx

#### FAIR LABOR PRACTICES CERTIFICATION

The undersigned, for and on behalf of the BIDDER, APPLICANT or PROPOSER named herein, certifies as follows:

A. That he or she is an officer or duly authorized agent of the above-referenced BIDDER,

	APPLICANT or PROPOSER, which has a submitted a bid, a contract or agreement with the county of Dane.	pplication or proposal for a
B.	That BIDDER, APPLICANT or PROPOSER has (check one)	:
	not been found by the National Labor Relations Boar Employment Relations Commission ("WERC") to have viola regarding labor standards or relations in the seven years prior Certification.	ted any statute or regulation
	been found by the National Labor Relations Board (Employment Relations Commission ("WERC") to have viola regarding labor standards or relations in the seven years prior Certification.	ted any statute or regulation
Offi	cer or Authorized Agent Signature	Date
Prin	ted or Typed Name and Title	

**NOTE:** You can find information regarding the violations described above at: <a href="www.nlrb.gov">www.nlrb.gov</a> and <a href="www.nlrb.gov">werc.wi.gov</a>.

For reference, Dane County Ordinance 25.09 is as follows:

Printed or Typed Business Name

(1) BIDDER RESPONSIBILITY. (a) Any bid, application or proposal for any contract with the county, including public works contracts regulated under chapter 40, shall include a certification indicating whether the bidder has been found by the National Labor Relations Board (NLRB) or the Wisconsin Employment Relations Committee (WERC) to have violated any statute or regulation regarding labor standards or relations within the last seven years. The Controller shall investigate any such finding and make a recommendation to the committee, which shall determine whether the conduct resulting in the finding affects the bidder's responsibility to perform the contract.

If you indicated that the NLRB or WERC have found you to have such a violation, you must include copies of any relevant information regarding such violation with your proposal, bid or application.

Include this completed Certification with your bid, application or proposal.

#### **COUNTY OF DANE**

#### WASTE & RENEWABLES CONSTRUCTION CONTRACT

Contract No.	Bid No. <u>319006</u>	
Authority: 2019 RES		
both parties have affixed the		by which authorized representatives of the County of Dane (hereafter referred (hereafter, "CONTRACTOR"),
and		
	WITNESSETI	HÍ:
Energy Center Way, Madiso	n, WI 53713, desires to have	enewables Director, 1919 Alliant CONTRACTOR provide Perimeter
	ine County Landfill Site No. 1	1 [including Alternate Bid[s] X and/or
Y ("the Project"); and		
WHEREAS, CONTRACTO		ble and willing to construct the Project,
in accordance with the Const		ble and wining to construct the Project,
in accordance with the Const	ruction Documents,	
NOW, THEREFORE, in co	onsideration of the above prer	mises and the mutual covenants of the
		which is acknowledged by each party
	NTRACTOR do agree as foll	
1 CONTRACTOR		d D : 4 1 4
		the Project and at the
contractor s own prop	dence Johan incurrence and of	h all materials, supplies, machinery,
		ther accessories and services necessary and prices stated in the Bid Form,
		de all maps, plats, plans, and other
		f, and the specifications therefore as
		e Architect / Engineer"), and as
		f which are made a part hereof and
collectively evidence and con		1 which are made a part hereof and
2. COUNTY agrees to pay t	he CONTRACTOR in curren	at funds for the performance of the
		in the General Conditions of Contract,
		Article 25 entitled, "Payments to
Contractor" of the General C		<del>-</del>
<b>3.</b> During the term of this Co	ontract, CONTRACTOR agre	ees to take affirmative action to ensure
		grees in accordance with Wisconsin

Statute 111.321 and Chapter 19 of the Dane County Code of Ordinances not to discriminate on

orientation, national origin, cultural differences, ancestry, physical appearance, arrest record or conviction record, military participation or membership in the national guard, state defense force or any other reserve component of the military forces of the United States, or political beliefs. Such equal opportunity shall include, but not be limited to, the following: employment,

the basis of age, race, ethnicity, religion, color, gender, disability, marital status, sexual

upgrading, demotion, transfer, recruitment, advertising, layoff, termination, training, rates of pay, and any other form of compensation. CONTRACTOR agrees to post in conspicuous places, available to all employees and applicants for employment, notices setting forth the provisions of this paragraph.

- 4. CONTRACTOR shall file an Affirmative Action Plan with the Dane County Contract Compliance Officer in accord with Chapter 19 of the Dane County Code of Ordinances. CONTRACTOR must file such plan within fifteen (15) business days of the effective date of this Contract. During the term of this Contract CONTRACTOR shall also provide copies of all announcements of employment opportunities to COUNTY'S Contract Compliance Office, and shall report annually the number of persons, by race, ethnicity, gender, and disability status, which apply for employment and, similarly classified, the number hired and number rejected.
- **5.** During the term of this Contract, all solicitations for employment placed on CONTRACTOR'S behalf shall include a statement to the effect that CONTRACTOR is an "Equal Opportunity Employer".
- **6.** CONTRACTOR agrees to furnish all information and reports required by COUNTY'S Contract Compliance Officer as the same relate to affirmative action and nondiscrimination, which may include any books, records, or accounts deemed appropriate to determine compliance with Chapter 19, Dane County Code of Ordinances, and the provisions of this Contract.
- 7. This Contract is intended to be a Contract solely between the parties hereto and for their benefit only. No part of this Contract shall be construed to add to, supplement, amend, abridge or repeal existing rights, benefits or privileges of any third party or parties including, but not limited to, employees of either of the parties.
- **8.** The entire agreement of the parties is contained herein and this Contract supersedes any and all oral agreements and negotiations between the parties relating to the subject matter hereof. The parties expressly agree that the express terms of this Contract shall not be amended in any fashion except in writing, executed by both parties.
- 9. CONTRACTOR must be pre-qualified as a Best Value Contractor with Dane County Department of Waste & Renewables before award of Contract. Subcontractors must be pre-qualified ten (10) business days prior to commencing Work under this Contract.

**IN WITNESS WHEREOF**, COUNTY and CONTRACTOR, by their respective authorized agents, have caused this Contract and its Schedules to be executed, effective as of the date by which all parties hereto have affixed their respective signatures, as indicated below.

* * * * * *	
FOR CONTRACTOR:	
Signature	Date
Printed or Typed Name and Title	
Signature	Date
Printed or Typed Name and Title	
NOTE: If CONTRACTOR is a corporation, Secretary should attered Regulations, unincorporated entities are required to provide either Employer Number in order to receive payment for services render	their Social Security or
This Contract is not valid or effectual for any purpose until approved designated below, and no work is authorized until the CONTRAC proceed by COUNTY'S Waste & Renewables Director.	
FOR COUNTY:	
Joseph/T. Parisi, County Executive	Date
Scott McDonell, County Clerk	Date

#### **Bid Bond**

CONTRACTOR: (Name, legal status and address)	SURETY: (Name, legal status and principal place of business)	

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

#### OWNER:

(Name, legal status and address)

#### BOND AMOUNT:

#### PROJECT:

(Name, location or address, and Project number, if any)

The Contractor and Surety are bound to the Owner in the amount set forth above, for the payment of which the Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, as provided herein. The conditions of this Bond are such that if the Owner accepts the bid of the Contractor within the time specified in the bid documents, or within such time period as may be agreed to by the Owner and Contractor, and the Contractor either (1) enters into a contract with the Owner in accordance with the terms of such bid, and gives such bond or bonds as may be specified in the bidding or Contract Documents, with a surety admitted in the jurisdiction of the Project and otherwise acceptable to the Owner, for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof, or (2) pays to the Owner the difference, not to exceed the amount of this Bond, between the amount specified in said bid and such larger amount for which the Owner may in good faith contract with another party to perform the work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect. The Surety hereby waives any notice of an agreement between the Owner and Contractor to extend the time in which the Owner may accept the bid. Waiver of notice by the Surety shall not apply to any extension exceeding sixty (60) days in the aggregate beyond the time for acceptance of bids specified in the bid documents, and the Owner and Contractor shall obtain the Surety's consent for an extension beyond sixty (60) days.

If this Bond is issued in connection with a subcontractor's bid to a Contractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

When this Bond has been furnished to comply with a statutory or other legal requirement in the location of the Project, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

Signed and sealed this day of		
	(Contractor as Principal)	(Seal)
(Witness)		
	(Title)	
	(Surety)	(Seal)
(Witness)		
	(Title)	

CAUTION: You should sign an original AIA Contract Document, on which this text appears in RED. An original assures that changes will not be obscured.



#### Performance Bond


CONTRACTOR: (Name, legal status and address)	SURETY: (Name, legal status and principal place of business)	
OWNER: (Name, legal status and address)		This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.
		Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.
CONSTRUCTION CONTRACT Date:		AIA Document A312–2010 combines two separate bonds, a
Amount:		Performance Bond and a Payment Bond, into one form.
Description: (Name and location)		This is not a single combined Performance and Payment Bond.
BOND Date: (Not earlier than Construction Contract Date)		
Amount:		
Modifications to this Bond: None	☐ See Section 16	
CONTRACTOR AS PRINCIPAL	SURETY	
Company: (Corporate Seal)	Company: (Corporate Seal)	
Signature:	Signature:	
Name Nam	e	
and Title: (Any additional signatures appear on the last	and Title: t page of this Performance Bond.)	
(FOR INFORMATION ONLY—Name, addr AGENT or BROKER:	OWNER'S REPRESENTATIVE:	
	(Architect, Engineer or other party:)	

- § 1 The Contractor and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Owner for the performance of the Construction Contract, which is incorporated herein by reference.
- § 2 If the Contractor performs the Construction Contract, the Surety and the Contractor shall have no obligation under this Bond, except when applicable to participate in a conference as provided in Section 3.
- § 3 If there is no Owner Default under the Construction Contract, the Surety's obligation under this Bond shall arise after
  - .1 the Owner first provides notice to the Contractor and the Surety that the Owner is considering declaring a Contractor Default. Such notice shall indicate whether the Owner is requesting a conference among the Owner, Contractor and Surety to discuss the Contractor's performance. If the Owner does not request a conference, the Surety may, within five (5) business days after receipt of the Owner's notice, request such a conference. If the Surety timely requests a conference, the Owner shall attend. Unless the Owner agrees otherwise, any conference requested under this Section 3.1 shall be held within ten (10) business days of the Surety's receipt of the Owner's notice. If the Owner, the Contractor and the Surety agree, the Contractor shall be allowed a reasonable time to perform the Construction Contract, but such an agreement shall not waive the Owner's right, if any, subsequently to declare a Contractor Default:
  - .2 the Owner declares a Contractor Default, terminates the Construction Contract and notifies the Surety; and
  - .3 the Owner has agreed to pay the Balance of the Contract/Price in accordance with the terms of the Construction Contract to the Surety or to a contractor selected to perform the Construction Contract.
- § 4 Failure on the part of the Owner to comply with the notice requirement in Section 3.1 shall not constitute a failure to comply with a condition precedent to the Surety's obligations, or release the Surety from its obligations, except to the extent the Surety demonstrates actual prejudice.
- § 5 When the Owner has satisfied the conditions of Section 3, the Surety shall promptly and at the Surety's expense take one of the following actions:
- § 5.1 Arrange for the Contractor, with the consent of the Owner, to perform and complete the Construction Contract;
- § 5.2 Undertake to perform and complete the Construction Contract itself, through its agents or independent contractors:
- § 5.3 Obtain bids or negotiated proposals from qualified contractors acceptable to the Owner for a contract for performance and completion of the Construction Contract, arrange for a contract to be prepared for execution by the Owner and a contractor selected with the Owner's concurrence, to be secured with performance and payment bonds executed by a qualified surety equivalent to the bonds issued on the Construction Contract, and pay to the Owner the amount of damages as described in Section 7 in excess of the Balance of the Contract Price incurred by the Owner as a result of the Contractor Default; or
- § 5.4 Waive its right to perform and complete, arrange for completion, or obtain a new contractor and with reasonable promptness under the circumstances:
  - After investigation, determine the amount for which it may be liable to the Owner and, as soon as practicable after the amount is determined, make payment to the Owner; or
  - .2 Deny liability in whole or in part and notify the Owner, citing the reasons for denial.
- § 6 If the Surety does not proceed as provided in Section 5 with reasonable promptness, the Surety shall be deemed to be in default on this Bond seven days after receipt of an additional written notice from the Owner to the Surety demanding that the Surety perform its obligations under this Bond, and the Owner shall be entitled to enforce any remedy available to the Owner. If the Surety proceeds as provided in Section 5.4, and the Owner refuses the payment or the Surety has denied liability, in whole or in part, without further notice the Owner shall be entitled to enforce any remedy available to the Owner.

- § 7 If the Surety elects to act under Section 5.1, 5.2 or 5.3, then the responsibilities of the Surety to the Owner shall not be greater than those of the Contractor under the Construction Contract, and the responsibilities of the Owner to the Surety shall not be greater than those of the Owner under the Construction Contract. Subject to the commitment by the Owner to pay the Balance of the Contract Price, the Surety is obligated, without duplication, for
  - .1 the responsibilities of the Contractor for correction of defective work and completion of the Construction Contract:
  - .2 additional legal, design professional and delay costs resulting from the Contractor's Default, and resulting from the actions or failure to act of the Surety under Section 5; and
  - .3 liquidated damages, or if no liquidated damages are specified in the Construction Contract, actual damages caused by delayed performance or non-performance of the Contractor.
- § 8 If the Surety elects to act under Section 5.1, 5.3 or 5.4, the Surety's liability is limited to the amount of this Bond.
- § 9 The Surety shall not be liable to the Owner or others for obligations of the Contractor that are unrelated to the Construction Contract, and the Balance of the Contract Price shall not be reduced or set off on account of any such unrelated obligations. No right of action shall accrue on this Bond to any person or entity other than the Owner or its heirs, executors, administrators, successors and assigns.
- § 10 The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.
- § 11 Any proceeding, legal or equitable, under this Bond may be instituted in any court of competent jurisdiction in the location in which the work or part of the work is located and shall be instituted within two years after a declaration of Contractor Default or within two years after the Contractor ceased working or within two years after the Surety refuses or fails to perform its obligations under this Bond, whichever occurs first. If the provisions of this Paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.
- § 12 Notice to the Surety, the Owner or the Contractor shall be mailed or delivered to the address shown on the page on which their signature appears.
- § 13 When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

#### § 14 Definitions

- § 14.1 Balance of the Contract Price. The total amount payable by the Owner to the Contractor under the Construction Contract after all proper adjustments have been made, including allowance to the Contractor of any amounts received or to be received by the Owner in settlement of insurance or other claims for damages to which the Contractor is entitled, reduced by all valid and proper payments made to or on behalf of the Contractor under the Construction Contract.
- § 14.2 Construction Contract. The agreement between the Owner and Contractor identified on the cover page, including all Contract Documents and changes made to the agreement and the Contract Documents.
- § 14.3 Contractor Default. Failure of the Contractor, which has not been remedied or waived, to perform or otherwise to comply with a material term of the Construction Contract.
- § 14.4 Owner Default. Failure of the Owner, which has not been remedied or waived, to pay the Contractor as required under the Construction Contract or to perform and complete or comply with the other material terms of the Construction Contract.
- § 14.5 Contract Documents. All the documents that comprise the agreement between the Owner and Contractor.
- § 15 If this Bond is issued for an agreement between a Contractor and subcontractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.





#### Payment Bond

CONTRACTOR: (Name, legal status and address)	SURETY: (Name, legal status and principal place of business)	
OWNER: (Name, legal status and address)		This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.
		Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.
CONSTRUCTION CONTRACT Date:		AIA Document A312–2010 combines two separate bonds, a
Amount:		Performance Bond and a Payment Bond, into one form.
Description: (Name and location)		This is not a single combined Performance and Payment Bond.
BOND Date: (Not earlier than Construction Contract Date)		
Amount:		
Modifications to this Bond: None	☐ See Section 18	
CONTRACTOR AS PRINCIPAL	SURETY	
Company: (Corporate Seal)	Company: (Corporate Seal)	
Signature:	Signature:	
Name Nam	е	
and Title: (Any additional signatures appear on the last	and Title: t page of this Payment Bond.)	
(FOR INFORMATION ONLY—Name, addr AGENT or BROKER:	ress and telephone) OWNER'S REPRESENTATIVE: (Architect, Engineer or other party:)	


- § 1 The Contractor and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Owner to pay for labor, materials and equipment furnished for use in the performance of the Construction Contract, which is incorporated herein by reference, subject to the following terms.
- § 2 If the Contractor promptly makes payment of all sums due to Claimants, and defends, indemnifies and holds harmless the Owner from claims, demands, liens or suits by any person or entity seeking payment for labor, materials or equipment furnished for use in the performance of the Construction Contract, then the Surety and the Contractor shall have no obligation under this Bond.
- § 3 If there is no Owner Default under the Construction Contract, the Surety's obligation to the Owner under this Bond shall arise after the Owner has promptly notified the Contractor and the Surety (at the address described in Section 13) of claims, demands, liens or suits against the Owner or the Owner's property by any person or entity seeking payment for labor, materials or equipment furnished for use in the performance of the Construction Contract and tendered defense of such claims, demands, liens or suits to the Contractor and the Surety.
- § 4 When the Owner has satisfied the conditions in Section 3, the Surety shall promptly and at the Surety's expense defend, indemnify and hold harmless the Owner against a duly tendered claim, demand, lien or suit.
- § 5 The Surety's obligations to a Claimant under this Bond shall arise after the following:
- § 5.1 Claimants, who do not have a direct contract with the Contractor,
  - .1 have furnished a written notice of non-payment to the Contractor, stating with substantial accuracy the amount claimed and the name of the party to whom the materials were, or equipment was, furnished or supplied or for whom the labor was done or performed, within ninety (90) days after having last performed labor or last furnished materials or equipment included in the Claim; and
  - .2 have sent a Claim to the Surety (at the address described in Section 13).
- § 5.2 Claimants, who are employed by or have a direct contract with the Contractor, have sent a Claim to the Surety (at the address described in Section 13).
- § 6 If a notice of non-payment required by Section 5.1.1 is given by the Owner to the Contractor, that is sufficient to satisfy a Claimant's obligation to furnish a written notice of non-payment under Section 5.1.1.
- § 7 When a Claimant has satisfied the conditions of Sections 5.1 or 5.2, whichever is applicable, the Surety shall promptly and at the Surety's expense take the following actions:
- § 7.1 Send an answer to the Claimant, with a copy to the Owner, within sixty (60) days after receipt of the Claim, stating the amounts that are undisputed and the basis for challenging any amounts that are disputed; and
- § 7.2 Pay or arrange for payment of any undisputed amounts.
- § 7.3 The Surety's failure to discharge its obligations under Section 7.1 or Section 7.2 shall not be deemed to constitute a waiver of defenses the Surety or Contractor may have or acquire as to a Claim, except as to undisputed amounts for which the Surety and Claimant have reached agreement. If, however, the Surety fails to discharge its obligations under Section 7.1 or Section 7.2, the Surety shall indemnify the Claimant for the reasonable attorney's fees the Claimant incurs thereafter to recover any sums found to be due and owing to the Claimant.
- § 8 The Surety's total obligation shall not exceed the amount of this Bond, plus the amount of reasonable attorney's fees provided under Section 7.3, and the amount of this Bond shall be credited for any payments made in good faith by the Surety.
- § 9 Amounts owed by the Owner to the Contractor under the Construction Contract shall be used for the performance of the Construction Contract and to satisfy claims, if any, under any construction performance bond. By the Contractor furnishing and the Owner accepting this Bond, they agree that all funds earned by the Contractor in the performance of the Construction Contract are dedicated to satisfy obligations of the Contractor and Surety under this Bond, subject to the Owner's priority to use the funds for the completion of the work.

- § 10 The Surety shall not be liable to the Owner, Claimants or others for obligations of the Contractor that are unrelated to the Construction Contract. The Owner shall not be liable for the payment of any costs or expenses of any Claimant under this Bond, and shall have under this Bond no obligation to make payments to, or give notice on behalf of, Claimants or otherwise have any obligations to Claimants under this Bond.
- § 11 The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.
- § 12 No suit or action shall be commenced by a Claimant under this Bond other than in a court of competent jurisdiction in the state in which the project that is the subject of the Construction Contract is located or after the expiration of one year from the date (1) on which the Claimant sent a Claim to the Surety pursuant to Section 5.1.2 or 5.2, or (2) on which the last labor or service was performed by anyone or the last materials or equipment were furnished by anyone under the Construction Contract, whichever of (1) or (2) first occurs. If the provisions of this Paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.
- § 13 Notice and Claims to the Surety, the Owner or the Contractor shall be mailed or delivered to the address shown on the page on which their signature appears. Actual receipt of notice or Claims, however accomplished, shall be sufficient compliance as of the date received.
- § 14 When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.
- § 15 Upon request by any person or entity appearing to be a potential beneficiary of this Bond, the Contractor and Owner shall promptly furnish a copy of this Bond or shall permit a copy to be made.

#### § 16 Definitions

- § 16.1 Claim. A written statement by the Claimant including at a minimum:
  - .1 the name of the Claimant;
  - .2 the name of the person for whom the labor was done, or materials or equipment furnished;
  - .3 a copy of the agreement or purchase order pursuant to which labor, materials or equipment was furnished for use in the performance of the Construction Contract;
  - .4 a brief description of the labor, materials or equipment furnished;
  - .5 the date on which the Claimant last performed labor or last furnished materials or equipment for use in the performance of the Construction Contract;
  - .6 the total amount earned by the Claimant for labor, materials or equipment furnished as of the date of the Claim:
  - .7 the total amount of previous payments received by the Claimant; and
  - .8 the total amount due and unpaid to the Claimant for labor, materials or equipment furnished as of the date of the Claim.
- § 16.2 Claimant. An individual or entity having a direct contract with the Contractor or with a subcontractor of the Contractor to furnish labor, materials or equipment for use in the performance of the Construction Contract. The term Claimant also includes any individual or entity that has rightfully asserted a claim under an applicable mechanic's lien or similar statute against the real property upon which the Project is located. The intent of this Bond shall be to include without limitation in the terms "labor, materials or equipment" that part of water, gas, power, light, heat, oil, gasoline, telephone service or rental equipment used in the Construction Contract, architectural and engineering services required for performance of the work of the Contractor and the Contractor's subcontractors, and all other items for which a mechanic's lien may be asserted in the jurisdiction where the labor, materials or equipment were furnished.
- § 16.3 Construction Contract. The agreement between the Owner and Contractor identified on the cover page, including all Contract Documents and all changes made to the agreement and the Contract Documents.

- § 16.4 Owner Default. Failure of the Owner, which has not been remedied or waived, to pay the Contractor as required under the Construction Contract or to perform and complete or comply with the other material terms of the Construction Contract.
- § 16.5 Contract Documents. All the documents that comprise the agreement between the Owner and Contractor.
- § 17 If this Bond is issued for an agreement between a Contractor and subcontractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.



changes will not be obscured.

# GENERAL CONDITIONS OF CONTRACT

# TABLE OF CONTENTS

	CONSTRUCTION DOCUMENTS	
	DEFINITIONS	
	ADDITIONAL INSTRUCTIONS AND DRAWINGS	
	SHOP DRAWINGS, PRODUCT DATA AND SAMPLES	
	CUTTING AND PATCHING	
	CLEANING UP	
7.	USE OF SITE	4
	MATERIALS AND WORKMANSHIP	
	CONTRACTOR'S TITLE TO MATERIALS	
	"OR EQUAL" CLAUSE	
	PATENTS AND ROYALTIES	
	SURVEYS, PERMITS, REGULATIONS AND TAXES	
	CONTRACTOR'S OBLIGATIONS AND SUPERINTENDENCE	
14.	WEATHER CONDITIONS	8
	PROTECTION OF WORK AND PROPERTY	
	INSPECTION AND TESTING OF MATERIALS	
	REPORTS, RECORDS AND DATA	
	CHANGES IN THE WORK	
	EXTRAS	
	TIME FOR COMPLETION	
	CORRECTION OF WORK	
	SUBSURFACE CONDITIONS FOUND DIFFERENT	
23.	RIGHT OF DEPARTMENT TO TERMINATE CONTRACT	.11
24.	CONSTRUCTION SCHEDULE AND PERIODIC ESTIMATES	.11
25.	PAYMENTS TO CONTRACTOR	. 12
26.	WITHHOLDING OF PAYMENTS	.13
27.	ACCEPTANCE OF FINAL PAYMENT AS RELEASE	.13
28.	PAYMENTS BY CONTRACTOR	. 14
29.	CONTRACT SECURITY	. 14
	ASSIGNMENTS	
31.	MUTUAL RESPONSIBILITY OF CONTRACTORS	. 14
32.	SEPARATE CONTRACTS	. 15
33.	SUBCONTRACTS	. 15
34.	WASTE & RENEWABLES PROJECT MANAGER'S AUTHORITY	.15
35.	ARCHITECT / ENGINEER'S AUTHORITY	.16
36.	STATED ALLOWANCES	. 16
	ESTIMATES OF QUANTITIES	
38.	LANDS AND RIGHTS-OF-WAY	. 16
39.	GENERAL GUARANTEE	. 16
	CONFLICTING CONDITIONS	
	NOTICE AND SERVICE THEREOF	
	PROTECTION OF LIVES AND HEALTH	
	AFFIRMATIVE ACTION PROVISION AND MINORITY / WOMEN /	
	DISADVANTAGED BUSINESS ENTERPRISES	.18
44.	COMPLIANCE WITH FAIR LABOR STANDARDS	
	DOMESTIC PARTNERSHIP BENEFITS	
	USE AND OCCUPANCY PRIOR TO ACCEPTANCE	
	MINIMUM WAGES	
	CLAIMS	
	ANTITRUST AGREEMENT	
	INSURANCE	
	WISCONSIN LAW CONTROLLING	

#### 1. CONSTRUCTION DOCUMENTS

- A. Construction Documents, listed in Table of Contents of this Specification volume shall form part of this Contract and provisions of Construction Documents shall be as binding upon parties as if they were fully set forth in Contract itself.
- B. These shall also be considered as part of Construction Documents: Addenda, including additions and modifications incorporated in such addenda before execution of Contract; requests for information; construction bulletins; change orders; and written interpretations by Architect / Engineer or Waste & Renewables Project Manager that are made after execution of Contract.
- C. Construction Documents are complementary, and what is required by one shall be as binding as if required by all. Intent of Construction Documents is to include all labor, materials and equipment necessary for proper execution of the Work.

#### 2. DEFINITIONS

- A. These terms as used in this Contract are respectively defined as follows:
  - 1. All uses of term "County" in Construction Documents shall mean Dane County.
  - 2. All uses of term "Department" in Construction Documents shall mean Department of Waste & Renewables, which is a unit of Dane County government. Department is County agency overseeing Contract with Contractor.
  - 3. Waste & Renewables Project Manager is appointed by and responsible to Department. Waste & Renewables Project Manager has authority to act on behalf of Department and will sign change orders, payment requests and other administrative matters related to projects.
  - 4. Waste & Renewables Project Manager is responsible for supervision, administration and management of field operations involved in construction phase of this Work.
  - 5. Term "Work" includes all labor, equipment and materials necessary to produce project required by Construction Documents.
  - 6. Term "Substantial Completion" is date when project or specified area of project is certified by Architect / Engineer that construction is sufficiently completed, in accordance with Construction Documents, and as modified by any subsequent changes agreed to by parties, so that County may occupy project or specified area of project for use for which it was intended subject to permit approval for occupancy.
  - 7. Contractor is person, firm, or corporation with whom County makes Contract. Though multiple contracts may be involved, Construction Documents treat them throughout as if each were of singular number.

#### 3. ADDITIONAL INSTRUCTIONS AND DRAWINGS

A. Contractor may be furnished additional instructions and detail drawings as necessary to carry out the Work included in Contract. Additional drawings and instructions thus supplied to Contractor will coordinate with Construction Documents and will be so prepared that they can be reasonably interpreted as part thereof. Contractor shall carry out the Work in accordance with additional detail drawings and instructions.

Bid No. 319006 GC - 2 rev. 01/18

#### 4. SHOP DRAWINGS, PRODUCT DATA AND SAMPLES

- A. Unless otherwise specified, Contractor shall submit three (3) copies of all Shop Drawings for each submission, until receiving final approval. After final approval, provide five (5) additional copies for distribution and such other copies as may be required.
- B. Contractor shall submit, on an on-going basis and as directed, Product Data such as brochures that shall contain catalog cuts and specifications of all furnished mechanical and electrical equipment. Product Data shall be marked to identify applicable products, models, options, and other data. After Architect / Engineer's approval, one (1) copy shall remain in Architect / Engineer's file, one (1) kept at Department's office and one (1) kept at job site by Contractor for reference purposes.
- C. Samples shall consist of physical examples furnished by Contractor in sufficient size and quantity to illustrate materials, equipment or workmanship, and to establish standards to compare the Work.
  - 1. Submit Samples in sufficient quantity (minimum of two (2)) to permit Architect / Engineer to make all necessary tests and of adequate size showing quality, type, color range, finish, and texture. Label each Sample stating material, type, color, thickness, size, project name, and Contractor's name.
  - 2. Submit transmittal letter requesting approval, and prepay transportation charges to Architect / Engineer's office on samples forwarded.
  - 3. Materials installed shall match approved Samples.
- D. Contractor shall review Shop Drawings and place their dated stamp thereon to evidence their review and approval and shall submit with reasonable promptness and in orderly sequence to cause no delay in the Work or in work of any other contractor. At time of submission, Contractor shall inform Architect / Engineer in writing of any deviation in Shop Drawings or Samples from requirements of Construction Documents. Architect / Engineer will not consider partial lists.
- E. Architect / Engineer will review and approve or reject Shop Drawings with reasonable promptness to cause no delay. Architect / Engineer's approval shall not relieve Contractor from responsibility for errors or omissions in Shop Drawings.
- F. Contractor shall not commence any work requiring Shop Drawing, Product Data or Sample submission until Architect / Engineer has approved submission. All such work shall be in accordance with approved Shop Drawings, Product Data and Samples.
- G. Contractor shall keep on site of the Work, approved or conformed copy of Shop Drawings and shall at all times give Department access thereto.
- H. By stamping and submitting Shop Drawings, Product Data and Samples, Contractor thereby represents that he or she has or will determine and verify all field measurements, field construction criteria, materials, catalog numbers, and similar data and that he or she has checked and coordinated each Shop Drawing, Product Data and Sample with requirements of the Work and of Construction Documents. Architect / Engineer shall return without examination, Shop Drawings, Product Data and Samples not so noted.
- I. All Shop Drawings from any one Contractor should be numbered consecutively and on cover sheet shall bear name and location of project, name of Contractor, date of submittal and date of each correction or revision and associated Specification section and page number.

Bid No. 319006 GC - 3 rev. 01/18

#### 5. CUTTING AND PATCHING

- A. Contractor shall be responsible for all cutting, fitting or patching required to complete the Work or to make its parts fit together properly.
- B. Contractor shall not damage or endanger portion of the Work or fully or partially completed construction of County or separate contractors by cutting, patching or otherwise altering such construction, or by excavation. Contractor shall not cut or otherwise alter such construction by County or separate contractor except with written consent of County and of such separate contractor; such consent shall not be unreasonably withheld. Contractor shall not withhold unreasonably from County or separate contractor, Contractor's consent to cutting or otherwise altering the Work.

#### 6. CLEANING UP

- A. Contractor shall keep premises and surrounding area free from accumulation of waste materials or rubbish caused by operations under Contract. Contractor shall remove from and about the Work waste materials, rubbish, Contractor's tools, construction equipment, machinery, and surplus materials at completion of the Work. Contractor shall maintain streets and sidewalks around the Work site in clean condition. Contractor shall remove all spillage and prevent tracking of spillage arising from performance of the Work, into, out of, and within the Work site. Contractor shall establish regular maintenance program of sweeping, vacuuming and / or hosing to minimize accumulation of dirt and dust upon such areas.
- B. If Contractor fails to clean up as directed in Construction Documents, County may do so and shall charge Contractor cost thereof.
- C. Contractor shall be responsible for broken windows and glass, and at completion of the Work shall replace such damaged or broken windows and glass. After replacing damaged or broken windows and glass, Contractor shall remove all labels, wash and polish both sides of all windows and glass.
- D. In addition to general cleaning (sweeping, vacuuming and / or hosing, as is appropriate to work surface), Contractor shall perform following final cleaning for all trades at completion of the Work:
  - 1. Remove temporary protections;
  - 2. Remove marks, stains, fingerprints and other soil or dirt from painted, decorated and finished woodwork and wall surfaces;
  - 3. Remove spots, plaster, soil and paint from ceramic tile, marble and other finished materials, and wash or wipe clean;
  - 4. Clean fixtures, cabinet work and equipment, removing stains, paint, dirt and dust, and leave same in undamaged, new condition;
  - 5. Clean aluminum in accordance with recommendations of manufacturer; and
  - 6. Clean resilient floors thoroughly with well-rinsed mop containing only enough moisture to clean off any surface dirt or dust and buff dry by machine to bring surfaces to sheen.

#### 7. USE OF SITE

A. Contractor shall provide County and Architect / Engineer access to the Work under all circumstances.

B. Contractor shall confine operations at site to areas permitted by County, law, ordinance, permits and Construction Documents and shall not unreasonably encumber site with materials or equipment. Contractor shall assure free, convenient, unencumbered, direct and safe access to all properties adjacent to the Work for County, its employees, invitees and guests.

#### 8. MATERIALS AND WORKMANSHIP

- A. Contractor shall perform all work and furnish all supplies and materials, machinery, equipment, facilities and means, necessary to complete the Work required by this Contract, within time specified, in accordance with provisions of Construction Documents.
- B. All equipment and materials incorporated in the Work covered by this Contract are to be new; use recycled and / or recovered materials to extent that such use is technically and economically feasible. Recovered materials are products recovered from solid waste in form identical to original form for use that is same as, or similar to original use. Recycled materials are products manufactured from solid waste.
- C. If requested, Contractor shall furnish satisfactory evidence as to kind and quality of construction materials proposed or used. Contractor shall furnish to Architect / Engineer, for approval, manufacturer name and model, performance capacities and other pertinent information of machinery, mechanical, electrical or other types of equipment, which Contractor plans to install.
- D. If not otherwise provided, materials and labor called for in this Contract shall be provided and performed in accordance with established practice and standards recognized by Architects, Engineers, Department, and construction industry.
- E. Reference to "Standard" specifications of any association or manufacturer, or codes of County authorities, intends most recent printed edition or catalog in effect on date that corresponds with date of Construction Documents.
- F. Whenever reference is made in Specifications that work shall be "performed", "applied", in accordance with "manufacturer's directions or instructions", Contractor to whom those instructions are directed shall furnish three (3) printed copies of such instructions to Architect / Engineer before execution of the Work.

#### 9. CONTRACTOR'S TITLE TO MATERIALS

A. Contractor or any subcontractor shall not purchase materials or supplies for the Work subject to any chattel mortgage or under conditional sale contract or other agreement by which seller retains interest. Contractor warrants that all materials and supplies used in the Work are free from all liens, claims or encumbrances and Contractor has good title to them.

#### 10. "OR EQUAL" CLAUSE

A. Whenever equipment or materials are identified on Drawings or in Specifications by reference to manufacturer's or vendor's name, trade name, catalog number, and other identifying information, it is intended to establish standards; and any equipment or material of other manufacturers and vendors which will perform adequately duties imposed by general design will be considered equally accepted provided equipment or material so proposed is, in opinion of Architect / Engineer, of equal substance and function. Architect / Engineer and Department shall provide written approval before Contractor may purchase or install it.

Bid No. 319006 GC - 5 rev. 01/18

- B. Equipment or materials of manufacturers, other than those named, may be used only upon following conditions:
  - 1. That, in opinion of Architect / Engineer and Department, proposed material or equipment item is fully equal or superior (in design, materials, construction, workmanship, performance, finish, etc.) to named item. No compromise in quality level, however small, is acceptable.
  - 2. That, in substituting materials or equipment, Contractor assumes responsibility for any changes in system or for modifications required in adjacent or related work to accommodate such substitution despite Architect / Engineer's and Department's approval, and all costs growing out of approval of "or equal" items shall be responsibility of Contractor. No extra costs resulting from such approval shall become responsibility of Department, Architect / Engineer or any other separate Contractor.
  - 3. It shall be understood that use of materials or equipment other than those specified, or approved equal by Architect / Engineer and Department, shall constitute violation of Contract, and that Architect / Engineer and Department shall have right to require removal of such materials or equipment and their replacement with specified materials or equipment at Contractor's expense.
  - 4. Product and manufacturer named first in Specifications or on information shown on Drawings is basis of selection of manufactured items and equipment, particularly mechanical equipment. In using other than first named products or manufacturers, including those specified as additionally approved or acceptable, Contractor assumes responsibility for any changes in system and for modifications in any work required to accommodate them. Architect / Engineer's approval of such additionally acceptable products or manufacturers, either in Specifications or in Addendum, does not relieve Contractor from obligation to coordinate such optional products with other Contractors, whose work may be affected by them, and to pay all additional costs resulting from their inclusion into the Work. Contractor's liability shall include payment of Architect / Engineer's fees for any additional services made necessary by or directly connected to such product changes. No extra costs resulting from such changes shall become responsibility of Department, Architect / Engineer or any other separate Contractor.
- C. No request for approval of "or equal" materials will be entertained except from Contractor. Identify any request for substitution as substitution on Contractor's letter of transmittal and give reasons for substitution. Department may in its sole discretion allow substitutions of materials.

### 11. PATENTS AND ROYALTIES

- A. If Contractor uses any design, device or material covered by letters, patent or copyright, it is mutually agreed and understood, that, without exception, contract prices shall include all royalties or costs arising from use of such design, device or materials, in any way involved in the Work.
- B. Contractor shall indemnify and save harmless County from any and all claims for infringement by reason of use of such patent or copyright in connection with the Work agreed to be performed under this Contract, and shall indemnify County for any cost, expense or damage which it may be obliged to pay by reason of such infringement at any time during prosecution of the Work or after completion of the Work.

### 12. SURVEYS, PERMITS, REGULATIONS AND TAXES

- A. Department will furnish to Contractor all site, topography and property surveys necessary for execution of the Work.
- B. Contractor shall procure all permits, licenses and approvals necessary for execution of this Contract.
- C. Contractor shall give all notices and comply with all State of Wisconsin, Federal and local laws, codes, rules and regulations relating to performance of the Work, protection of adjacent property, and maintenance of passageways, guard fences or other protective facilities.
- D. Contractor shall pay all Sales, Consumer, Use and other similar taxes required by law.
- E. Contractor shall promptly notify Architect / Engineer of any variances of Drawings or Specifications with that of any State of Wisconsin, federal or local law, code, rule or regulation. Upon such notification, Architect / Engineer will require correction of variance to comply with applicable law, code, rule or regulation at no additional cost to Contractor.
- F. Work under this Contract shall comply with all applicable State of Wisconsin, Federal and local laws, codes and regulations.
- G. Contractor shall pay charges for water, sewer and other utility connections made by municipalities where required by Specifications.

#### 13. CONTRACTOR'S OBLIGATIONS AND SUPERINTENDENCE

- A. Contractor shall provide and pay for all materials, labor, tools, equipment, transportation and superintendence necessary to execute, complete and deliver the Work within specified time. Contractor agrees to secure at their own expense all personnel necessary to carry out the Work. Such personnel shall not be deemed County employees nor shall they have or be deemed to have any direct contractual relationship with County.
- B. Performance of any work necessary after regular working hours, on Sundays or Legal Holidays shall be without additional expense to County. Performance of any work at site at other than normal working hours must be coordinated with Waste & Renewables Project Manager.
- C. Contractor shall furnish, erect, maintain and remove such temporary works as may be required.
- D. Contractor shall observe, comply with, and be subject to all terms, conditions, requirements and limitations of Construction Documents.
- E. At the Work site, Contractor shall give personal superintendence to the Work or shall employ construction superintendent or foreman, experienced in character of work covered by Contract, who shall have full authority to act for Contractor. Understand that such superintendent or foreman shall be acceptable to Architect / Engineer and Department.
- F. Remove from project or take other corrective action upon notice from Architect / Engineer or Department for Contractor's employees whose work is considered by Architect / Engineer or Department to be unsatisfactory, careless, incompetent, unskilled or otherwise objectionable.

Bid No. 319006 GC - 7 rev. 01/18

- G. Contractor and subcontractors shall be required to conform to Labor Laws of State of Wisconsin and various acts amendatory and supplementary thereto and to other laws, ordinances and legal requirements applicable to the Work.
- H. Presence and observation of the Work by Architect / Engineer or Waste & Renewables Project Manager shall not relieve Contractor of any obligations.

#### 14. WEATHER CONDITIONS

A. In event of temporary suspension of work, or during inclement weather, or whenever Architect / Engineer shall direct, Contractor shall, and shall cause subcontractors to protect carefully all work and materials against damage or injury from weather. If, in opinion of Architect / Engineer or Department, any work or materials that have been damaged or injured due to failure on part of Contractor or any subcontractors so to protect the Work, such materials shall be removed and replaced at expense of Contractor.

#### 15. PROTECTION OF WORK AND PROPERTY

- A. Contractor shall at all times safely guard County's property from injury or loss in connection with this Contract. Contractor shall at all times safely guard and protect the Work, and adjacent property, from damage. Contractor shall replace or make good any such damage, loss or injury unless such is caused directly by errors contained in Contract, or by County, or County's duly authorized representative.
- B. Contractor may act diligently, without previous instructions from Architect / Engineer and / or Department, in emergency that threatens loss or injury of property, or safety of life. Contractor shall notify Architect / Engineer and / or Department immediately thereafter. Promptly submit any claim for compensation by Contractor due to such extra work to Architect / Engineer and / or Department for approval as provided for in Article 18 herein.

#### 16. INSPECTION AND TESTING OF MATERIALS

- A. Authorized representatives and agents of County government shall have access at all times to the Work wherever it is in preparation or progress and Contractor shall provide facilities for such access and for inspection.
- B. Should it be considered necessary or advisable at any time before final acceptance of the Work to make examination of work already completed, by removing or tearing out same, Contractor shall upon request, promptly furnish all necessary facilities, labor and materials. If such work is found to be defective in any aspect, due to fault of Contractor or subcontractors thereof, Contractor shall assume all expenses of such examination and of satisfactory reconstruction. Contractor will be reimbursed for such examination and replacement in accordance with Article 18 A.3., of these General Conditions of Contract if such work is found to meet requirements of Contract.
- C. If Specifications, Architect / Engineer's, or Waste & Renewables Project Manager's instructions require any work to be specially tested or approved, Contractor shall give Architect / Engineer and Waste & Renewables Project Manager timely notice of its readiness for testing or inspection. Test all materials and equipment requiring testing in accordance with accepted or specified standards, as applicable. Architect / Engineer shall recommend laboratory or inspection agency and Department will select and pay for all initial laboratory

Bid No. 319006 GC - 8 rev. 01/18

- inspection services. Should retesting be required, due to failure of initial testing, cost of such retesting shall be borne by Contractor.
- D. Cost of any testing performed by manufacturers or Contractor for substantiating acceptability of proposed substitution of materials and equipment, or necessary conformance testing in conjunction with manufacturing processes or factory assemblage, shall be borne by Contractor or manufacturer responsible.

#### 17. REPORTS, RECORDS AND DATA

A. Contractor shall submit to Architect / Engineer and Waste & Renewables Project Manager such schedule of quantities and costs, progress schedules, payrolls, reports, estimates, invoices, records and other data as either may request concerning work performed or to be performed under this Contract.

#### 18. CHANGES IN THE WORK

- A. Make no changes, except in cases of emergency, in the Work covered by approved Construction Documents without having prior written approval of Department. Charges or credits for the Work covered by approved change shall be determined by one of these methods:
  - 1. Unit bid prices previously approved.
  - 2. Agreed lump sum based on actual cost of:
    - a) Labor, including foremen, and all fringe benefits that are associated with their wages.
    - b) Materials entering permanently into the Work.
    - c) Ownership or rental cost of construction tools and equipment during time of use on extra work.
    - d) Power and consumable supplies for operation of power equipment.
    - e) Workmen's Compensation Insurance, Contractor's Public Liability and Property Damage Insurance, and Comprehensive Automobile Liability Insurance.
    - f) Social Security and old age and unemployment contributions.
    - g) Add to cost under (2), fixed fee to be agreed upon, but not to exceed fifteen percent (15%) of actual cost of work performed with their own labor force. Fee shall be compensation to cover cost of supervision, overhead, bond, profit and any other general expense.
    - h) On that portion of the Work under (2) done under subcontract, Contractor may include not over seven and one-half percent (7½%) for supervision, overhead, bond, profit and any other general expense.
    - i) Department may require correct amount of costs with supporting vouchers; Contractor shall keep and present in such form as directed.
  - 3. Cost-plus work, with not-to-exceed dollar limit, based on actual cost of:
    - a) Labor, including foremen, and all fringe benefits that are associated with their wages.
    - b) Materials entering permanently into the Work.
    - c) Ownership or rental cost of construction tools and equipment during time of use on extra work. Rental cost cannot exceed fifty percent (50%) replacement value of rented equipment.
    - d) Power and consumable supplies for operation of power equipment.
    - e) Workmen's Compensation Insurance, Contractor's Public Liability and Property Damage Insurance, and Comprehensive Automobile Liability Insurance.
    - f) Social Security and old age and unemployment contributions.
    - g) To cost under (3), there shall be added fixed fee to be agreed upon but not to exceed fifteen percent (15%) of actual cost of work performed with their own labor force.

- Fee shall be compensation to cover cost of supervision, overhead, bond, profit, and any other general expense.
- h) On that portion of the Work under (3) done under subcontract, Contractor may include not over seven and one-half percent (7½%) for supervision, overhead, bond, profit, and any other general expense.
- i) Contractor shall keep and present, in such form as directed, correct amount of cost together with such supporting vouchers as may be required by Department.
- B. If Contractor claims that by any instructions given by Architect / Engineer, Department, by drawings or otherwise, regarding performance of the Work or furnishing of material under Contract, involves extra cost, Contractor shall give Department written notice of cost thereof within two (2) weeks after receipt of such instructions and in any event before proceeding to execute work, unless delay in executing work would endanger life or property.
- C. No claim for extra work or cost shall be allowed unless it was done in pursuance of written Change Order from Architect / Engineer and approved by Department, as previously mentioned, and claim presented with payment request submitted after changed or extra work is completed.
- D. Negotiation of cost for change in the Work shall not be cause for Contractor to delay prosecution of the Work if Contractor has been authorized in writing by Waste & Renewables Project Manager to proceed.

#### 19. EXTRAS

A. Without invalidating Contract, Department may order extra work or make changes by altering, adding to or deducting from the Work, contract sum being adjusted in accordance with Article 18 herein.

#### 20. TIME FOR COMPLETION

A. Contractor agrees that the Work shall be prosecuted regularly and diligently and complete the Work as stated in Construction Documents.

#### 21. CORRECTION OF WORK

- A. All work, all materials whether incorporated in the Work or not, and all processes of manufacture shall at all times and places be subject to inspection of Architect / Engineer and Waste & Renewables Project Manager who shall be judge of quality and suitability of the Work, materials, and processes of manufacture for purposes for which they are used. Should they fail to meet Architect / Engineer's and Waste & Renewables Project Manager's approval they shall be reconstructed, made good, replaced or corrected, by Contractor at Contractor's expense. Immediately remove all rejected material from site.
- B. If Contractor defaults or neglects to carry out the Work in accordance with Construction Documents or fails to perform any provision of Contract, Department may, after ten (10) business days' written notice to Contractor and without prejudice to any other remedy County may have, make good such deficiencies. In such case, appropriate Change Order shall be issued deducting from Contractor's payments then or thereafter, cost of correcting such deficiencies, including cost of Architect / Engineer's additional services made necessary by such default, neglect or failure.

Bid No. 319006 GC - 10 rev. 01/18

#### 22. SUBSURFACE CONDITIONS FOUND DIFFERENT

A. If Contractor encounters subsurface or latent conditions at site materially differing from those shown on Drawings or indicated in Specifications, Contractor shall immediately give notice to Architect / Engineer and Waste & Renewables Project Manager of such conditions before they are disturbed. Architect / Engineer will thereupon promptly investigate conditions, and if Architect / Engineer finds that they materially differ from those shown on Drawings or indicated in Specifications, Architect / Engineer will at once make such changes as necessary, any increase or decrease of cost resulting from such changes to be adjusted in manner provided in above Article 18 entitled "Changes in the Work".

#### 23. RIGHT OF DEPARTMENT TO TERMINATE CONTRACT

- A. In event that any provisions of this Contract are violated by Contractor or by any subcontractors, County may serve written notice upon Contractor and Surety of its intention to terminate Contract, such notice to contain reasons for such intention to terminate Contract, and unless within ten (10) business days after serving of such notice upon Contractor, such violation or delay shall cease and satisfactory arrangement or correction be made, Contract shall, upon expiration of said ten (10) business days, cease and terminate.
- B. In event of any such termination, County shall immediately serve notice thereof upon Surety and Contractor, and Surety shall have right to take over and perform Contract subject to County's approval; provided, however, that if Surety does not commence performance thereof within ten (10) business days from date of mailing to such Surety of notice of termination, County may take over the Work and prosecute same to completion by contract, or by force account, at expense of Contractor; Contractor and Surety shall be liable to County for any excess cost occasioned County thereby, and in such event County may take possession of and utilize in completing the Work, such materials and equipment as may be on the Work site and therefore necessary.

#### 24. CONSTRUCTION SCHEDULE AND PERIODIC ESTIMATES

- A. Contractor shall be responsible for Construction Schedule and coordination. Immediately after execution and delivery of Contract and before making first payment, Contractor shall notify all subcontractors to furnish all required information to develop Construction Schedule. Contractor and all subcontractors associated with the Work shall furnish following information from each Division of Specifications:
  - 1. List of construction activities;
  - 2. Start, finish and time required for completion of each activity;
  - 3. Sequential relationships between activities;
  - 4. Identify all long lead-time items, key events, meetings or activities such as required submittals, fabrication and delivery, procurement of materials, installation and testing;
  - 5. Weekly definition of extent of work and areas of activity for each trade or Subcontract; and
  - 6. Other information as determined by Waste & Renewables Project Manager.
- B. In addition to above requested items, Contractor shall request delivery dates for all County-furnished equipment, materials or labor. This shall include any work handled by Department under separate contracts such as asbestos abatement, air and water balancing, etc. Indicate on Construction Schedule these associated delivery and installation dates.
- C. Progress Reporting:

Bid No. 319006 GC - 11 rev. 01/18

- Contractor shall update and publish Construction Schedule on monthly basis. Revisions
  to Schedule shall be by Contractor and made in same detail as original Schedule and
  accompanied by explanation of reasons for revision; and shall be subject to approval by
  Department.
- 2. Failure of Contractor to keep Schedule in updated format shall result in County hiring firm specializing in construction schedule development and deducting those costs associated with updating process from payments due Contractor.
- 3. Contractor shall submit show actual percentage of each activity completed, estimated future progress, and anticipated completion time.

### D. Responsibility for timely completion requires:

- 1. Contractor and subcontractors understand that performance of each is interdependent upon performance of others.
- 2. Whenever it becomes apparent from current schedule, that phasing or progress completion dates will not be met, Contractor must take some or all following actions at no additional cost to County:
  - a) Increase construction labor in such quantities and crafts as will eliminate backlog of work.
  - b) Increase number of working hours per shift, shifts per working day, working days per week, amount of construction equipment, or any combination of foregoing to eliminate backlog of work.
  - c) Reschedule work (yet remain in conformance with Drawings and Specifications).
- 3. Prior to proceeding with any of above actions, Contractor shall notify Waste & Renewables Project Manager.
- E. Maintain current Construction Schedule at all times. Revise Construction Schedule in same detail as original and accompany with explanation of reasons for revision. Schedule shall be subject to approval by Architect / Engineer and Waste & Renewables Project Manager.

#### 25. PAYMENTS TO CONTRACTOR

- A. County will make partial payments to Contractor for value, proportionate to amount of Contract, of all labor and material incorporated in the Work during preceding calendar month upon receipt and approval of Application and Certificate for Payment form by Department.
- B. Contractor shall submit all Application and Certificate for Payment forms to Waste & Renewables Project Manager for approval. If requested, Application and Certificate for Payment shall be supported by such additional evidence as may be required, showing Contractor's right to payment claimed.
- C. Application and Certificate for Payment for preparatory work and materials delivered and suitably stored at site to be incorporated into the Work at some future period, will be given due consideration. Requesting payment for materials stored off site, may be rejected, however, if deemed essential for reasons of job progress, protection, or other sufficient cause, requests will be considered, conditional upon submission by Contractor of bills of sale, photographs and such other procedures as will adequately protect County's interest such as storage in bonded warehouse with adequate coverage. If there is any error in payment, Contractor is obligated to notify Department immediately, but no longer than ten (10) business days from receipt of payment.
- D. Payments by County will be due within forty-five (45) business days after receipt by Department of Application and Certificate for Payment.

Bid No. 319006 GC - 12 rev. 01/18

- E. County will retain five percent (5%) of each Application and Certificate for Payment until final completion and acceptance of all the Work covered by Contract. However, anytime after fifty percent (50%) of the Work has been furnished and installed at site, County will make remaining payments in full if Waste & Renewables Project Manager find that progress of the Work corresponds with Construction Schedule. If Waste & Renewables Project Manager find that progress of the Work does not correspond with Construction Schedule, County may retain up to ten percent (10%) of each Application and Certificate for Payment for the Work completed.
- F. All material and work covered by partial payments made shall become sole property of County, but this provision shall not be construed as relieving Contractor from sole responsibility for care and protection of materials and work upon which payments have been made, or restoration of any damaged work, or as waiver of right of County to require fulfillment of all of terms of Contract.
- G. County will make final payment within sixty (60) calendar days after final completion of the Work, and will constitute acceptance thereof.
- H. County may make payment in full, including retained percentages and less authorized deductions, upon completion and acceptance of each Division where price is stated separately in Contract.
- I. Every contractor engaged in performance of any contract for Department of Waste & Renewables shall submit to this Department, as requested and with final application for payment for work under said contract, affidavit(s) as required to prove that all debts and claims against this Work are paid in full or otherwise satisfied, and give final evidence of release of all liens against the Work and County.

#### 26. WITHHOLDING OF PAYMENTS

- A. County, after having served written notice on said Contractor, may either pay directly any unpaid bills of which Department has written notice, or withhold from Contractor's unpaid compensation sum of money deemed reasonably sufficient to pay any and all such lawful claims until satisfactory evidence is furnished that all liabilities have been fully discharged; whereupon, payment to Contractor shall be resumed in accordance with terms of this Contract, but in no event shall these provisions be construed to impose any obligations upon County to either Contractor or Contractor's Surety.
- B. In paying any unpaid bills of Contractor, County shall be deemed agent of Contractor, and any payment so made by County, shall be considered as payment made under Contract by County to Contractor and County shall not be liable to Contractor for any such payment made in good faith.
- C. Contractor shall indemnify, hold harmless and defend Dane County, its boards, commissions, agencies, officers, employees and representatives from all claims growing out of lawful demands of subcontractors, laborers, workers, mechanics, material men, and furnishers of machinery and parts thereof, equipment, power tools, and all supplies, including commissary, incurred in performance of this Contract.
- D. At Department's request, Contractor shall furnish satisfactory evidence that all obligations of nature designated above have been paid, discharged or waived.

#### 27. ACCEPTANCE OF FINAL PAYMENT AS RELEASE

Bid No. 319006 GC - 13 rev. 01/18

- A. Making of final payment shall constitute waiver of all claims by County except those arising from:
  - 1. Unsettled lien;
  - 2. Faulty or defective work appearing after substantial completion;
  - 3. Failure of the Work to comply with requirements of Construction Documents; or
  - 4. Terms of any special guarantees required by Construction Documents.
- B. Acceptance of final payment shall constitute waiver of all claims by Contractor.

#### 28. PAYMENTS BY CONTRACTOR

- A. Contractor shall pay following not later than fifth (5<sup>th</sup>) business day following each payment received from County:
  - 1. All transportation and utility services rendered;
  - 2. All materials, tools, and other expendable equipment that have been delivered at site of the Work to extent of ninety percent (90%) of cost thereof, and balance of cost thereof when said balance is paid to Contractor; and
  - 3. Each subcontractor, respective amount allowed Contractor because of work performed by subcontractor to extent of subcontractor's interest therein.

#### 29. CONTRACT SECURITY

- A. Contractor shall furnish Performance and Payment Bonds in amount at least equal to one hundred percent (100%) of Contract price as security for faithful performance of this Contract and payment of all persons performing labor on project under this Contract and furnishing materials in connection with this Contract.
- B. Sample Performance and Payment Bonds that Contractor will be required to execute is bound into these Construction Documents. Before construction Contract is consummated, completed Performance and Payment Bonds must be approved by Department.

#### 30. ASSIGNMENTS

A. Contractor shall not assign whole or any part of this Contract or any moneys due or to become due hereunder without written consent of Department. In case Contractor assigns all or any part of any moneys due or to become due under this Contract, instrument of assignment shall contain clause substantially to effect that it is agreed that right of assignee in and to any moneys due or to become due to Contractor shall be subject to prior claims of all persons, firms and corporations for services rendered or materials supplied for performance of the Work called for in this Contract.

#### 31. MUTUAL RESPONSIBILITY OF CONTRACTORS

A. If, through acts of neglect on part of Contractor or any subcontractor shall suffer loss or damage on the Work, Contractor agrees to settle with such subcontractor by agreement or arbitration if such other subcontractor will so settle. If such subcontractor shall assert any claim against County on account of any damage alleged to have been sustained, Department shall notify Contractor, who shall indemnify, hold harmless and defend Dane County, its boards, commissions, agencies, officers, employees and representatives against any such claim.

Bid No. 319006 GC - 14 rev. 01/18

#### 32. SEPARATE CONTRACTS

- A. Department may award other contracts for the Work and all Contractors shall fully cooperate with each other and carefully adjust their work to that provided under other contracts as may be directed by Department. No Contractor shall commit or permit any act that will interfere with performance of the Work by any other Contractor.
- B. Contractor shall coordinate the Work with those of other Contractors. Cooperation will be required in arrangement for storage of materials and in detailed execution of the Work. Contractor, including subcontractors, shall keep informed of progress and detail work of others and shall notify Architect / Engineer or Department immediately of lack of progress or defective workmanship on part of others. Failure of Contractor to keep informed of the Work progressing on site and failure to give notice of lack of progress or defective workmanship by others shall be construed as acceptance by Contractor of status of the Work as being satisfactory for proper coordination with Contractor's own work.

#### 33. SUBCONTRACTS

- A. Contractor may use services of specialty subcontractors on those parts of the Work that, under normal contracting practices, are performed by specialty subcontractors.
- B. Contractor shall not award any work to any subcontractor without prior approval of Department. Qualifications of subcontractors shall be same as qualifications of Contractor. Request for subcontractor approval shall be submitted to Department fifteen (15) business days before start of subcontractor's work. If subcontractors are changed or added, Contractor shall notify Department in writing.
- C. Contractor shall be as fully responsible to County for acts and omissions of subcontractors, and of persons either directly or indirectly employed by them, as Contractor is for acts and omissions of persons directly employed by Contractor.
- D. Contractor shall cause appropriate provisions to be inserted in all subcontracts relative to the Work to bind subcontractors to Contractor by terms of General Conditions of Contract and other Construction Documents insofar as applicable to work of subcontractors and to give Contractor same power as regards terminating any subcontract that Department may exercise over Contractor under any provision of Construction Documents.
- E. Nothing contained in this Contract shall create any contractual relation between any subcontractor and County.
- F. Contractor shall insert in all subcontracts, Articles 26, 33, 43 and 45, respectively entitled: "Withholding of Payments", "Subcontracts", "Affirmative Action Provision and Minority / Women / Disadvantaged Business Enterprises", and "Minimum Wages", and shall further require all subcontractors to incorporate physically these same Articles in all subcontracts.

#### 34. WASTE & RENEWABLES PROJECT MANAGER'S AUTHORITY

- A. Waste & Renewables Project Manager shall:
  - 1. Administer and ensure compliance with Construction Documents;
  - 2. Provide responsible on-site observations of construction and have authority to request work and to stop work whenever necessary to insure proper enforcement of Construction Documents;

Bid No. 319006 GC - 15 rev. 01/18

- 3. Convene and chair project meetings and foreman's coordination meetings when necessary to coordinate resolution of conflicts between Contractors, Architects, Engineers, Consultants, and Department; and
- 4. Check and inspect material, equipment and installation procedures of all trades for proper workmanship and for compliance with Drawings, Specifications and Shop Drawings, permit no material on project site that is not satisfactory and reject work not in compliance with Construction Documents.

#### 35. ARCHITECT / ENGINEER'S AUTHORITY

- A. Architect / Engineer is retained by, and is responsible to Department acting for County.
- B. Architect / Engineer shall determine amount, quality, acceptability, and fitness of several kinds of work and materials that are provided under this Contract and shall decide all questions that may arise in relation to said work and construction thereof.
- C. Architect / Engineer shall decide meaning and intent of any portion of Specifications and of any Drawings where they may be found obscure or be in dispute.
- D. Architect / Engineer shall provide responsible observation of construction. Architect / Engineer has authority to stop the Work whenever such stoppage may be necessary to insure proper execution of Construction Documents.
- E. Architect / Engineer shall be interpreter of conditions of Construction Documents and judge of its performance.
- F. Within reasonable time, Architect / Engineer shall make decisions on all matters relating to progress of the Work or interpretation of Construction Documents.
- G. Architect / Engineer's decisions are subject to review by Waste & Renewables Project Manager.

#### 36. STATED ALLOWANCES

A. Not applicable.

### 37. ESTIMATES OF QUANTITIES

A. Whenever estimated quantities of work to be done and materials to be furnished under this Contract are shown in any of Construction Documents, they are given for use in comparing bids and right is especially reserved to increase or diminish them as they may be deemed reasonably necessary or desirable by Department to complete the Work included in this Contract, and cost for such increase or diminution shall be adjusted in manner provided for in General Conditions of Contract Article 18 entitled "Changes in the Work".

#### 38. LANDS AND RIGHTS-OF-WAY

A. Prior to start of construction, County shall furnish all land and rights-of-way necessary for carrying out and completion of the Work to be performed under this Contract.

### 39. GENERAL GUARANTEE

Bid No. 319006 GC - 16 rev. 01/18

- A. Neither final certificate of payment nor any provision in Construction Documents nor partial or entire occupancy of premises by County shall constitute acceptance of work not done in accordance with Construction Documents or relieve Contractor of liability in respect to any expressed warranties or responsibility for faulty materials or workmanship.
  - 1. In no event shall making of any payment required by Contract constitute or be construed as waiver by County of any breach of covenants of Contract or waiver of any default of Contractor and making of any such payment by County while any such default or breach shall exist shall in no way impair or prejudice right of County with respect to recovery of damages or other remedy as result of such breach or default.
- B. Contractor shall remedy and make good all defective workmanship and materials and pay for any damage to other work resulting there from, which appear within period of one (1) year from date of substantial completion, providing such defects are not clearly due to abuse or misuse by County. Department will give notice of observed defects with reasonable promptness.
- C. Guarantee on work executed after certified date of substantial completion will begin on date when such work is inspected and approved by Architect / Engineer and Waste & Renewables Project Manager.
- D. Where guarantees or warrantees are required in sections of Specifications for periods in excess of one (1) year, such longer terms shall apply; however, Contractor's Performance and Payment Bonds shall not apply to any guarantee or warranty period in excess of one (1) year.

#### 40. CONFLICTING CONDITIONS

- A. Any provision in any of Construction Documents which may be in conflict or inconsistent with any Articles in these General Conditions of Contract or Supplementary Conditions shall be void to extent of such conflict or inconsistency.
- B. In case of ambiguity or conflict between Drawings and Specifications, Specifications shall govern.
- C. Printed dimensions shall be followed in preference to measurements by scale. Large-scale drawings take precedence over small-scale drawings. Dimensions on Drawings and details are subject to field measurements of adjacent work.

#### 41. NOTICE AND SERVICE THEREOF

A. Any notice to Contractor from Department relative to any part of this Contract shall be in writing and considered delivered and service thereof completed, when said notice is posted, by certified or registered mail, to Contractor at Contractor's last given address, or delivered in person to said Contractor, or Contractor's authorized representative on the Work.

#### 42. PROTECTION OF LIVES AND HEALTH

A. In order to protect lives and health of Contractor's employees under Contract, Contractor shall comply with all pertinent provisions of Wisconsin Administrative Code, Rules of Department of Commerce, relating to Safety and Health.

Bid No. 319006 GC - 17 rev. 01/18

B. Contractor alone shall be responsible for safety, efficiency and adequacy of Contractor's tools, equipment and methods, and for any damage that may result from their failure or their improper construction, maintenance or operation.

# 43. AFFIRMATIVE ACTION PROVISION AND MINORITY / WOMEN / DISADVANTAGED BUSINESS ENTERPRISES

#### A. Affirmative Action Provisions.

- 1. During term of their Contract, Contractor agrees not to discriminate on basis of race, religion, color, sex, handicap, age, sexual preference, marital status, physical appearance, or national origin against any person, whether recipient of services (actual or potential), employee, or applicant for employment. Such equal opportunity shall include but not be limited to following: employment, upgrading, demotion, transfer, recruitment, advertising, layoff, termination, training, rates of pay, and any other form of compensation or level of service(s). Contractor agrees to post in conspicuous places, these affirmative action standards so as to be visible to all employees, service recipients and applicants for this paragraph. Listing of prohibited bases for discrimination shall no be construed to amend in any fashion state or federal law setting forth additional bases and exceptions shall be permitted only to extent allowable in state or federal law.
- 2. Contractor is subject to this Article only if Contractor has ten (10) or more employees and receives \$10,000.00 or more in annual aggregate contracts with County. Contractor shall file and Affirmative Action Plan with Dane County Contract Compliance Officer in accord with Chapter 19 of Dane County Code of Ordinances. Such plan must be filed within fifteen (15) business days of effective date of this Contract and failure to do so by said date shall constitute ground for immediate termination of Contract by County. Contractor shall also, during term of this Contract, provide copies of all announcements of employment opportunities to County's Contract Compliance Office, and shall report annually number of persons, by race, sex and handicap status, who apply for employment, and, similarly classified, number hired and number rejected.
- 3. Contact Dane County Contract Compliance Officer at Dane County Contract Compliance Office, 210 Martin Luther King, Jr. Blvd., Room 421, Madison, WI 53703, 608/266-4114.
- 4. In all solicitations for employment placed on Contractor's behalf during term of this Contract, Contractor shall include statement to affect Contractor is "Equal Opportunity Employer". Contractor agrees to furnish all information and reports required by County's Contract Compliance Officer as same relate to affirmative action and nondiscrimination, which may include any books, records, or accounts deemed appropriate to determine compliance with Chapter 19, Dane County Code of Ordinances, and provision of this Contract.

#### B. Minority / Women / Disadvantaged / Emerging Small Business Enterprises.

- 1. Chapter 19.508 of Dane County Code of Ordinances is official policy of Dane County regarding utilization of, to fullest extent of, Minority Business Enterprises (MBEs), Women Business Enterprises (WBEs) Disadvantage Business Enterprises (DBEs) and Emerging Small Business Enterprises (ESBEs).
- 2. Contractor may utilize MBEs / WBEs / DBEs / ESBEs as subcontractors or suppliers. List of subcontractors will be required of low bidder as stated in this Contract. List shall indicate which are MBEs / WBEs / DBEs / ESBEs and percentage of subcontract awarded, shown as percentage of total dollar amount of bid.

#### 44. COMPLIANCE WITH FAIR LABOR STANDARDS

Bid No. 319006 GC - 18 rev. 01/18

- A. During term of this Contract, Contractor shall report to County Contract Compliance Officer, within ten (10) business days, any allegations to, or findings by National Labor Relations Board (NLRB) or Wisconsin Employment Relations Commission (WERC) that Contractor has violated statute or regulation regarding labor standards or relations. If investigation by Contract Compliance Officer results in final determination that matter adversely affects Contractor's responsibilities under this Contract, and which recommends termination, suspension or cancellation of this Contract, County may take such action.
- B. Contractor may appeal any adverse finding by Contract Compliance Officer as set forth in Dane County Ordinance 25.015(11)(c) through (e).
- C. Contractor shall post this statement in prominent place visible to employees: "As condition of receiving and maintaining contract with Dane County, this employer shall comply with federal, state and all other applicable laws prohibiting retaliation or union organizing."

#### 45. DOMESTIC PARTNERSHIP BENEFITS

A. Not used.

#### 46. USE AND OCCUPANCY PRIOR TO ACCEPTANCE

- A. Contractor agrees to use and occupancy of portion or unit of the Work before formal acceptance by Department, provided Department:
  - 1. Secures written consent of Contractor; except when in opinion of Waste & Renewables Project Manager, Contractor is chargeable with unwarranted delay in final cleanup of punch list items or other Contract requirements.
  - 2. Secures endorsement from insurance carrier and consent of Surety permitting occupancy of building or use of the Work during remaining period of construction, or, secures consent of Surety.
  - 3. Assumes all costs and maintenance of heat, electricity and water.
  - 4. Accepts all work completed within that portion or unit of the Work to be occupied, at time of occupancy.

#### **47. MINIMUM WAGES**

- A. Contractor shall post, at appropriate conspicuous point on site of project, schedule showing all determined minimum wage rates for various classes of laborers and mechanics to be engaged in the Work under this Contract and all deductions, if any, required by law to be made from unpaid wages actually earned by laborers and mechanics so engaged.
- B. Supplementary Conditions section in Construction Documents lists wage determinations required by State Law.
- C. If, after award of Contract, it becomes necessary to employ any person in trade or occupation not classified in wage determinations, such person shall be paid at not less than such rate as shall be determined by Wisconsin Department of Workforce Development. Such approved minimum rate shall be retroactive to time of initial employment of such person in such trade or occupation. Contractor shall notify Department of Contractor's intention to employ persons in trades or occupations not so classified in sufficient time for Department to obtain approved rates for such trades or occupations.

Bid No. 319006 GC - 19 rev. 01/18

- D. Specified wage rates are minimum rates only, and Department will not consider any claims for additional compensation made by Contractor because of payment by Contractor of any wage rate in excess of applicable rate contained in this Contract. Contractor shall adjust any disputes in regard to payment of wages in excess of those specified in this Contract.
- E. Submit required affidavit(s) to Department of Waste & Renewables, as requested and with final application for payment for work under said contract. Affidavit(s) shall clearly indicate name, trade or occupation, and paid wages of every laborer, worker or mechanic employed by Contractor and all subcontractors during billing period including accurate record of number of hours worked by each employee and actual wages paid as stipulated in Wisconsin Statue 66.0903. Use "Dane County, Wisconsin Contractor Wage Affidavit" form included in Supplementary Conditions.

#### 48. CLAIMS

A. No claim may be made until Department's Director has reviewed Architect / Engineer's decision as provided for in Article 35 of General Conditions of Contract. If any claim remains unresolved after such review by Department's Director the claim may be filed under Wisconsin Statute 893.80. Work shall progress during period of any dispute or claim. Unless specifically agreed between parties, venue will be in Dane County, Wisconsin.

#### 49. ANTITRUST AGREEMENT

A. Contractor and County recognize that in actual economic practice, overcharges resulting from antitrust violations are in fact usually borne by County. Therefore, Contractor hereby assigns to County any and all claims for such overcharges as to goods and materials purchased in connection with this Contract, except as to overcharges which result from antitrust violations commencing after price is established under this Contract and any change order thereto.

#### **50. INSURANCE**

#### A. Contractor Carried Insurance:

- Contractor shall not commence work under this Contract until Contractor has obtained all
  insurance required under this Article and has provided evidence of such insurance to Risk
  Manager, 425 City-County Building, 210 Martin Luther King Jr. Blvd., Madison, WI
  53703. Contractor shall not allow any subcontractor to commence work until insurance
  required of subcontractor has been so obtained and approved. Company providing
  insurance must be licensed to do business in Wisconsin.
- 2. Worker's Compensation Insurance:
  - a) Contractor shall procure and shall maintain during life of this Contract, Worker's Compensation Insurance as required by statute for all of Contractor's employees engaged in work at site of project under this Contract and, in case of any such work sublet, Contractor shall require subcontractor similarly to provide Worker's Compensation Insurance for all of latter's employees to be engaged in such work unless such employees are covered by protection afforded by Contractor's Worker's Compensation Insurance.
  - b) If any claim of employees engaged in hazardous work on project under this Contract is not protected under Worker's Compensation Statute, Contractor shall provide and shall cause each subcontractor to provide adequate Employer's Liability Insurance for protection of such of Contractor's employees as are not otherwise protected.
- 3. Contractor's Public Liability and Property Damage Insurance:

- a) Contractor shall procure and maintain during life of this Contract, Contractor's Public Liability Insurance and Contractor's Property Damage Insurance in amount not less than \$1,000,000 bodily injury, including accidental death, to any one person, and subject to same limit for each person, in amount not less than \$1,000,000 on account of one accident, and Contractor's Property Damage Insurance in amount not less then \$1,000,000 or combined single limit of at least \$1,000,000 with excess coverage over and above general liability in amount not less than \$5,000,000. Contractor shall add "Dane County" as additional insured for each project.
- b) Contractor's Public Liability and Property Damage Insurance shall include Products, Completed Operation, and Contractual Liability under Insurance Contract. "Contractor shall in all instances save, defend, indemnify and hold harmless County and Architect / Engineer against all claims, demands, liabilities, damages or any other costs which may accrue in prosecution of the Work and that Contractor will save, defend, indemnify and hold harmless County and Architect / Engineer from all damages caused by or as result of Contractor's operations" and each shall be listed as additional insured on Contractor's and sub-contractors' insurance policies.
- c) Obligations of Contractor under Article 50.A.2.b) shall not extend to liability of Architect / Engineer, agents or employees thereof, arising out of:
  - 1) Preparation or approval of maps, drawings, opinions, reports, surveys, change orders, designs or specifications; or
  - 2) Giving of or failure to give directions or instructions by Architect / Engineer, agents or employees thereof provided such giving or failure to give is primary cause of injury or damage.
- d) Contractor shall procure and shall maintain during life of this Contract, Comprehensive Automobile Liability Insurance covering owned, non-owned and hired automobiles for limits of not less than \$1,000,000 each accident single limit, bodily injury and property damage combined with excess coverage over and above general liability in amount not less than \$5,000,000.
- e) Contractor shall either:
  - 1) Require each subcontractor to procure and to maintain during life of subcontract, subcontractor's Public Liability Property Damage Insurance, and Comprehensive Automobile Liability Insurance of type and in same amount specified in preceding paragraphs; or
  - 2) Insure activities of subcontractors in Contractor's own policy.
- 4. Scope of Insurance and Special Hazards: Insurance required under Article 50.A.2 & 50.A.3. hereof shall provide adequate protection for Contractor and subcontractors, respectively, against damage claims which may arise from operations under this Contract, whether such operation be by insured or by anyone directly or indirectly employed by insured and also against any of special hazards which may be encountered in performance of this Contract as enumerated in Supplementary Conditions.
- 5. Proof of Carriage of Insurance: Contractor shall furnish Risk Manager with certificates showing type, amount, class of operations covered, effective dates, dates of expiration of policies and "Dane County" listed as additional insured. Such certificates shall also contain (substantially) following statement: "Insurance covered by this certificate will not be canceled or materially altered, except after ten (10) business days written notice has been received by Risk Manager."

#### B. Builder's Risk:

1. County shall provide Builder's Risk insurance coverage for its insurable interests in construction or renovation projects with completed value of \$1,000,000 or less. Therefore, if project completed value is more than \$1,000,000, Contractor shall obtain and maintain in force, at its own expense, Builder's Risk Insurance on all risks for amount equal to full completed value of covered structure or replacement value of

Bid No. 319006 GC - 21 rev. 01/18

alterations or additions. Any deductible shall not exceed \$25,000 for each loss. Policy shall include occupancy clause and list Dane County as loss payee.

#### C. Indemnification / Hold Harmless:

- 1. Contractor shall indemnify, hold harmless and defend Dane County, its boards, commissions, agencies, officers, employees and representatives from and against all claims, damages, losses and expenses including attorneys' fees arising out of or resulting from performance of the Work, provided that any such claim, damage, loss or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself) including loss of use resulting therefrom, and is caused in whole or in part by any act or omission of Contractor, any subcontractor, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, regardless of whether or not it is caused in part by part indemnified hereunder.
- 2. In any and all claims against Dane County, its boards, commissions, agencies, officers, employees and representatives or by any employee of Contractor, any subcontractor, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, indemnification obligation under this Contract shall not be limited in any way by any limitation on amount or type of damages, compensation or benefits payable by or for Contractor or any subcontractor under worker's compensation acts, disability benefits or other employee benefit acts.
- 3. Obligations of Contractor under this Contract shall not extend to liability of Architect / Engineer, its agents or employees arising out of:
  - a) Preparation or approval of maps, drawings, opinion, reports, surveys, change orders, designs or specifications; or
  - b) Giving of or failure to give directions or instruction by Architect / Engineer, its agents or employees provided such giving or failure to give is primary cause of injury or damage.
- 4. Dane County shall not be liable to Contractor for damages or delays resulting from work by third parties or by injunctions or other restraining orders obtained by third parties.

#### 51. WISCONSIN LAW CONTROLLING

A. It is expressly understood and agreed to by parties hereto that in event of any disagreement or controversy between parties, Wisconsin law shall be controlling.

Bid No. 319006 GC - 22 rev. 01/18

#### SUPPLEMENTARY CONDITIONS

### 1. APPLICATION & CERTIFICATE FOR PAYMENT

A. Every contractor engaged in performance of any contract for Department of Waste and Renewables shall submit partial and final Application & Certificate for Payment for work under said contract. Form shall provide similar information as shown on AIA G702<sup>TM</sup> and G703<sup>TM</sup> forms (samples shown below). Forms shall be submitted to Waste and Renewables Project Manager for approval.

	for Payment			
O OWNER:	PROJECT:	3		stribution to:
			PERIOD TO:	OWNER
			CONTRACT FOR: ARC	CHITECT
FROM CONTRACTOR:	VIA ARCHI	TECT:	CONTRACT DATE: CONTR	RACTOR III
			PROJECT NOS:	FIELD 🗆
CONTRACTOR'S APPLICATION			The undersigned Contractor certifies that to the best of the Contractor's knowledge	OTHER
ALÀ Document 0703™, Continuation Sheet, in Ontional CONTRACT SIM   NET CHANGE BY CHANGE GREERS  NET CHANGE BY CHANGE ORDERS  1. TOTAL COMPLETED & STORED TO DATE (fcc   fcc)   ** "sof Completed Work  (Column D + E on 0708)   ** "sof Completed Work  (Column D + E on 0708)   ** "sof Stored Material  (Column D on 0708)   ** "Sof Total Retuings (Emms 5 o + 35, or Total In  TOTAL REARNED LESS RETANAGE  (Line 4 minus Line 3 Toul)   ** LESS PREVIOUS CERTIFICATES FOR PAYME  (Line 6 from prior Certification)  CURRENT PAYMENT USE  **. BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE  (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE   (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE   (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE   (Line 8 minus Line 6)   **BALANCE TO FINISH, INCLUDIOR RETANAGE   (Line 8 minus Line 6)   **BALANCE TO FINISH   **BALANCE TO	S S S Column 1 of G703)		with the Contract Documents, that all amounts have been paid by the Contractor which pervisors certificates for Payment were issued and payments received from the that current payment shown been it is now due.  COUTRACTOR  BY:  Date:  Shale of Country of Subscribed and savorn to before me this document to be the contractor of the Country of Subscribed and savorn to before me this document to be the contract Documents. Board on on-nite observations and the day contracts and the contract Documents. Board on on-nite observations and the day contracts and belief the Work has propressed as indicated, the quality of the accordance with the Contract Documents, and the Contractor is entitled to pay AMOLINI CERTIFIED.  AMOUNT CERTIFIED  AMOUNT CERTIFIED	ta comprising s knowledge, Work is in yment of the
	ADDITIONS	DEDUCTIONS	Application and on the Continuation Sheet that are changed to conform with the amou ARCHITECT:	mt certified.)
CHANGE ORDER SUMMARY  Total changes approved in previous months by		S	By: Date:	
Total approved this month	S	s	10-	
	TAL S	s	This Certificate is not negotiable. The AMOUNT CERTIFIED is payable only to the C named herein. Issuance, payment and acceptance of payment are without prejudice to:	ontractor any rights of
NET CHANGES by Change Order	s		the Owner or Contractor under this Contract.	
			n RED. An original assures that changes will not be obscured.	

containing In tabulati	JA Document G70274–1992. Application and Certificate for Payment, or G73274–2009, opplication and Certificate for Payment. Construction Manager as Adviser Edition, orthing Centractive's signed certification is attached, tabulations below, announts are in US dollars. See Column In Contracts where variable retaining for line items may apply.				APPLICATION NO: APPLICATION DATE: PERIOD TO: ARCHITECT'S PROJECT NO:					
A	В	С	D	E	F		G	//	Н	I
			WORK CO	MPLETED	MATERIALS	TOTAL			] ]	
ITEM NO.	DESCRIPTION OF WORK	SCHEDULED VALUE	FROM PREVIOUS APPLICATION (D + E)	THIS PERIOD	PRESENTLY STORED (Not thi D or E)	COMPLETE STORED TO (D+E-	ED AND O DATE	(G+C)	BALANCE TO FINISH (C - G)	RETAINAGE (If variable rate)
	GRAND TOTAL	1					-			

#### SECTION 01001

#### **BASIC REQUIREMENTS**

#### PART 1 GENERAL

#### 1.1 SECTION SUMMARY

Α.	Castion	Includes:
Α.	Section	meruaes:

- 1. Section Summary
- 2. Summary of the Work
- 3. Contractor Use of Premises
- 4. Applications for Payment
- 5. Change Procedures
- 6. Alternates
- 7. Lump Sum Allowances for Work
- 8. Coordination
- 9. Cutting and Patching
- 10. Conferences
- 11. Progress Meetings
- 12. Job Site Administration
- 13. Submittal Procedures
- 14. Proposed Products List
- 15. Shop Drawings
- 16. Product Data
- 17. Samples
- 18. Manufacturers' Instructions
- 19. Manufacturers' Certificates
- 20. Quality Assurance / Quality Control of Installation
- 21. References
- 22. Interior Enclosures
- 23. Protection of Installed Work
- 24. Parking
- 25. Staging Areas
- 26. Occupancy During Construction and Conduct of Work
- 27. Protection
- 28. Progress Cleaning
- 29. Products
- 30. Transportation, Handling, Storage and Protection
- 31. Product Options
- 32. Substitutions
- 33. Starting Systems
- 34. Demonstration and Instructions
- 35. Contract Closeout Procedures
- 36. Final Cleaning
- 37. Adjusting
- 38. Operation and Maintenance Data
- 39. Spare Parts and Maintenance Materials

Bid No. 319006 Basic Requirements rev. 03/18 01001 - 1

#### 40. As-Built and Record Drawings and Specifications

#### 1.2 SUMMARY OF THE WORK

- A. Project Description: Perform the Work as specified and detailed in the Project Manual and Construction Plan Set.
- B. Work by Owner: See Instructions to Bidders, Section 19.
- C. Diggers Hotline:
  - 1. It is General Contractor's responsibility to contact Diggers Hotline to have all utility locations marked prior to excavation and planning excavation so as not to delay the Work.
  - 2. County shall be responsible to contact & hire private utility locating services, if necessary.

#### 1.3 CONTRACTOR USE OF PREMISES

- A. Refer to General Conditions of Contract, Section 7 titled "Use of Site".
- B. Coordinate utility outages and shutdowns with Owner.

#### 1.4 APPLICATIONS FOR PAYMENT

- A. Submit one (1) original copies with "wet" signatures of each application on AIA G702<sup>TM</sup> and G703<sup>TM</sup> forms or approved contractors invoice form.
- B. Content and Format: Utilize Schedule of Values for listing items in Application for Payment.
- C. Payment Period: Monthly.
- D. Submit Applications for Payment to Waste & Renewables Project Manager for approval & processing for payment.

#### 1.5 CHANGE PROCEDURES

A. Refer to General Conditions of Contract, Article 18 titled "Changes in the Work".

### 1.6 ALTERNATES

- A. Alternates quoted on Bid Form shall be reviewed and accepted or rejected at Owner's option.
- B. Coordinate related work and modify surrounding work as required.
- C. Schedule of Alternates: Refer to Bid Form.

Bid No. 319006

Requirements

onumber 1900 

Basic Requirements

onumber 1900 

01001 - 2

#### 1.7 LUMP SUM ALLOWANCES FOR WORK

A. Not Applicable.

#### 1.8 COORDINATION

- A. Coordinate scheduling, submittals, and work of various sections of Specifications to assure efficient and orderly sequence of installation of interdependent construction elements.
- B. Verify utility requirement characteristics of operating equipment are compatible with building utilities.
- C. Coordinate space requirements and installation of mechanical and electrical work that are indicated diagrammatically on Drawings.

#### 1.9 CUTTING AND PATCHING

A. Refer to General Conditions of Contract, Section 5 titled "Cutting and Patching".

#### 1.10 CONFERENCES

- A. Project shall have pre-bid conference; see Instructions to Bidders.
- B. Owner will schedule preconstruction conference after Award of Contract for all affected parties.
- C. Contractor shall submit Construction Schedule at pre-construction meeting.
- D. When required in individual Specification section, convene pre-installation conference at project site prior to commencing work of Section.

#### 1.11 PROGRESS MEETINGS

- A. Owner shall schedule and administer meetings throughout progress of the Work on an asneeded basis.
- B. Owner shall preside at meetings, record minutes, and distribute copies within two (2) business days to those affected by decisions made.
- C. Attendance at scheduled progress meetings by General Contractor, subcontractors, or their authorized representative, is mandatory.
- D. Contractors shall give verbal reports of progress on the Work, discuss schedule for upcoming period and present all conflicts, discrepancies or other difficulties for resolution.

Bid No. 319006

Basic Requirements

01001 - 3

#### 1.12 JOB SITE ADMINISTRATION

A. County shall have representative on site during progress of the Work.

#### 1.13 SUBMITTAL PROCEDURES

- A. Submittal form to identify Project, Contractor, Subcontractor or supplier; and pertinent Construction Documents references.
- B. Apply Contractor's stamp, signed or initialed, certifying that review, verification of Products required, field dimensions, adjacent construction work, and coordination of information is in accordance with requirements of the Work and Construction Documents.
- C. Identify variations from Construction Documents and Product or system limitations that may be detrimental to successful performance of completing the Work.
- D. Revise and resubmit submittals as required; identify all changes made since previous submittal.

#### 1.14 PROPOSED PRODUCTS LIST

A. Within fifteen (15) business days after date of Award of Contract, submit complete list of major Products proposed for use, with name of manufacturer, trade name, and model number of each Product.

#### 1.15 SHOP DRAWINGS

A. Refer to General Conditions of Contract, Section 4 titled "Shop Drawings, Product Data and Samples".

#### 1.16 PRODUCT DATA

A. Refer to General Conditions of Contract, Section 4 titled "Shop Drawings, Product Data and Samples".

#### 1.17 SAMPLES

A. Refer to General Conditions of Contract, Section 4 titled "Shop Drawings, Product Data and Samples".

#### 1.18 MANUFACTURERS' INSTRUCTIONS

A. When specified in individual Specification sections, submit manufacturers' printed instructions for delivery, storage, assembly, installation, start-up, adjusting, and finishing, in quantities specified for Product Data.

Bid No. 319006

Basic Requirements

01001 - 4

#### 1.19 MANUFACTURERS' CERTIFICATES

- A. When specified in individual Specification sections, submit manufacturers' certificate to Waste & Renewables Project Manager for review, in quantities specified for Product Data.
- B. Indicate material or Product conforms to or exceeds specified requirements. Submit supporting reference data, affidavits, and certifications as appropriate.

#### 1.20 OUALITY ASSURANCE / QUALITY CONTROL OF INSTALLATION

- A. Monitor quality control over suppliers, manufacturers, Products, services, site conditions, and workmanship, to produce work of specified quality.
- B. Comply fully with manufacturers' instructions.
- C. Comply with specified standards as minimum quality for the Work except when more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.

#### 1.21 REFERENCES

- A. Conform to reference standard by date of issue current as of date for receiving bids.
- B. Should specified reference standard conflict with Construction Documents, request clarification from Waste & Renewables Project Manager before proceeding.

#### 1.22 INTERIOR ENCLOSURES

A. Not applicable.

#### 1.23 PROTECTION OF INSTALLED WORK

A. Refer to General Conditions of Contract, Section 15 titled "Protection of Work and Property".

#### 1.24 PARKING

- A. Refer to General Conditions of Contract, Section 7 titled "Use of Site".
- B. Parking shall be available at the Work site.

#### 1.25 STAGING AREAS

A. Refer to General Conditions of Contract, Section 7 titled "Use of Site".

#### 1.26 OCCUPANCY DURING CONSTRUCTION AND CONDUCT OF WORK

A. Refer to General Conditions of Contract, Section 7 titled "Use of Site".

Bid No. 319006 Basic Requirements rev. 03/18 01001 - 5

- B. All construction material and salvage material shall be removed from facility or secured at day's end.
- C. Smoking is prohibited on Dane County property.
- D. Contractor shall, at all times, provide approved, safe walkways and facility entrances for use by Owner, employees and public.
- E. Contractor shall provide adequate protection for all parts of facility, its contents and occupants wherever the Work under this Contract is to be performed.
- F. Each Contractor shall arrange with Owner to make necessary alterations, do new work, make connections to all utilities, etc., at such times as will not cause interruption of utility services to facility. Contractor doing this work shall protect, cap, cut off and / or replace and relocate existing pipes, electrical work and other active utilities encountered which may interfere with new construction work.
- G. Contractor is responsible for providing & maintaining temporary toilet facilities.

#### 1.27 PROTECTION

- A. Contractor shall protect from damage / injury all trees, shrubs, hedges, plantings, grass, mechanical, electrical & plumbing equipment, walks and driveways and pay for any damage to same resulting from insufficient or improper protection.
- B. Contractor shall provide and maintain barricades & signage to prohibit public access to construction site.

#### 1.28 PROGRESS CLEANING

A. Refer to General Conditions of Contract, Section 6 titled "Cleaning Up".

#### 1.29 PRODUCTS

- A. Products: Means new material, machinery, components, equipment, fixtures, and systems forming the Work, but does not include machinery and equipment used for preparation, fabrication, conveying and erection of the Work. Products may also include existing materials or components specifically identified for reuse.
- B. Do not use materials and equipment removed from existing premises, except as specifically identified or allowed by Construction Documents.

#### 1.30 TRANSPORTATION, HANDLING, STORAGE AND PROTECTION

A. Transport, handle, store and protect Products in accordance with manufacturer's instructions.

Bid No. 319006

Basic Requirements

01001 - 6

#### 1.31 PRODUCT OPTIONS

- A. Where definite material is specified, it is not intentional to discriminate against "equal" product made by another manufacturer. Intention is to set definite standard of material quality. Should bidder choose to bid materials other than those specified, bidder shall submit said materials specifications to Waste & Renewables Project Manager for approval at least seven (7) business days prior to Bid Due Date.
- B. Products and materials that are not specified, but have been approved for use by Waste & Renewables Project Manager shall be identified in addenda to all bidding contractors.
- C. Requests for material or product substitutions submitted after Bid Due Date may be considered. Owner reserves right to approve or reject substitutions based on Specification requirements and intended use.

#### 1.32 SUBSTITUTIONS

- A. Waste & Renewables Project Manager shall consider requests for Substitutions only up to seven (7) business days prior to date of Bid Due Date.
- B. Document each request with complete data substantiating compliance of proposed Substitution with Construction Documents.
- C. Submit three (3) copies of requests for Substitution for consideration. Limit each request to one (1) proposed Substitution.
- D. Substitutions shall not change contract price established at Bid Due Date.

#### 1.33 STARTING SYSTEMS

- A. Provide written notification prior to start-up of each equipment item or system.
- B. Ensure that each piece of equipment or system is ready for operation.
- C. Execute start-up under supervision of responsible persons in accordance with manufacturers' instructions.
- D. Submit written report that equipment or system has been properly installed and is functioning correctly.

### 1.34 DEMONSTRATION AND INSTRUCTIONS

- A. Demonstrate operation and maintenance of Products to Owner's personnel prior to date of final inspection.
- B. Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, maintenance, and shutdown of each item of equipment at agreed-upon times, at designated location.

Bid No. 319006

Requirements

onumber 1900 

Basic Requirements

onumber 1900 

01001 - 7

C. Owner may choose to photograph or videotape demonstration session; demonstration and demonstrator shall be to level of satisfaction of Owner.

#### 1.35 CONTRACT CLOSEOUT PROCEDURES

- A. Submit written certification that Construction Documents have been reviewed, the Work has been inspected, and the Work is complete in accordance with Construction Documents and ready for Waste & Renewables Project Manager's inspection.
- B. Submit final Application for Payment identifying total adjusted Contract Sum / Price, previous payments, and amount remaining due.

#### 1.36 FINAL CLEANING

A. Refer to General Conditions of Contract, Section 6 titled "Cleaning Up".

#### 1.37 ADJUSTING

A. Adjust operating Products and equipment to ensure smooth and unhindered operation.

#### 1.38 OPERATION AND MAINTENANCE MANUAL

A. Provide two (2) bound, hard-copy operation and maintenance manuals that include all systems, materials, products, equipment, mechanical and electrical equipment and systems supplied and installed in the Work. Provide electronic version of operation and maintenance manual also.

#### 1.39 SPARE PARTS AND MAINTENANCE MATERIALS

- A. Provide Products, spare parts, maintenance and extra materials in quantities specified in individual Specification Sections.
- B. Deliver to the Work site and place in location as directed.

#### 1.40 AS-BUILT AND RECORD DRAWINGS AND SPECIFICATIONS

A. Contractor-produced Drawings and Specifications shall remain property of Contractor whether Project for which they are made is executed or not. Contractor shall furnish Waste & Renewables Project Manager with original marked up redlines of Construction Documents' drawings and specifications that shall include all Addendums, Change Orders, Construction Bulletins, on-site changes, field corrections, etc. These are project As-Built Drawings & Specifications. Record Drawings & Specifications shall be created from these As-Builts by Waste & Renewables.

#### PART 2 PRODUCTS

Not Used.

Bid No. 319006 Basic Requirements rev. 03/18 01001 - 8

## PART 3 EXECUTION

Not Used.

END OF SECTION

Bid No. 319006 rev. 03/18

Basic Requirements
01001 - 9

#### SECTION 01010 SUMMARY OF WORK

#### PART 1 GENERAL

#### 1.1 GENERAL PROJECT DESCRIPTION

A. Installation of a perimeter gas mitigation system at the Dane County Landfill Site No. 1 in Verona, Wisconsin.

#### DESCRIPTION OF THE WORK 1.2

- Α. The Work includes, but is not limited to:
  - Provide and install erosion control devices. 1.
  - 2. Provide and install gas control wells, wellheads, and vault/cover.
  - 3. Provide and install header/lateral piping, condensate drains, and related appurtenances as required for a complete installation.
  - Provide and install gas monitoring probes/methane sensors, and related appurtenances as 4. required for a complete installation.
  - 5. Install blower, electrical/controls conduits and wiring, , and related control appurtenances as required for a complete installation.
  - 6. Other related work described in the Contract Documents such as submittals, quality control, restoration, temporary construction facilities and controls, cleaning, protection, etc., necessary and incidental to fully execute the Work.
  - 7. Start-up and testing of system.

#### WORK BY OTHERS 1.3

Refer to Section 19 in Instructions to Bidders titled "Work by Owner". A.

#### 1.4 GENERAL REQUIREMENTS

- A. Perform Work in a manner which minimizes disruptions to the operation of the Site.
- B. Perform Work in compliance with federal, state and local codes, zoning laws, and other applicable regulations.
- C. Perform Work in accordance with the Erosion Control Plan.
- D. Obtain all necessary permits, including building and/or electrical.
- E. Notify public utilities a reasonable time before starting the Work. Verify public utility markings prior to Work. Contractor is responsible for damage to public utilities or subterranean structures, including property damage or environmental damage resulting from damage to public utilities or subterranean structures and other incidental damage, if Contractor fails to obtain markings of public utility lines or subterranean structures, or if Contractor performs the Work in disregard of utility or structure markings, or if Contractor is otherwise negligent in performing the Work.
- F. Contractor is responsible for damage to private utilities or subterranean structures, including property damage or environmental damage resulting from damage to private utilities or subterranean structures and other incidental damage, if Contractor performs the Work in disregard of utility or structure markings or if Contractor is otherwise negligent in performing the Work.
- G. Utilities should not be removed or relocated unless indicated or specified in the Contract Documents. Inactive or abandoned utilities encountered during Work shall be removed, plugged, or capped as directed by the affected utility company.

Bid No. 319006 Summary of Work

#### 1.5 WARRANTY OF CONSTRUCTION

- A. In addition to other warranties in this Contract, Contractor warrants that Work is free of any defects for a period of 1 year.
- B. The warranty shall take effect upon Owner's written notice of acceptance of the completed Work.
- C. Contractor shall remedy, at Contractor's expense, any defect in Work within 2 weeks of written notice of defect.
- D. Defect repairs shall be made to the requirements of the Specifications.

#### PART 2 PRODUCTS

Not Used

#### PART 3 EXECUTION

Not Used

END OF SECTION

Bid No. 319006 Summary of Work

#### SECTION 01016 SAFETY REQUIREMENTS AND PROTECTION OF PROPERTY

#### PART 1 GENERAL

#### 1.1 HEALTH AND SAFETY CONSIDERATIONS

- A. The site is adjacent to a closed municipal solid waste landfill and the blower/generator buildings for the landfill gas extraction system. While there is no specific knowledge that refuse will be encountered, HAZARDOUS SUBSTANCES INCLUDING METHANE GAS MAY BE ENCOUNTERED. Contractor shall comply with applicable laws and regulation concerning such substances, and shall be responsible for recognizing potentially hazardous situations.
- B. Contractor is solely and completely responsible for health and safety as set forth in Section 42 of the General Conditions. This requirement applies continuously for the duration of the Contract. The Owner, Engineer, and their representatives are not responsible for safety.
- C. Employ a person who is qualified and experienced in construction safety, whose prime responsibility will be accident prevention during construction. Such person(s) shall be at the work site and be authorized to supervise and enforce compliance with the Health and Safety Plan.
- D. Provide all equipment required to implement the Health and Safety Plan.

#### 1.2 HEALTH AND SAFETY PLAN

- A. Develop and implement in accordance with the Agreement, OSHA regulations, and any other applicable federal, state, or local regulations. At a minimum, the plan shall address the items listed below as well as any additional items required by site-specific project conditions and/or local, state, and federal regulations.
  - 1. Key Personnel and on-site Competent Person.
  - 2. Comprehensive workplan.
  - 3. Hazard analysis for each site task.
  - 4. Employee training.
  - 5. Personal protective equipment.
  - 6. Medical surveillance.
  - 7. Frequency and types of air monitoring, personnel monitoring and environmental sampling techniques, and instrumentation to be used.
  - 8. Site control measures.
  - 9. Emergency response plan.
  - 10. Spill containment program.

#### 1.3 EXCAVATION SAFETY

A. Maintain a temporary barrier (i.e., orange plastic fencing) around excavation at all times while open to restrict access.

#### 1.4 ACCIDENT REPORTS

- A. If serious injury or damage occurs, the accident shall be reported immediately by telephone or email to the Owner and to appropriate local authorities. In addition, the Contractor must promptly report in writing to the Owner all accidents occurring in connection with the Work, giving full details, names, and statements of witnesses.
- B. If a claim is made by anyone against the Contractor or any Subcontractor resulting from an accident, the Contractor shall promptly report the facts in writing to the Owner, giving full details of the claim, including investigation and restitution.

C. In addition, a summary report shall be made to the Owner with each Payment Application which shall indicate the date, time, name of the injured, details of the accident, and current status.

## 1.5 COMPLAINTS

- A. All complaints received by the Contractor shall be reported to the Owner no later than the working day following receipt thereof. Such reports shall include the name, address, date, time received, date and time of action complained about, and a brief description of the alleged damages or other circumstances upon which the complaint is predicated. Each complaint shall be assigned a separate number, and all complaints shall be numbered consecutively in order of receipt. In the event that more than one complaint is received from the same complainant, each latter complaint shall show all previous complaint numbers registered by the same complainant.
- B. In addition, a summary report shall be made to the Owner with each Payment Application which shall indicate the date, time, and name of the person investigating the complaint and the amount of damages claimed (or estimate thereof), including the amount of settlement, if any.
- C. When settlement of a claim is made, the Owner shall be furnished with a copy of the release of claim by the claimant. The Owner shall be notified immediately, throughout the statutory period of liability, of any formal claims or demands made by attorneys on behalf of claimants; of the serving of notice, summons, subpoena, or other legal documents incidental to litigation; and for any out-of-court settlement or court verdicts resulting from litigation.

## 1.6 FIRE PREVENTION AND PROTECTION

A. Execute all Work in a fire-safe manner. Supply and maintain on the site adequate fire-fighting equipment capable of extinguishing incipient fires. Comply with applicable fire-prevention laws. Where these laws do not apply, applicable parts of the National Fire Prevention Standard for Safeguarding Building Construction Operations (NFPA No. 241) shall be followed.

## 1.7 SECURITY

A. If the Contractor deems it necessary to employ watchmen to safeguard the Work, equipment, or the public, employ only licensed and uniformed watchmen, physically capable of adequately patrolling the entire work area.

### 1.8 PROTECTION OF PROPERTY

A. Employ such means and methods as necessary to adequately protect all property against damage. In the event of damage to such property, immediately restore the property to a condition at least equal to its original condition and to the satisfaction of the Owner, at Contractor's expense.

### 1.9 SITE RESTORATION AND CLEANUP

- A. At all times during the Work, keep the premises clean and orderly; and upon completion of the Work, repair all damage caused by equipment and leave the project free of rubbish or excess materials of any kind.
- B. Stockpile excavated materials in a manner that will cause the least damage to adjacent lawns, grassed areas, shrubbery, or fences; remove all excavated materials from grassed and planted areas, and leave these surfaces in a condition equivalent to their original condition.

### **PART 2 PRODUCTS**

Not Applicable.

## PART 3 EXECUTION

Not Applicable.

# SECTION 01200 MEASUREMENT AND PAYMENT

## PART 1 GENERAL

### 1.1 SECTION INCLUDES

A. Procedures for measurement and payment for the Work to be done under the respective items listed in the itemized quantity listing for this project.

## 1.2 GENERAL

- A. The following paragraphs describe measurement of and payment for the Work included under the respective items listed in the itemized bid for this contract.
- B. Each lump sum and unit price stated in the itemized bid shall constitute full compensation for not only all labor, equipment and materials necessary and required to complete all work specified under that particular item including cleaning up, but also all costs for doing related work as set forth in these Specifications and/or on the Contract Drawings or implied in carrying out their intent.
- C. It is anticipated that all work satisfactorily completed will be processed under monthly Payment Requests, each dated on the 30th day of each month during the construction period.
- D. Owner will provide initial topographic survey and final as-built survey in areas being constructed. All other construction staking and lay-out is the responsibility of the Contractor.

# 1.3 QUANTITIES

- A. Quantities indicated in the Bid Form are for bidding and contract purposes only. Actual payment quantities will be determined by measured quantities supplied or constructed and verified by Owner.
- B. If the actual Work requires quantities less than or greater than those quantities indicated in the Bid Form, Contractor will provide the required quantities at the unit prices contracted.
- C. The quantities given in the Contract Documents are approximate only, and are given as a basis for the uniform comparison of bids. Owner does not expressly or by implication agree that the actual amount of work will correspond therewith.
- D. The Contractor must provide, for Unit Price Work, a proposed contract price determined on the basis of estimated quantities required for each item. The estimated quantities of items are not guaranteed and are solely for the purpose of comparing bids. Each such unit price will be deemed to include an amount for overhead, profit and indirect costs for each separately defined item.
- E. An increase or decrease in the quantity for any unit price item shall not be regarded as sufficient grounds for an increase or decrease in the price of the items.

## 1.4 MEASUREMENT AND COMPUTATION OF QUANTITIES

- A. Measurement of quantities expressed as area shall be based upon a horizontal, planimetric projection to the Work limits as determined by survey Record Drawings for each item with no additional allowances for slopes.
- B. Measurement of quantities expressed as volume shall be based upon comparison of survey Record Drawings performed both prior to and upon completion of each item.

- C. Computation of the volume of prismoids shall be by the method of average end areas of surveyed cross sections recorded at 50-foot stations at the same locations both prior to construction and upon completion of construction of these items. Measurement of length for these items shall be recorded along the top centerline for purposes of volume computations.
- D. Measurement of linear items such as piping, drainage swales, and access roads will be for quantities actually installed to the specified work limits, based upon minimum 50-foot surveyed stations (planimetric horizontal distance) recorded along the straight or curved centerline of each respective item with no additional allowances for slope.
- E. No partial payments shall be made for items which have not been tested and approved.
- F. Payment will be made to the limits as specified in the Contract Documents. If the constructed limits are less than the specified limit, payment will be made to the actual limits of construction as shown on the Record Drawings. Payment for quantities that exceed the specified contract limits will only be made with the approval of the Owner/Owner/Engineer. The payment for quantities that exceed the contract quantities can only be obtained through an approved change order before contract quantities are exceeded.

### 1.5 SCHEDULE OF CONTRACT PAYMENT ITEMS

- A. Bid Item 1 Mobilization/Demobilization:
  - 1. The lump sum price for this item shall be payment in full for supervision and management, ongoing project related expenses such as site health and safety, utilities, dust control, bonds, and insurances, etc. and compliance with the requirements of regulatory agencies and utilities, as well as mobilization and demobilization of all parts, material, and equipment to and from the site.
  - 2. The price shall include, but not be limited to, the following:
    - a. Supervision and management expenses such as:
      - 1) The salaries of Project Manager, Engineer, Superintendent, QA/QC Specialist, etc.
      - 2) Management travel, etc.
    - b. Ongoing project related expenses such as:
      - Transportation or delivery of all parts, material, and equipment necessary for the work to and/or from the site.
      - 2) Dust control.
      - 3) Master mechanic services.
      - 4) Contractor's facilities, office trailers, and their related expenses.
      - 5) Vehicles and related maintenance including supplies such as fuel.
      - 6) Sanitary facilities and related maintenance.
      - 7) Contractor provided utilities.
      - 8) Dewatering.
      - 9) Preparation and submission of submittals, shop drawings, Operations and Maintenance Manual, etc.
      - 10) Landfill gas control measures during construction, if necessary.
      - 11) Protection of existing facilities to remain and protection of completed work.
      - 12) All other related costs to complete the Project not specifically referenced in the bid tabulation.
  - 3. Executing any and all the requirements of utility companies and regulatory agencies as pertaining to the Work.
  - 4. Carrying out the work in compliance with the requirements set forth in the General Conditions, Supplementary Conditions, and the General Requirements.
  - 5. Unloading and suitably storing all Owner provided materials.
  - 6. Measurement: Lump Sum

7. Payment: This item will be payable in partial payments made monthly based on the percent complete status of the Contract as determined by the Owner/Engineer.

# B. Bid Item 2 – Site Preparation and Erosion Control:

- 1. The lump sum payment for this item includes but is not limited to all necessary equipment, material, and labor required for, installation and maintenance of erosion control products, construction and management of stockpiles, construction and maintenance of haul roads to and from areas under construction, and stockpiles.
- 2. Measurement: Lump Sum
- 3. Payment: Payment for this item will be made monthly based on the percentage of the work related to this item that is complete and approved by the Owner/Engineer at the time of the pay request, and as determined by the Record Documents.

## C. Bid Item 3 – Gas Control Wells:

## 1. Well Drilling and Installation

- a. Work includes, procurement, drilling, and installation of Gas Control Wells including casing pipe, stone, bentonite, and geotextile in all locations identified or described on the Drawings and Specifications. Work also includes monitoring air quality during drilling, staking and surveying, preparation and submittal of well construction forms, and disposal of drill cuttings.
- b. Measurement: Vertical Feet (based on bore depth as measured in the field by Owner/Engineer)
- c. Payment: Payment for this item will be made monthly until the completion of the item, based on the Vertical Feet installed of Gas Control Wells and approved by the Owner/Engineer.

### 2. Wellheads

- a. Work includes, procurement and installation of wellheads, flex hose, fittings, vault, vault cover, locking chain and pad lock, excavation and disposal of excavated spoils required for installation, and other appurtenances as required for a complete installation in all locations identified or described on the Drawings and Specifications.
- b. Measurement: Each
- c. Payment: Payment for this item will be made monthly, until the completion of the item, based on the number of completed wellhead installations as approved by the Owner/Engineer.

# D. Bid Item 4 – Piping:

- 1. Work includes, procurement and installation of 4" HDPE gas lateral piping, 6" HDPE gas header piping, HDPE condensate drains, valves, including all pipe, fittings, pipe supports, staking and surveying, pipe bedding, backfill, topsoil/base course/asphalt, disposal of excess trench spoils, and piping flushing and pressure testing required to be installed in all locations identified or described in the Drawings or Specifications.
- 2. Measurement: Lump Sum
- 3. Payment for this item will be made monthly based on the percentage of the work related to this item that is complete and approved by the Owner/Engineer at the time of the pay request, and as determined by the Record Documents.

# E. Bid Item 5 – Gas Monitoring Probes:

- 1. Gas monitoring probe drilling and installation
  - Work includes, procurement, drilling, and installation of Gas Monitoring Probes including casing pipe, stone, and bentonite, in all locations identified or described on the Drawings and Specifications. Work also includes monitoring air

- quality during drilling, surveying, preparation and submittal of gas probe construction forms, and disposal of drill cuttings.
- Measurement: Vertical Feet (based on bore depth as measured in the field by Owner/Engineer)
- c. Payment: Payment for this item will be made monthly until the completion of the item, based on the Vertical Feet installed of Gas Monitoring Probes and approved by the Owner/Engineer.

### 2. Methane sensors

- a. Work includes, procurement and installation of the methane sensors including piping, supports, electrical conduits, instrumentation wiring and connections from the sensors to the control panel, required to be installed in all locations identified or described in the Drawings and Specifications.
- b. Measurement: Each
- c. Payment: Payment of this item will be made monthly, until the completion of the item, based on the number of completed methane sensor installations as approved by the Owner/Engineer.

## F. Bid Item 6 – Blower, Instrumentation, and Controls:

- 1. Work includes, installation of the blower (purchased by Owner) including unloading, storing, placing, and securing of the blower; installation of the control panel, pressure sensor, and flow meter (to be procured by Others), and procurement and installation of conduits, power and instrumentation wiring, wiring connections, bumper posts, and all necessary concrete, excavation and backfill, and system startup and testing, required at the locations identified or described in the Drawings and Specifications.
- 2. Measurement: Lump Sump
- 3. Payment: Payment of this item will be made after completion of the blower installation and startup testing as approved by the Owner/Engineer.

## G. Bid Item 7 – Site Restoration:

- The lump sum payment for this item includes but is not limited to all necessary
  equipment, material, and labor required for, installation and maintenance of seed,
  fertilizer, and mulch in topsoil areas, and installation of asphalt over base course in the
  access road area, at the locations identified or described in the Drawings and
  Specifications.
- 2. Measurement: Lump Sum
- 3. Payment: Payment for this item will be made monthly based on the percentage of the work related to this item that is complete and approved by the Owner/Engineer at the time of the pay request, and as determined by the Record Documents.

## H. Alternate Bid Item 1 – Waste Material Handling:

- 1. Work includes separating, stockpiling, loading, hauling, and unloading waste materials at Dane County Landfill Site No. 2 (Rodefeld) that may be encountered during excavation, trenching, or drilling.
- 2. Measurement: Ton
- 3. Payment: Payment for this item will be made monthly based on the Tons of materials managed as approved by the Owner/Engineer at the time of the pay request, and as determined by the Record Documents.

# I. Alternate Bid Item 2 – Rock Excavation:

1. Work includes trenching through competent bedrock that may be encountered during gas header piping trenching as confirmed by the Owner/Engineer and that can reasonably be removed by mechanical means. Includes ripping, excavating, and offsite disposal of

- encountered bedrock as required to the depths and locations described in the Drawings and Specifications.
- 2. Measurement: Ton
- 3. Payment: Payment for this item will be made monthly based on the Tons of bedrock removed as approved by the Owner/Engineer at the time of the pay request, and as determined by the Record Documents.

# PART 2 PRODUCTS

Not Used

# SECTION 01650 SYSTEM STARTUP

### PART 1 GENERAL

#### 1.1 STARTING SYSTEMS

- A. Coordinate with Engineer/Owner and Controls Contractor, blower and variable frequency drive (VFD) vendors for startup of equipment.
- B. Notify Owner 7 days prior to system startup.
- C. Verify that each piece of equipment or system has been checked for proper drive rotation, control sequence, or other conditions, which may cause damage.
- D. Verify that tests, meter readings, and specified electrical characteristics agree with those required by the equipment or system manufacturer prior to equipment startup.
- E. Verify operation of control instrumentation in accordance with specifications.
- F. Verify wiring and support components for equipment are complete and tested.
- G. Execute startup under supervision of Owner/Controls Contractor.
- H. When specified in individual Sections, provide authorized representative to be present at site to inspect, check and approve equipment or system installation prior to startup, and to supervise placing equipment or system in operation.
- I. Adjust equipment to ensure smooth and unhindered operation.
- J. Demonstrate startup, operation, control, adjustment, trouble-shooting, servicing, maintenance, and shutdown of the system.
- K. Prepare and insert additional data in operations and maintenance manuals when need for additional data becomes apparent during installation.
- L. During startup, operation of the equipment will be varied through its available operating range to show that it is operating properly. Electrical current will be monitored during startup to show that the equipment is within its normal operating range and that the overload protection is working properly.

### **PART 2 PRODUCTS**

Not Applicable

PART 3 EXECUTION

Not Applicable

END OF SECTION

Bid No. 319006 System Startup

# SECTION 02200 EARTHWORK, TRENCHING, AND BACKFILLING

### PART 1 GENERAL

## 1.1 DESCRIPTION

A. Section includes trenching, excavating, placing, compacting, and grading of soil/aggregate materials; placing and compacting asphalt; and placing topsoil, seed, fertilizer, and mulch.

### 1.2 REFERENCES

- A. American Society for Testing and Materials (ASTM):
  - ASTM D1557 Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort
- B. State of Wisconsin Department of Transportation (WisDOT):
  - 1. Standard Specifications for Highway and Structure Construction, latest edition.

## 1.3 SUBMITTALS

- A. Submit granular bedding sample within 2 weeks of Project award.
- B. Submit 1/2-inch to 3/4-inch stone sample within 2 weeks of Project award.
- C. Submit base course sample within 2 weeks of Project award.
- D. Submit seed and fertilizer type and rate of application within 2 weeks of Project award.

## 1.4 QUALITY ASSURANCE

A. Owner will pay for and provide field density testing of compacted fill and laboratory testing of

## **PART 2 PRODUCTS**

## 2.1 GENERAL FILL

A. Clean soil from site cuts, or imported soil if required, that is free of debris, organic material, frozen material, and particles larger than 6 inches.

# 2.2 1/2-INCH TO 3/4-INCH STONE

A. Well graded mixture of rounded to subangular gravel with the following gradation: 1/2-inch to 3/4-inch as follows unless otherwise approved by Engineer/Owner.

Sieve Size	Percent Passing
1-inch	100
3/4-inch	90 to 100
1/2-inch	0 to 15
3/8-inch	0 to 5

## 2.3 PIPE BEDDING MATERIALS

A. Granular Bedding

1. Primarily sand-size particles with no particles larger than 1 ½ inch.

### 2.4 BASE COURSE

A. Crushed stone or gravel meeting WisDOT Section 305, 1 ¼-inch dense-graded base.

# 2.5 ASPHALT

A. WisDOT Section 460 mixture LT.

### 2.6 TOPSOIL, SEED, FERTILIZER, AND MULCH

- A. Topsoil:
  - 1. Topsoil salvaged from trenching, or imported topsoil meeting WisDOT Section 625.2 if required.
- B. Permanent Seeding:
  - 1. WisDOT Section 630 Seed Mix No. 20.
- C. Fertilizer:
  - 1. Meet the requirements of WisDOT Section 629 fertilizer Type A.
- D. Mulching:
  - 1. Wood excelsior fiber, paper fibers, or other suitable material of a similar nature which is substantially free of noxious weed seeds and objectionable foreign matter meeting WisDOT standard specifications.
  - 2. Mulch is not required where erosion matt is placed.

### PART 3 EXECUTION

# 3.1 INSPECTION

A. Examine the areas and conditions where Work will be performed, and notify the Owner in writing of conditions detrimental to the proper and timely completion of the Work. Do not proceed with the Work until unsatisfactory conditions have been corrected.

# 3.2 TRENCHING/EXCAVATION

- A. Gas Header/Lateral Pipe Installation:
  - 1. Trench/excavate to design grades as shown on Drawings.
- B. Condensate Drain Installation:
  - 1. Excavate to design grades as shown on Drawings.

# 3.3 FILL PLACEMENT AND GRADING

- A. Pipe Bedding Material:
  - 1. Place, grade, compact, and survey in accordance with Section 15067 Polyethylene Pipe and as shown on the Drawings.

## B. 1/2-inch -3/4-inch Stone:

1. Place as shown on Drawings. Compact stone around condensate drain using maximum 12-inch-thick lifts.

# C. General Fill:

1. Place as shown on the Drawings. Use soil from site cuts. Provide imported general fill as needed to supplement onsite material. Compact to a minimum of 95 percent of modified Proctor maximum dry density (ASTM D1557) in lift thicknesses of 12 inches or less.

### D. Base Course:

1. Place, grade, and compact as shown on Drawings. Compact to a minimum of 95 percent of modified Proctor maximum dry density (ASTM D1557) in lift thicknesses of 6 inches or less.

# E. Topsoil:

1. Place and grade as shown on Drawings. Use salvaged topsoil from site cuts. Provide imported topsoil as needed to supplement onsite topsoil. Do not compact topsoil material.

## 3.4 ASPHALT

A. Place in accordance with WisDOT Section 460.

## 3.5 GRASSED AREA RESTORATION

A. Place topsoil, seed, fertilizer and mulch to maximize the germination and viability of the grass seed, and minimize the soil and seed loss due to erosion.

## B. Topsoil:

1. Place topsoil over disturbed areas as shown on Drawings.

## C. Permanent Seed:

- 1. Follow the seeding rate as described in WisDOT Section 630.3.3.5.1 right-of-way seeding.
- 2. Place seed in accordance with WisDOT standard specifications.

## D. Fertilizer:

1. Apply as recommended and in accordance with WisDOT standard specifications.

## E. Mulch:

- 1. Place in accordance with WisDOT standard specifications.
- 2. Maintain the mulched areas and repair any areas damaged by wind, erosion, traffic, fire or other causes prior to final acceptance of Work under the contract.

## 3.6 DISPOSAL OF TRENCH SPOILS

A. Remove and dispose of excess trench spoils in a timely manner as materials are extracted. Dispose of cuttings at location(s) approved by Owner.

B. If waste materials are encountered, separate and store onsite until waste characterization is completed. Transport and dispose at the Dane County Landfill Site No. 2 (Rodefeld) as directed by Owner.

# SECTION 02270 EROSION CONTROL

### PART 1 GENERAL

#### 1.1 **DESCRIPTION**

Section includes silt fence. A.

#### 1.2 REFERENCES

- A. Wisconsin Department of Natural Resources (WDNR):
  - 1. Conservation Practice Standard, latest edition.

#### 1.3 **QUALITY ASSURANCE**

#### A. General:

Repair any areas damaged by erosion for a period of 1 year following completion of 1. restoration activities.

#### 1.4 **SUBMITTALS**

- A. Submit silt fence identification and material specifications 2 weeks prior to installation.
- B. Submit in accordance with Section 01001, Basic Requirements.

## **PART 2 PRODUCTS**

#### 2.1 SILT FENCE

A. Conform to WDNR Silt Fence Standard (1056).

# PART 3 EXECUTION

#### 3.1 **INSPECTION**

Examine the areas and conditions where Work will be performed and notify Owner in writing of A. conditions detrimental to proper and timely completion of Work. Do not proceed with Work until unsatisfactory conditions have been corrected.

#### 3.2 SILT FENCE INSTALLATION AND MAINTENANCE

- Install according to WDNR Silt Fence Standard (1056). A.
- B. Overlap ends of silt fence at joints for a length equal to distance between two stakes.
- C. Inspect silt fence within 24 hours after each rainfall.
- D. Repair or replace if silt fence is torn, sagging, overtopped, blown over (laying down), or in any way is not functioning for sediment containment.
- E. Remove sediment when sediment deposits reach no more than one half of silt fence height.

# END OF SECTION

Bid No. 319006 **Erosion Control** 

# SECTION 02665 GAS MONITORING PROBES

### PART 1 GENERAL

### 1.01 SUMMARY

A. Gas monitoring probes.

### 1.02 HAZARDOUS ENVIRONMENT

A. Work under this Section includes drilling next to an existing municipal solid waste landfill. While there is no specific knowledge that refuse will be encountered, HAZARDOUS SUBSTANCES INCLUDING METHANE GAS MAY BE ENCOUNTERED DURING DRILLING. Contractor shall comply with applicable laws and regulation concerning such substances and shall be responsible for recognizing potentially hazardous situations.

## 1.03 SUBMITTALS

A. Provide gas monitoring probe drilling and construction logs after construction and prior to final acceptance per Section 01001, Basic Requirements.

### 1.04 QUALITY ASSURANCE

A. A professional geologist or qualified technician who is directly supervised by a professional geologist must observe and direct the drilling and installation of all probes.

# PART 2 PRODUCTS

## 2.01 CASING PIPE

 As depicted on Drawings. Comply with provisions of Section 15051 – PVC Pipe for pipe materials.

### 2.02 METHANE SENSORS

A. Refer to Section 16912 – Field Instruments.

# 2.03 1/2-INCH TO3/4-INCH STONE

A. Refer to Section 02200 – Earthwork, Trenching, and Backfilling.

### 2.04 BENTONITE

A. Bentonite chips or pellets.

### PART 3 EXECUTION

## 3.01 PREPARATION

- A. Confirm location and depth of gas monitoring probes with Engineer/Owner prior to drilling.
- B. Notify Owner at least 48 hours prior to drilling.
- C. Stake locations of gas monitoring probes at least 24 hours prior to drilling. Include gas monitoring probe number, existing ground surface elevation, and drill depth on stake.

### 3.02 GAS PROBE INSTALLATION

- A. Drill hole of diameter and to elevation shown on Drawings.
- B. Monitor air quality in vicinity of borehole while drilling.
- C. Install piping in drill hole in accordance with Section 15051 PVC Pipe.
- D. Backfill drill hole with materials as shown on Drawings and as specified in presence of Engineer/Owner. Place stone in a manner which will not damage pipe during backfilling operations. Monitor quantity of backfill during placement to evaluate potential for stone bridging in borehole. Measure and record depths and quantities of stone and bentonite. Hydrate bentonite and allow bentonite to set up in accordance with manufacturer's recommendations prior to completing successive backfilling operations.
- E. Construct to elevations provided on Drawings.
- F. Do not leave boreholes open overnight unless approved by Owner.
- G. Complete gas monitoring probe construction forms to document elevation of bottom of borehole, bottom of gas monitoring probe, top of screen, top of stone, top of seal, ground surface, and top of probe. Document gas monitoring probe coordinates, borehole diameter, probe diameter, probe screen and casing material, stone material, and seal material on probe construction forms.

### 3.03 DISPOSAL OF DRILLING SPOILS

- A. Provide control of drill cuttings from borehole during drilling. Remove and dispose of cuttings in a timely manner as materials are extracted. Dispose of cuttings at location(s) approved by Owner.
- B. If waste materials are encountered, separate and store onsite until waste characterization is completed. Transport and dispose at the Dane County Landfill Site No. 2 (Rodefeld) as directed by Owner.

# SECTION 02693 GAS CONTROL WELLS

### PART 1 GENERAL

## 1.01 SUMMARY

A. Gas control wells.

### 1.02 HAZARDOUS ENVIRONMENT

A. Work under this Section includes drilling next to an existing municipal solid waste landfill. While there is no specific knowledge that refuse will be encountered, HAZARDOUS SUBSTANCES MAY BE ENCOUNTERED INCLUDING METHANE GAS DURING DRILLING. Contractor shall comply with applicable laws and regulation concerning such substances, and shall be responsible for recognizing potentially hazardous situations.

## 1.03 SUBMITTALS

A. Provide well drilling and construction logs after construction and prior to final acceptance per Section 01001, Basic Requirements.

### **PART 2 PRODUCTS**

### 2.01 CASING PIPE

A. As depicted on drawings. Comply with provisions of Section 15051 – PVC Pipe for pipe materials.

# 2.02 1/2-INCH TO 3/4-INCH STONE

A. Refer to Section 02200 – Earthwork, Trenching, and Backfilling.

# 2.04 BENTONITE

A. Baroid "Benseal" or approved equal.

# 2.05 GEOTEXTILE

A. Nonwoven polypropylene, polyethylene, polyamide, or polyester; 12 ounce geotextile.

# 2.06 WELLHEAD VAULT

- A. Vault: ADS N-12 pipe as shown on the Drawings.
- B. Cover: Taylor-Made HDPE cover.
- C. Locking Chain and Pad Lock: steel, rust proof, suitable for outdoor use

## PART 3 EXECUTION

## 3.01 PREPARATION

- A. Confirm location and depth of gas control wells with Owner prior to drilling.
- B. Notify Engineer/Owner at least 48 hours prior to drilling.

Bid No. 319006 Gas Control Wells

C. Stake locations of gas control wells at least 24 hours prior to drilling. Include gas control well number, existing ground surface elevation, and drill depth on stake.

#### 3.02 WELL INSTALLATION

- Drill hole of diameter and to elevation shown. A.
- B. Monitor air quality in vicinity of borehole while drilling.
- C. Install piping in drill hole in accordance with Section 15051.
- D. Backfill drill hole with materials as shown and as specified in presence of Owner. Place stone in a manner which will not damage pipe during backfilling operations. Monitor quantity of stone backfill during placement to evaluate potential for stone bridging in borehole. Measure and record depths and quantities of stone and bentonite. Hydrate bentonite and allow bentonite to set up in accordance with manufacturer's recommendations prior to completing successive backfilling operations.
- E. Construct to elevations provided on Drawings.
- F. Do not leave boreholes open overnight unless approved by Owner.
- G. Survey to document that pipes are placed at specified locations and grades, and in specified configuration. Bring deviations from plans and specifications to attention of Owner for evaluation of necessity of corrective action.
- H. Complete well construction forms to document elevation of bottom of borehole, bottom of well, top of screen, top of stone, top of seal, ground surface, and top of well. Document well coordinates, borehole diameter, well diameter, well screen and casing material, stone material, and seal material on well construction forms.

#### 3.03 DISPOSAL OF DRILLING SPOILS

- A. Provide control of drill cuttings from borehole during drilling. Remove and dispose of cuttings in a timely manner as materials are extracted. Dispose of cuttings at locations(s) approved by Owner.
- В. If waste materials are encountered, separate and store onsite until waste characterization is completed. Transport and dispose at the Dane County Landfill Site No. 2 (Rodefeld) as directed by Owner.

END OF SECTION

Bid No. 319006 Gas Control Wells

## SECTION 15051 PVC PIPE

# PART 1 GENERAL

#### 1.1 WORK INCLUDED

A. PVC to be used for gas control wells and gas monitoring probes.

#### 1.2 **REFERENCES**

- American Society for Testing and Materials (ASTM). A.
  - 1. ASTM D1785 - Standard Specification for PVC Plastic Pipe, Schedules 40, 80, and 120.

#### 1.3 **QUALITY ASSURANCE**

- Store pipe on site in a manner suitable to protect it from long-term ultraviolet light exposure prior A. to installation.
- B. Owner will observe pipe to confirm that pipe is of specified size and schedule, manufactured of specified material, and has pipe perforations sized and spaced as specified. Remove rejected/damaged pipe from work area.
- C. Bring deviations from plans and specifications to attention of Owner to evaluate necessity of corrective action.

#### **SUBMITTALS** 1.4

Submit cut sheet of the piping perforations and piping manufacturer. A.

## **PART 2 PRODUCTS**

2.1 Provide PVC piping as specified on the Drawings.

# PART 3 EXECUTION

#### 3.1 **INSTALLATION**

Install PVC piping in accordance with the manufacturer's recommendations and as shown on A. Drawings.

#### 3.2 **SURVEYING**

Locate as shown on Drawings. Survey to record location and elevation of pipes. A.

# **END OF SECTION**

Bid No. 319006 **PVC** Pipe

## **SECTION 15067** POLYETHYLENE PIPE

## PART 1 GENERAL

#### 1.1 **WORK INCLUDED**

High Density Polyethylene Pipe (HDPE) to be used as gas collection piping. A.

#### 1.2 **REFERENCES**

- A. American Society for Testing and Materials (ASTM).
  - ASTM D3261 Standard Specification for Butt Heat Fusion Polyethylene (PE) Plastic 1. Fittings for PE Plastic Pipe, and Tubing.
  - ASTM D3350 Standard Specification for Polyethylene Plastics Pipe and Fittings 2. Materials.
  - ASTM D4976 Standard Specification for Polyethylene Plastics Molding and Extrusion 3. Materials.

### **QUALITY ASSURANCE** 1.3

- Store pipe on site in a manner suitable to protect it from long-term ultraviolet light exposure prior A. to installation.
- B. Owner will observe pipe to confirm that pipe is of specified size and dimension ratio, and manufactured of specified material. Remove rejected/damaged pipe from work area.
- C. Bring deviations from plans and specifications to attention of Owner to evaluate necessity of corrective action.

#### 1.4 **SUBMITTALS**

- A. Submit cut sheet of the piping manufacturer.
- B. Submit as-built survey data for piping, including Northing, Easting, and Elevation in accordance with Section 3.3.A below.

## **PART 2 PRODUCTS**

#### 2.1 HDPE PIPE

- A. Provide HDPE piping as specified on the Drawings.
- B. Provide pipe made from extra high molecular weight (EHMW) PE resin having a cell classification of 445574 (PE 4710) as defined by ASTM D3350. Provide pipe free of paint or other surface treatment. Size and SDR per Drawings. Fittings to be molded unless otherwise approved by Owner.

#### 2.2 **VALVES**

Butterfly valves: Corrosion-resistant thermoplastic butterfly valve rated for 150 psi compatible A. with HDPE and PVC pipe. Provide nitrile seats and seals.

# PART 3 EXECUTION

#### **PREPARATION** 3.1

A. Ream pipe and tube ends. Remove burns.

Bid No. 319006 Polyethylene Pipe 15067 - 1

- В. Remove dirt and foreign material, inside and outside, from pipe and fitting materials before assembly.
- C. Make straight field cuts without chipping or cracking pipe.

#### 3.2 **INSTALLATION**

- Install polyethylene piping in accordance with the manufacturer's recommendations and as shown A. on Drawings.
- В. Make pipe connections with butt fusion procedure (ASTM D3261). Confirm that adequate pressures are used for fusing pipes and that sufficient cooling periods are allowed prior to testing, bending, or backfilling pipe sections.
- C. Allow Owner to observe temperature of welding equipment, pipe cleaning procedure, weld bead sizes, heat and cooling times, fusing pressures, and hold pressure.
- D. Do not place piping in presence of excessive moisture.
- E. Lay pipe from low end toward high point. Provide continuous smooth invert. Consult with Owner if adjustments to inverts are required at connections to existing pipe. Tape or otherwise seal open pipe ends when handling on site to minimize potential for debris to enter pipe.
- F. Bed and backfill pipe in accordance with Section 02200 and as shown on Drawings. Allow Owner to observe pipe alignment and joints prior to backfilling. Shovel slice pipe bedding or compact pipe bedding to spring line of pipe to provide proper bedding.

#### 3.3 SURVEYING

- Locate as shown on Drawings. Survey to record location and elevation of pipes and submit per A. Section 01001, Basic Requirements. Document pipe elevations every 25 linear feet by survey or every 50 feet if elevations are set using a total station or laser equipment, as well as at key points, including changes in grade, at fittings, at intersections, and at endpoints.
- B. Minimum allowable tolerance for pipe grade is 0.10 foot at each location. Maintain minimum pipe slope as shown on Drawings.

#### PIPE CLEANING 3.4

Jet clean pipe with water using sewer-cleaning equipment. Give 48-hour notice to Owner prior to A. testing. Remove obstructions as necessary and repeat tests as required until satisfactory results are obtained.

#### 3.4 PIPE PRESSURE TESTING

- Pressure test solid-wall pipe, fittings, and appurtenances. Mechanically plug line to be tested. A. Pressure line to 5 pounds per square inch (psi) (gauge pressure). Close valve on pressurizing unit, and monitor pressure for a minimum of 60 minutes. After 60 minutes, a temperature-corrected system pressure drop of 1 percent or less shall be considered acceptable.
- B. Perform test during period when pipe segment will be out of direct sunlight to minimize pressure changes as a result of temperature fluctuations.
- C. Perform leakage and pressure tests in presence of Owner. Give 48-hour notice to Owner prior to testing. Prepare and submit a written report for each test. Provide gauges, pumps, pipe, connections, and other necessary apparatus to conduct tests.
- If results of tests performed do not conform to specified requirements, make necessary repairs and D. repeat tests as required until satisfactory results are obtained.

Bid No. 319006 Polyethylene Pipe

# END OF SECTION

Bid No. 319006 Polyethylene Pipe 15067 - 3

# SECTION 16050 GENERAL ELECTRICAL REQUIREMENTS

## PART 1 GENERAL

### 1.1 DESCRIPTION

- A. Provide and install conduits and wiring from Generator Building to control panel and blower.
- B. Provide and install light and duplex receptacle.
- C. Provide and install conduits and wiring from control panel to methane sensors.
- D. Provide and install conduits and wiring from control panel to blower area sensors.

# 1.2 GENERAL REQUIREMENTS

- A. Identify applicable requirements prior to submitting a bid and include the cost of any required revisions to the Specifications with the base bid.
- B. All electrical components shall be UL listed.

# **PART 2 PRODUCTS**

# 2.1 ELECTRICAL SERVICE

A. Size as specified on the Drawings.

# 2.2 LIGHT

- A. Provide one (1) light, suitable for installation in an outdoor setting.
- B. 125V, 3000 lumen LED or equivalent.
- C. Dusk to dawn sensor/operation.

## 2.3 DUPLEX RECEPTACLE

A. 125V, 20 amp duplex GFCI receptacle in a weatherproof enclosure.

## 2.4 ADDITIONAL ELECTRICAL SUPPLIES

A. Provide additional electrical supplies as needed to provide a complete installation in accordance with state and local code requirements.

## PART 3 EXECUTION

## 3.1 INSTALLATION

A. Perform all Work in accordance with state and local codes.

# SECTION 16912 FIELD INSTRUMENTS

# PART 1 GENERAL

#### 1.1 **SUMMARY**

A. This section describes the requirements of field-mounted instruments.

### **SUBMITTALS** 1.2

- Submit product data including operation and maintenance data 21 days after award of contract. A.
- B. Submit in accordance with Section 01001, Basic Requirements.

# **PART 2 PRODUCTS**

#### 2.1 **METHANE SENSORS**

- A. Ultima XE Main Methane Sensor, model no.: A-ALTIMA-X-XP-E-38-U-3-S-0-0-0-0-1-0-0
- B. Tag Nos. CH4 101, CH4 102, CH4 103, CH4 104, CH4 105

#### 2.2 FLOW METER

- A. Endress + Hauser: Proline t-mass 65I Thermal mass flowmeter
- B. Or approved equivalent
- C. Tag No. FIT 100

#### 2.3 PRESSURE SENSOR

- Endress + Hauser: A. PMC71 Pressure Transmitter
- B. Or approved equivalent
- C. Tag No. PIT 100

## PART 3 EXECUTION

### 3.1 **INSTALLATION**

Install equipment in accordance with manufacturer's recommendations and make all electrical and A. piping connections.

# END OF SECTION

Bid No. 319006 Field Instruments