

CONSTRUCTION DOCUMENTS PROJECT MANUAL

DANE COUNTY DEPARTMENT OF PUBLIC WORKS, HIGHWAY AND TRANSPORTATION

PUBLIC WORKS ENGINEERING DIVISION 1919 ALLIANT ENERGY CENTER WAY MADISON, WISCONSIN 53713

REQUEST FOR BIDS NO. 320002 CFS PHOTOVOLTAIC ARRAY DANE COUNTY CONSOLIDATED FOOD SERVICE BUILDING 1000 EAST VERONA AVENUE VERONA, WISCONSIN

Due Date / Time: TUESDAY, AUGUST 11, 2020 / 2:00 P.M. Location: PUBLIC WORKS OFFICE

Performance / Payment Bond: 100% OF CONTRACT AMOUNT Bid Deposit: 5% OF BID AMOUNT

FOR INFORMATION ON THIS REQUEST FOR BIDS, PLEASE CONTACT:

ERIC URTES, AIA, PROJECT MANAGER TELEPHONE NO.: 608/266 FAX NO.: 608/267-1533

E-MAIL: urtes.eric@countyofdane.com

SECTION 00 01 10

TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

- 00 01 01 Project Manual Cover Page
- 00 01 10 Table of Contents
- 00 11 16 Invitation to Bid
- 00 21 13 Instructions to Bidders
- 00 41 13 Bid Form
- 00 52 96 Sample Public Works Construction Contract
- 00 61 12 Sample Bid Bond
- 00 61 13.13 Sample Performance Bond
- 00 61 13.16 Sample Payment Bond
- 00 72 13 General Conditions of Contract
- 00 73 00 Supplementary Conditions
- 00 73 07 Best Value Contracting Application
- 00 73 11 Fair Labor Practices Certification

DIVISION 01 - GENERAL REQUIREMENTS

- 01 00 00 General Requirements
- 01 74 19 Construction Waste Management, Disposal & Recycling

DIVISION 26 - ELECTRICAL

- 26 05 00 Common Work Results for Electircal
- 26 05 04 Cleaning, Inspection, and Testing of Electrical Equipment
- 26 05 19 Low Voltage Electrical Power Conductors and Cable
- 26 05 26 Grounding and Bonding for Electrical Systems
- 26 05 29 Hangers and Supports for Electrical Systems
- 26 05 33 Raceways and Boxes for Electrical Systems
- 26 24 16 Panelboards
- 26 27 28 Disconnect Switches
- 26 31 00 Photovoltaic Collectors

DRAWINGS

- T100 Title Sheet
- E100 Schedules, Abbreviations, and Legend
- E101 Lower Level Floor Plan Electrical
- E102 First Floor Plan Electrical
- E103 Roof Plan Electrical
- E401 Electrical One-Line Diagram

END OF SECTION

RFB No. 320002 Table of Contents rev. 10/19 00 01 10 - 1

SECTION 01 11 16

INVITATION TO BID

LEGAL NOTICE

Dane County Dept. of Public Works, Hwy & Transp., 1919 Alliant Energy Center Way, Madison, WI 53713, will receive sealed Bids until:

2:00 P.M., TUESDAY, AUGUST 11, 2020 <u>RFB NO. 320002</u>

CFS PHOTOVOLTAIC ARRAY DANE COUNTY CONSOLIDATED FOOD SERVICE BUILDING 1000 EAST VERONA AVENUE, VERONA, WI

Dane County is inviting Bids for construction services for a photovoltaic array on the roof of the Dane County Consolidated Food Service Building. Only firms with capabilities, experience & expertise with similar projects should obtain this Request for Bids (RFB) document & submit Bids.

RFB document may be obtained after **2:00 p.m. on July 16,** 2020 by downloading it from <u>bids-pwht.countyofdane.com</u>. Please call Eric Urtes, AIA, Project Mgr., at 608/266-4798, or our office at 608/266-4018, for any questions or additional information.

All Bidders must be qualified as a Best Value Contractor before Bid Due Date / Time. Complete Pre-qualification Application for Contractors at <u>publicworks.countyofdane.com/bvc</u> or obtain one by calling 608/267-0119.

A pre-bid site tour will be held July 28, 2020 at 10:00 a.m. at the Dane County Consolidated Food Service Building. Bidders are strongly encouraged to attend this tour.

PUBLISH: JULY 14 & JULY 21, 2020 - WISCONSIN STATE JOURNAL JULY 13 & JULY 20, 2020 - THE DAILY REPORTER

END OF SECTION

RFB No. 320002 Invitation to Bid rev. 07/2020 00 11 16 - 1

SECTION 00 21 13

INSTRUCTIONS TO BIDDERS

TABLE OF CONTENTS

1. GENERAL	. 1
2. DRAWINGS AND SPECIFICATIONS	1
3. INTERPRETATION	
4. QUALIFICATIONS OF BIDDER (CONTRACTOR AND SUBCONTRACTOR)	2
5. BID GUARANTEE	3
6. WITHDRAWAL OF BIDS	3
7. CONTRACT FORM	3
8. CONTRACT INTERESTS BY COUNTY PUBLIC OFFICIALS	3
9. EMERGING SMALL BUSINESS PROVISIONS	
10. METHOD OF AWARD - RESERVATIONS	6
11. SECURITY FOR PERFORMANCE AND PAYMENTS	6
12. TAXES	6
13. SUBMISSION OF BIDS	7
14. SUBCONTRACTOR LISTING	
15. ALTERNATE BIDS	7
16. INFORMATIONAL BIDS	
17. UNIT PRICES	8
18. COMMENCEMENT AND COMPLETION	8
19. WORK BY OWNER	
20. SPECIAL HAZARDS COVERAGE	8
FORM A	9
FORM B	10
FORM C	11
FORM D	12

1. GENERAL

- A. Before submitting Bid, bidder shall thoroughly examine all Construction Documents. Successful Bidder shall be required to provide all the Work that is shown on Drawings, set forth in Specifications, or reasonably implied as necessary to complete Contract for this project.
- B. Bidder shall visit site to become acquainted with adjacent areas, means of approach to site, conditions of actual site and facilities for delivering, storing, placing, and handling of materials and equipment.
- C. Pre-bid meeting is scheduled on July 28, 2020 at 10:00 a.m. at the Dane County Consolidated Food Service building, 1000 Verona Avenue, Verona. Attendance by all bidders is optional, however bidders and subcontractors are strongly encouraged to attend.
- D. Failure to visit site or failure to examine any and all Construction Documents will in no way relieve successful Bidder from necessity of furnishing any necessary materials or equipment, or performing any work, that may be required to complete the Work in accordance with Drawings and Specifications. Neglect of above requirements will not be accepted as reason for delay in the Work or additional compensation.

2. DRAWINGS AND SPECIFICATIONS

- A. Drawings and Specifications that form part of this Contract, as stated in Article 1 of General Conditions of Contact, are enumerated in Document Index of these Construction Documents.
- B. Complete sets of Drawings and Specifications for all trades will be available to all Bidders, irrespective of category of work to be bid on, in order that all Bidders may be familiar with work of other trades as they affect their bid.

3. INTERPRETATION

- A. No verbal explanation or instructions will be given in regard to meaning of Drawings or Specifications before Bid Due Date. Bidders shall bring inadequacies, omissions or conflicts to Owner or Architect / Engineer's attention at least ten (10) calendar days before Bid Due Date. Prompt clarification will be available to all bidders by Addendum.
- B. Failure to so request clarification or interpretation of Drawings and Specifications will not relieve successful Bidder of responsibility. Signing of Contract will be considered as implicitly denoting that Contractor has thorough understanding of scope of the Work and comprehension of Construction Documents.
- C. Owner or Architect / Engineer will not be responsible for verbal instructions.

4. QUALIFICATIONS OF BIDDER (CONTRACTOR AND SUBCONTRACTOR)

- A. Before award of Contract can be approved, Owner shall be satisfied that Bidder involved meets following requirements:
 - 1. Has completed at least one (1) project of at least fifty percent (50%) of size or value of Division of work being bid and type of work completed is similar to that being bid. If greater magnitude of experience is deemed necessary, other than size or value of work, such requirements will be described in appropriate section of Specifications.
 - 2. Maintains permanent place of business.
 - 3. Can be bonded for terms of proposed Contract.
 - 4. Has record of satisfactorily completing past projects. Criteria which will be considered in determining satisfactory completion of projects by bidder will include:
 - a. Completed contracts in accordance with drawings and specifications.
 - b. Diligently pursued execution of work and completed contracts according to established time schedule unless Owner grants extensions.
 - c. Fulfilled guarantee requirements of construction documents.
 - d. Is not presently on ineligible list maintained by County's Department of Administration for noncompliance with equal employment opportunities and affirmative action requirements.
 - e. Authorized to conduct business in Wisconsin. By submitting Bid, bidder warrants that it has: complied with all necessary requirements to do business in State of Wisconsin; that persons executing contract on its behalf are authorized to do so; and, if corporation, that name and address of bidder's registered agent are as set forth in Contract. Bidder shall notify Owner immediately, in writing, of any change in its registered agent, their address, and bidder's legal status. For partnership, term "registered agent" shall mean general partner.

B. County's Public Works Project Manager will make such investigations as are deemed necessary to determine ability of bidder to perform the Work, and bidder shall furnish to County's Public Works Project Manager or designee all such information and data for this purpose as County's Public Works Project Manager may request. Owner reserves right to reject Bid if evidence submitted by, or investigation of, bidder fails to satisfy Owner that bidder is responsible and qualified to carry out obligations of Contract and to complete the Work contemplated therein.

5. BID GUARANTEE

- A. Bank certified check, cashier's check or Bid Bond, payable to County in amount not less than five percent (5%) of maximum bid, shall accompany each Bid as guarantee that if Bid is accepted, Bidder will execute and return proposed Contract and Performance and Payment Bonds within ten (10) business days after being notified of acceptance of Bid. Company issuing bonds must be licensed to do business in Wisconsin.
- B. Any bid, which is not accompanied by bid guarantee, will be considered "No Bid" and will not be read at Bid Due Date.
- C. If successful Bidder so delivers Contract, Certificate of Insurance, and Performance and Payment Bonds, check will be returned to Bidder. In case Bidder fails to deliver such Contract, insurance, and bond, amount of bid guarantee will be forfeited to County as liquidated damages.
- D. All checks tendered as bid guarantee, except those of three (3) lowest qualified, responsible bidders, will be returned to their makers within three (3) business days after Bid Due Date. All such retained checks will be returned immediately upon signing of Contract and Performance and Payment Bonds by successful Bidder.

6. WITHDRAWAL OF BIDS

- A. Bids may be withdrawn by written request received from bidder or authorized representative thereof prior to time fixed for Bid Due Date, without prejudice to right of bidder to file new Bid. Withdrawn Bids will be returned unopened. Negligence on part of bidder in preparing their Bid confers no right for withdrawal of Bid after it has been opened.
- B. No Bid may be withdrawn for period of sixty (60) calendar days after Bid Due Date.
- C. If Bid contains error, omission or mistake, bidder may limit liability to amount of bidder's guarantee by giving written Notice of Intent not to execute Contract to Owner within seventy-two (72) hours of Bid Due Date.

7. CONTRACT FORM

A. Sample copy of contract that successful Bidder will be required to enter into is included in these Construction Documents and bidders are required to familiarize themselves with all conditions contained therein.

8. CONTRACT INTERESTS BY COUNTY PUBLIC OFFICIALS

A. In accordance with Wisconsin Statute 946.13, county official may not bid for or enter into any contract involving receipts or disbursements of more than \$15,000.00 in a year, in which they have private pecuniary interest, direct or indirect if at same time they are authorized to

take official action with respect to making of this Contract. Any contract entered into in violation of this Statute is void and County incurs no liability thereon. This subsection does not affect application and enforcement of Wisconsin Statute 946.13 by state prosecutors in criminal courts of this state.

9. EMERGING SMALL BUSINESS PROVISIONS

- A. Emerging Small Business Definition. For purposes of this provision, ESB is defined as:
 - 1. Independent business concern that has been in business minimum of one year;
 - 2. Business located in State of Wisconsin;
 - 3. Business comprised of less than twenty-five (25) employees;
 - 4. Business must not have gross sales in excess of three million dollars (\$3,000,000.00) over past three years; and
 - 5. Business does not have history of failing to complete projects.
- B. Emerging Small Business (ESB) Involvement. Bidder shall make good faith effort to award minimum of ten percent (10%) of the Work to ESBs. Bidder shall submit report to Dane County Contract Compliance Specialist within ten (10) business days of Bid Due Date demonstrating such efforts. Good faith efforts means significant contact with ESBs for purposes of soliciting bids from them. Failure to make or demonstrate good faith efforts will be grounds for disqualification.
- C. **Emerging Small Business Report.** Emerging Small Business Enterprise Report is to be submitted by Bidder in separate envelope marked "Emerging Small Business Report". This report is due by 2:00 p.m. following specified ten (10) business days after Bid Due Date. Bidder who fails to submit Emerging Small Business Report shall be deemed not responsive.
- D. **ESB Goal.** Goal of this project is ten percent (10%) ESB participation. ESB utilizations are shown as percentage of total Bid. If Bidder meets or exceeds specified goal, Bidder is only required to submit Form A Certification, and Form B Involvement. Goal shall be met if Bidder qualifies as ESB.
- E. **Report Contents.** Following award of Contract, Bidder shall submit copies of executed contracts for all Emerging Small Businesses. Emerging Small Business Report shall consist of these:
 - 1. Form A Certification;
 - 2. Form B Involvement;
 - 3. Form C Contacts;
 - 4. Form D Certification Statement (if appropriate); and
 - 5. Supportive documentation (i.e., copies of correspondence, telephone logs, copies of advertisements).
- F. ESB Listing. Bidders may solicit bids from this ESB listing: pdf.countyofdane.com/commissions/2013-2015_Targeted_Business_Directory.pdf.

- G. **ESB Certification.** All contractors, subcontractors and suppliers seeking ESB certification must complete and submit Emerging Small Business Report to Dane County Contract Compliance Program.
- H. **Certification Statement.** If ESB firm has not been certified by County as ESB prior to submittal of this Bid, ESB Report cannot be used to fulfill ESB goal for this project unless firm provides "Form D Certification Statement". Certification statement must be completed and signed by ESB firm.
- I. Questions. Questions concerning Emerging Small Business provisions shall be directed to:

Dane County Contract Compliance Specialist City-County Building, Room 356 210 Martin Luther King, Jr. Blvd. Madison, WI 53703 608/266-4192

- J. Substituting ESBs. In event of any significant changes in subcontract arrangements or if need arises to substitute ESBs, Bidder shall report such proposed changes to Contract Compliance Specialist to making any official changes and request authorization to substitute ESB firm. Bidder further agrees to make every possible effort to replace ESB firm with another qualified ESB firm.
- K. **Good Faith Efforts.** Good faith efforts can be demonstrated by meeting all of these obligations:
 - 1. Selecting portions of the Work to be performed by ESBs in order to increase likelihood of meeting ESB goal including, where appropriate, breaking down Contract into smaller units to facilitate ESB participation.
 - 2. Advertising in general circulation, trade associations and women / minority focus media concerning subcontracting opportunities.
 - 3. Providing written notices to reasonable number of specific ESBs that their interest in Contract was being solicited in sufficient time to allow ESBs to participate effectively.
 - 4. Following up on initial solicitations of interest by contacting ESBs within five (5) business days prior to Bid Due Date to determine with certainty whether ESB were interested, to allow ESBs to prepare bids.
 - 5. Providing interested ESB with adequate information about Drawings, Specifications and requirements of Contract.
 - 6. Using services of available minority, women and small business organizations and other organizations that provide assistance in recruitment of MBEs / WBEs / ESBs.
 - 7. Negotiating in good faith with interested ESBs, not rejecting ESBs as unqualified without sound reason based on thorough investigation of their capabilities.
 - 8. Submitting required project reports and accompanying documents to County's Contract Compliance Specialist within twenty-four (24) hours after Bid Due Date.
- L. **Appeals Disqualification of Bid.** Bidder who is disqualified may appeal to Public Works & Transportation Committee and Equal Opportunity Commission.

10. METHOD OF AWARD - RESERVATIONS

- A. Following will be basis of award of Contract, providing cost does not exceed amount of funds then estimated by County as available to finance Contract(s):
 - 1. Lowest dollar amount submitted by qualified responsible bidder on Base Bid for all work comprising project, combined with such additive Owner accepted alternates.
 - 2. Owner reserves right to reject all bids or any bid, to waive any informality in any bid, and to accept any bid that will best serve interests of County.
 - 3. Unit Prices and Informational Bids will not be considered in establishing low bidder.

11. SECURITY FOR PERFORMANCE AND PAYMENTS

- A. Simultaneous with delivery of signed Contract, Bidder shall be required to furnish Performance and Payment Bonds as specified in Article 29 of General Conditions of Contract, "Contract Security". Surety Company shall be licensed to do business in Wisconsin. Performance and Payment Bonds must be dated same date or subsequent to date of Contract. Performance and Payment Bonds must emulate information in Sample Performance and Payment Bonds in Construction Documents.
- B. Provide certified copy of power of attorney from Surety Company showing that agent who signs Bond has power of attorney to sign for Surety Company. Secretary or Assistant Secretary of company must sign this certification, not attorney-in-fact. Certification must bear same or later date as Bond. Power of Attorney must emulate model power of attorney information detailed in Sample Performance and Payment Bonds.
- C. If Bidder is partnership or joint venture, State certified list, providing names of individuals constituting partnership or joint venture must be furnished. Contract itself may be signed by one partner of partnership, or one partner of each firm comprising joint venture, but Performance and Payment Bonds must be signed by all partners.
- D. If Bidder is corporation, it is necessary that current certified copy of resolution or other official act of directors of corporation be submitted showing that person who signs Contract is authorized to sign contracts for corporation. It is also necessary that corporate seal be affixed to resolution, contract, and performance and payment bonds. If your corporation has no seal, it is required that above documents include statement or notation to effect that corporation has no seal.

12. TAXES

- A. Wisconsin Statute 77.54 (9m) allows building materials that become part of local unit government facilities to be exempt from sales & use tax. Vendors & materials suppliers may not charge Bidders sales & use tax on these purchases. This does not include highways, streets or roads. Any other Sales, Consumer, Use & other similar taxes or fees required by law shall be included in Bid.
- B. In accordance with Wisconsin Statute 71.80(16)(a), successful nonresident bidder, whether incorporated or not, and not otherwise regularly engaged in business in this state, shall file surety bond with State of Wisconsin Department of Revenue payable to Department of Revenue, to guarantee payment of income taxes, required unemployment compensation contributions, sales and use taxes and income taxes withheld from wages of employees,

together with any penalties and interest thereon. Amount of bond shall be three percent (3%) of Contract or subcontract price on all contracts of \$50,000 or more.

13. SUBMISSION OF BIDS

- A. All Bids shall be submitted on standard Bid Form bound herein and only Bids that are made on this Bid Form will be considered. Entire Bid Form and other supporting documents, if any, shall be removed or copied from Construction Documents, filled out, and submitted in manner specified hereinafter. Submit completed Bid Bond with Bid as well.
- B. No bids for any subdivision or any sub-classification of this Work, except as indicated, will be accepted. Any conditional Bid, amendment to Bid Form or appended item thereto, or inclusion of any correspondence, written or printed matter, or details of any nature other than that specifically called for, which would alter any essential provision of Construction Documents, or require consideration of unsolicited material or data in determining award of Contract, will disqualify Bid. Telecommunication alterations to Bid will not be accepted.
- C. Bidders must submit single Bid for all the Work.
- D. Bid amounts shall be inserted in words and in figures in spaces provided on Bid Form; in case of conflict, written word amounts will govern.
- E. Addenda issued after Bid Letting shall become part of Construction Documents. Bidders shall acknowledge receipt of such addenda in appropriate space provided on Bid Form. Bid may be rejected if receipt of any particular addendum applicable to award of Contract has not been acknowledged on Bid Form.
- F. Bids shall be signed, placed in envelope, sealed and delivered before due time to place designated in Invitation to Bid, and identified with project name, bid number, location, category of work being bid upon, Bid Due Date, name and address of bidder.
- G. Bidder shall be responsible for sealed Bid being delivered to place designated for Bid Due Date on or before date and time specified. Bids received after time of closing will be rejected and returned to bidder unopened.
- H. Bid will be considered invalid and will be rejected if bidder has not signed it.
- I. Faxed or emailed Bids will not be accepted.
- J. Bidder's organization shall submit completed with Bid, Fair Labor Practices Certification form, included in these Construction Documents.

14. SUBCONTRACTOR LISTING

A. Bidders shall be required to submit list of major subcontractors for General Construction, Plumbing, HVAC, and Electrical work proposed for this project to include committed prices for each subcontractor. List shall be placed in separate sealed envelope that must be clearly identified as "Major Subcontractor List", for named project and name of Bidder submitting it. County must receive envelope no later than date by which successful Bidder is required to submit his or her signed Contract, as established in Construction Documents.

15. ALTERNATE BIDS

A. Not Applicable.

16. INFORMATIONAL BIDS

A. Not Applicable.

17. UNIT PRICES

A. Not Applicable.

18. COMMENCEMENT AND COMPLETION

- A. Successful Bidder shall commence work when schedule and weather permit, but no later than stated in Bid Form. Contractor shall pursue the Work regularly and continuously at reasonable rate to insure completion of the Work within time stated in Bid.
- B. Should it be found impossible to complete the Work on or before time specified for completion, written request may be submitted for extension of time setting forth reasons believed to justify granting of such request. Refer to Article 20 of General Conditions of Contract, titled "Time for Completion".

19. WORK BY OWNER

A. Not Applicable.

20. SPECIAL HAZARDS COVERAGE

A. Not Applicable.

FORM A

DANE COUNTY EMERGING SMALL BUSINESS REPORT - CERTIFICATION

In accordance with General Conditions of Contract, submit this Emerging Small Business Report within ten (10) days after Bid Due Date.

PROJECT NAME:		
BID NO.:	BID DUE DATE:	
BIDDER INFORMATION		
COMPANY NAME:		
ADDRESS:		
CONTACT PERSON:		
EMAIL ADDRESS:		

FORM B

Dago	of
Page	of

DANE COUNTY

(Copy this Form as necessary to provide complete information)

EMERGING SMALL BUSINESS REPORT - INVOLVEMENT

COMPANY NAME:
PROJECT NAME:
BID NO.: BID DUE DATE:
ESB NAME:
CONTACT PERSON:
ADDRESS:
PHONE NO & EMAIL.:
Indicate percentage of financial commitment to this ESB:
ESB NAME:
CONTACT PERSON:
ADDRESS:
PHONE NO & EMAIL.:
Indicate percentage of financial commitment to this ESB:

FORM C

Dago	of
Page	of

DANE COUNTY

(Copy this Form as necessary to provide complete information)

EMERGING SMALL BUSINESS REPORT - CONTACTS

COMPANY NAME:					
PROJECT NAME: _					
BID NO.:		BID DUE	DATE:		
ESB FIRM NAME CONTACTED	DATE	PERSON CONTACTED	DID ESB BID?	EPT	REASON FOR REJECTION
	_				

FORM D

DANE COUNTY EMERGING SMALL BUSINESS REPORT - CERTIFICATION STATEMENT

Ι,	,of
Name	Title
Company	certify to best of my knowledge and
belief that this business meets Emerging Small E	Business definition as indicated in Article 9 and
that information contained in this Emerging Sma	all Business Report is true and correct.
Bidder's Signature	Date

Name of Bidding Firm:	
· ·	

SECTION 00 41 13

BID FORM

BID NO. 320002

PROJECT: CFS PHOTOVOLTAIC ARRAY

DANE COUNTY CONSOLIDATED FOOD SERVICE BUILDING

TO: DANE COUNTY DEPARTMENT OF PUBLIC WORKS, HIGHWAY &

TRANSPORTATION PROJECT MANAGER 1919 ALLIANT ENERGY CENTER WAY

MADISON, WISCONSIN 53713

NOTE: WISCONSIN STATUTE 77.54 (9M) ALLOWS FOR NO SALES & USE TAX ON THE PURCHASE OF MATERIALS FOR COUNTY PUBLIC WORKS PROJECTS.

BASE BID - LUMP SUM:

Dane County is inviting Bids for construction services for a photovoltaic array on the roof of the Dane County Consolidated Food Service Building. The undersigned, having examined the site where the Work is to be executed and having become familiar with local conditions affecting the cost of the Work and having carefully examined the Drawings and Specifications, all other Construction Documents and Addenda thereto prepared by Dane County Department of Public Works, Highway & Transportation hereby agrees to provide all labor, materials, equipment and services necessary for the complete and satisfactory execution of the entire Work, as specified in the Construction Documents, for the Base Bid stipulated sum of:

	and /100 Dollars
Written Price	und, 100 20Mab
\$	
Numeric Price	
Receipt of the following addenda and acknowledged:	d inclusion of their provisions in this Bid is hereby
Addendum No(s).	through
Dated	
• •	stration must have this project completed by December 18, tarted by August 24, 2020, what dates can you commence
Commencement Date:	Completion Date:

Bid No. 320002 Bid Form rev. 12/19 00 41 13 - 1

(Name of Corporation, Partnership or Person submitting Bid)
Select one of the following: 1. A corporation organized and existing under the laws of the State of
2. A partnership consisting of
3. A person conducting business as
Of the City, Village, or Town of of the State of
I have examined and carefully prepared this Bid from the associated Construction Documents and have checked the same in detail before submitting this Bid; that I have full authority to make such statements and submit this Bid in (its) (their) (my) behalf; and that the said statements are true and correct. In signing this Bid, we also certify that we have not, either directly or indirectly, entered into any agreement or participated in any collusion or otherwise taken any action in restraint of free competition; that no attempt has been made to induce any other person or firm to submit or not to submit a Bid; that this Bid has been independently arrived at without collusion with any other bidder, competitor, or potential competitor; that this Bid has not been knowingly disclosed prior to the Bids Due Date to another bidder or competitor; that the above statement is accurate under penalty of perjury.
The undersigned is qualified as a Best Value Contractor or has proven their exemption. Qualification or exemption shall be complete before Bid Due Date / Time.
The undersigned further agrees to honor the Base Bid and the Alternate Bid(s) for sixty (60) calendar days from date of Award of Contract.
SIGNATURE:(Bid is invalid without signature)
Print Name: Date:
Title:
Address:
Telephone No.: Fax No.:
Email Address:

I hereby certify that all statements herein are made on behalf of:

END OF SECTION

Contact Person:

RFB No. 320002 Bid Form rev. 06/20 00 41 13 - 2

THIS PAGE IS FOR BIDDERS' REFERENCE DO NOT SUBMIT WITH BID FORM.

BID CHECK LIST:		
These items must be included with	Bid:	
☐ Bid Form	☐ Bid Bond	☐ Fair Labor Practices Certification

DANE COUNTY BEST VALUE CONTRACTING QUALIFICATION

General Contractors & all Subcontractors must be qualified as a Best Value Contractor with the Dane County Public Works Engineering Division. Qualification & listing is not permanent & must be renewed every 24 months. Complete a *Best Value Contracting Application* online at:

pwht.countyofdane.com/bvc_application.aspx

DANE COUNTY VENDOR REGISTRATION PROGRAM

All bidders are strongly encouraged to be a registered vendor with Dane County. Registering allows vendors an opportunity to receive notifications for RFBs & RFPs issued by the County and provides the County with up-to-date company contact information. Complete a new form or renewal online at:

danepurchasing.com/Account/Login?

RFB No. 320002 Bid Form rev. 06/20 00 41 13 - 3

COUNTY OF DANE

PUBLIC WORKS CONSTRUCTION CONTRACT

Contract No Bid No. <u>320002</u>
Authority: 2020 RES
THIS CONTRACT, made and entered into as of the date by which authorized representatives of both parties have affixed their signatures, by and between the County of Dane (hereafter referred to as "COUNTY") and (hereafter, "CONTRACTOR"), and
WITNESSETH:
WHEREAS, COUNTY, whose address is c/o Deputy Public Works Director, 1919 Alliant Energy Center Way, Madison, WI 53713, desires to have CONTRACTOR provide a Photovoltaic Array at the Dane County Consolidated Food Service building ("the Project"); and WHEREAS, CONTRACTOR, whose address is
is able and willing to construct the Project,
in accordance with the Construction Documents;
NOW, THEREFORE, in consideration of the above premises and the mutual covenants of the parties hereinafter set forth, the receipt and sufficiency of which is acknowledged by each party for itself, COUNTY and CONTRACTOR do agree as follows:
1. CONTRACTOR agrees to construct, for the price of \$
2. COUNTY agrees to pay the CONTRACTOR in current funds for the performance of the Contract subject to additions and deductions, as provided in the General Conditions of Contract, and to make payments on account thereof as provided in Article entitled, "Payments to Contractor" of the General Conditions of Contract.
3. During the term of this Contract, CONTRACTOR agrees to take affirmative action to ensure equal employment opportunities. The CONTRACTOR agrees in accordance with Wisconsin

Statute 111.321 and Chapter 19 of the Dane County Code of Ordinances not to discriminate on

orientation, national origin, cultural differences, ancestry, physical appearance, arrest record or conviction record, military participation or membership in the national guard, state defense force or any other reserve component of the military forces of the United States, or political beliefs. Such equal opportunity shall include, but not be limited to, the following: employment,

the basis of age, race, ethnicity, religion, color, gender, disability, marital status, sexual

upgrading, demotion, transfer, recruitment, advertising, layoff, termination, training, rates of pay, and any other form of compensation. CONTRACTOR agrees to post in conspicuous places, available to all employees and applicants for employment, notices setting forth the provisions of this paragraph.

- **4.** CONTRACTOR shall file an Affirmative Action Plan with the Dane County Contract Compliance Specialist in accord with Chapter 19 of the Dane County Code of Ordinances. CONTRACTOR must file such plan within fifteen (15) business days of the effective date of this Contract. During the term of this Contract CONTRACTOR shall also provide copies of all announcements of employment opportunities to COUNTY'S Office of Equity & Inclusion, and shall report annually the number of persons, by race, ethnicity, gender, and disability status, which apply for employment and, similarly classified, the number hired and number rejected.
- **5.** During the term of this Contract, all solicitations for employment placed on CONTRACTOR'S behalf shall include a statement to the effect that CONTRACTOR is an "Equal Opportunity Employer".
- **6.** CONTRACTOR agrees to furnish all information and reports required by COUNTY'S Contract Compliance Specialist as the same relate to affirmative action and nondiscrimination, which may include any books, records, or accounts deemed appropriate to determine compliance with Chapter 19, Dane County Code of Ordinances, and the provisions of this Contract.
- 7. This Contract is intended to be a Contract solely between the parties hereto and for their benefit only. No part of this Contract shall be construed to add to, supplement, amend, abridge or repeal existing rights, benefits or privileges of any third party or parties including, but not limited to, employees of either of the parties.
- **8.** The entire agreement of the parties is contained herein and this Contract supersedes any and all oral agreements and negotiations between the parties relating to the subject matter hereof. The parties expressly agree that the express terms of this Contract shall not be amended in any fashion except in writing, executed by both parties.
- 9. CONTRACTOR must be qualified as a Best Value Contractor or have proven their exemption with Dane County Public Works Engineering Division before Bid Due Date / Time. All contractors and subcontractors must be qualified as a Best Value Contractor or have proven their exemption to perform any work under this Contract.

IN WITNESS WHEREOF, COUNTY and CONTRACTOR, by their respective authorized agents, have caused this Contract and its Schedules to be executed, effective as of the date by which all parties hereto have affixed their respective signatures, as indicated below.

FOR CONTRACTOR:

Signature	Date
Printed or Typed Name and Title	
Signature	Date
Printed or Typed Name and Title	
NOTE: If CONTRACTOR is a corporation, Secretary should Regulations, unincorporated entities are required to provide ei Employer Number in order to receive payment for services remains the services r	ther their Social Security or
This Contract is not valid or effectual for any purpose until ap designated below, and no work is authorized until the CONTF proceed by COUNTY'S Deputy Public Works Director.	proved by the appropriate authority RACTOR has been given notice to
FOR COUNTY:	
Joseph T. Parisi, County Executive	Date
Scott McDonell County-Clerk	Date

Bid Bond

CONTRACTOR: (Name, legal status and address)	SURETY: (Name, legal status and principal place of business)

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

OWNER:

(Name, legal status and address)

BOND AMOUNT:

PROJECT:

(Name, location or address, and Project number, if any)

The Contractor and Surety are bound to the Owner in the amount set forth above, for the payment of which the Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, as provided herein. The conditions of this Bond are such that if the Owner accepts the bid of the Contractor within the time specified in the bid documents, or within such time period as may be agreed to by the Owner and Contractor, and the Contractor either (1) enters into a contract with the Owner in accordance with the terms of such bid, and gives such bond or bonds as may be specified in the bidding or Contract Documents, with a surety admitted in the jurisdiction of the Project and otherwise acceptable to the Owner, for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof, or (2) pays to the Owner the difference, not to exceed the amount of this Bond, between the amount specified in said bid and such larger amount for which the Owner may in good faith contract with another party to perform the work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect. The Surety hereby waives any notice of an agreement between the Owner and Contractor to extend the time in which the Owner may accept the bid. Waiver of notice by the Surety shall not apply to any extension exceeding sixty (60) days in the aggregate beyond the time for acceptance of bids specified in the bid documents, and the Owner and Contractor shall obtain the Surety's consent for an extension beyond sixty (60) days.

If this Bond is issued in connection with a subcontractor's bid to a Contractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

When this Bond has been furnished to comply with a statutory or other legal requirement in the location of the Project, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

Signed and sealed this day of		
	(Contractor as Principal)	(Seal)
(Witness)		
	(Title)	
	(Surety)	(Seal)
(Witness)		
	(Title)	

CAUTION: You should sign an original AIA Contract Document, on which this text appears in RED. An original assures that changes will not be obscured.



Performance Bond


CONTRACTOR: (Name, legal status and address)	SURETY: (Name, legal status and principal place of business)	
OWNER: (Name, legal status and address)		This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.
		Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.
CONSTRUCTION CONTRACT Date:		AIA Document A312–2010 combines two separate bonds, a
Amount:		Performance Bond and a Payment Bond, into one form.
Description: (Name and location)		This is not a single combined Performance and Payment Bond.
BOND Date: (Not earlier than Construction Contract Date)		
Amount:		
Modifications to this Bond: None	☐ See Section 16	
CONTRACTOR AS PRINCIPAL	SURETY	
Company: (Corporate Seal)	Company: (Corporate Seal)	
Signature:	Signature:	
Name Nam	e	
and Title: (Any additional signatures appear on the last	and Title: t page of this Performance Bond.)	
(FOR INFORMATION ONLY—Name, addr AGENT or BROKER:	OWNER'S REPRESENTATIVE:	
	(Architect, Engineer or other party:)	

- § 1 The Contractor and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Owner for the performance of the Construction Contract, which is incorporated herein by reference.
- § 2 If the Contractor performs the Construction Contract, the Surety and the Contractor shall have no obligation under this Bond, except when applicable to participate in a conference as provided in Section 3.
- § 3 If there is no Owner Default under the Construction Contract, the Surety's obligation under this Bond shall arise after
 - the Owner first provides notice to the Contractor and the Surety that the Owner is considering declaring a Contractor Default. Such notice shall indicate whether the Owner is requesting a conference among the Owner, Contractor and Surety to discuss the Contractor's performance. If the Owner does not request a conference, the Surety may, within five (5) business days after receipt of the Owner's notice, request such a conference. If the Surety timely requests a conference, the Owner shall attend. Unless the Owner agrees otherwise, any conference requested under this Section 3.1 shall be held within ten (10) business days of the Surety's receipt of the Owner's notice. If the Owner, the Contractor and the Surety agree, the Contractor shall be allowed a reasonable time to perform the Construction Contract, but such an agreement shall not waive the Owner's right, if any, subsequently to declare a Contractor Default:
 - .2 the Owner declares a Contractor Default, terminates the Construction Contract and notifies the Surety; and
 - .3 the Owner has agreed to pay the Balance of the Contract/Price in accordance with the terms of the Construction Contract to the Surety or to a contractor selected to perform the Construction Contract.
- § 4 Failure on the part of the Owner to comply with the notice requirement in Section 3.1 shall not constitute a failure to comply with a condition precedent to the Surety's obligations, or release the Surety from its obligations, except to the extent the Surety demonstrates actual prejudice.
- § 5 When the Owner has satisfied the conditions of Section 3, the Surety shall promptly and at the Surety's expense take one of the following actions:
- § 5.1 Arrange for the Contractor, with the consent of the Owner, to perform and complete the Construction Contract;
- § 5.2 Undertake to perform and complete the Construction Contract itself, through its agents or independent contractors:
- § 5.3 Obtain bids or negotiated proposals from qualified contractors acceptable to the Owner for a contract for performance and completion of the Construction Contract, arrange for a contract to be prepared for execution by the Owner and a contractor selected with the Owner's concurrence, to be secured with performance and payment bonds executed by a qualified surety equivalent to the bonds issued on the Construction Contract, and pay to the Owner the amount of damages as described in Section 7 in excess of the Balance of the Contract Price incurred by the Owner as a result of the Contractor Default, or
- § 5.4 Waive its right to perform and complete, arrange for completion, or obtain a new contractor and with reasonable promptness under the circumstances:
 - After investigation, determine the amount for which it may be liable to the Owner and, as soon as practicable after the amount is determined, make payment to the Owner; or
 - .2 Deny liability in whole or in part and notify the Owner, citing the reasons for denial.
- § 6 If the Surety does not proceed as provided in Section 5 with reasonable promptness, the Surety shall be deemed to be in default on this Bond seven days after receipt of an additional written notice from the Owner to the Surety demanding that the Surety perform its obligations under this Bond, and the Owner shall be entitled to enforce any remedy available to the Owner. If the Surety proceeds as provided in Section 5.4, and the Owner refuses the payment or the Surety has denied liability, in whole or in part, without further notice the Owner shall be entitled to enforce any remedy available to the Owner.

- § 7 If the Surety elects to act under Section 5.1, 5.2 or 5.3, then the responsibilities of the Surety to the Owner shall not be greater than those of the Contractor under the Construction Contract, and the responsibilities of the Owner to the Surety shall not be greater than those of the Owner under the Construction Contract. Subject to the commitment by the Owner to pay the Balance of the Contract Price, the Surety is obligated, without duplication, for
 - .1 the responsibilities of the Contractor for correction of defective work and completion of the Construction Contract:
 - .2 additional legal, design professional and delay costs resulting from the Contractor's Default, and resulting from the actions or failure to act of the Surety under Section 5; and
 - .3 liquidated damages, or if no liquidated damages are specified in the Construction Contract, actual damages caused by delayed performance or non-performance of the Contractor.
- § 8 If the Surety elects to act under Section 5.1, 5.3 or 5.4, the Surety's liability is limited to the amount of this Bond.
- § 9 The Surety shall not be liable to the Owner or others for obligations of the Contractor that are unrelated to the Construction Contract, and the Balance of the Contract Price shall not be reduced or set off on account of any such unrelated obligations. No right of action shall accrue on this Bond to any person or entity other than the Owner or its heirs, executors, administrators, successors and assigns.
- § 10 The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.
- § 11 Any proceeding, legal or equitable, under this Bond may be instituted in any court of competent jurisdiction in the location in which the work or part of the work is located and shall be instituted within two years after a declaration of Contractor Default or within two years after the Contractor ceased working or within two years after the Surety refuses or fails to perform its obligations under this Bond, whichever occurs first. If the provisions of this Paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.
- § 12 Notice to the Surety, the Owner or the Contractor shall be mailed or delivered to the address shown on the page on which their signature appears.
- § 13 When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

§ 14 Definitions

- § 14.1 Balance of the Contract Price. The total amount payable by the Owner to the Contractor under the Construction Contract after all proper adjustments have been made, including allowance to the Contractor of any amounts received or to be received by the Owner in settlement of insurance or other claims for damages to which the Contractor is entitled, reduced by all valid and proper payments made to or on behalf of the Contractor under the Construction Contract.
- § 14.2 Construction Contract. The agreement between the Owner and Contractor identified on the cover page, including all Contract Documents and changes made to the agreement and the Contract Documents.
- § 14.3 Contractor Default. Failure of the Contractor, which has not been remedied or waived, to perform or otherwise to comply with a material term of the Construction Contract.
- § 14.4 Owner Default. Failure of the Owner, which has not been remedied or waived, to pay the Contractor as required under the Construction Contract or to perform and complete or comply with the other material terms of the Construction Contract.
- § 14.5 Contract Documents. All the documents that comprise the agreement between the Owner and Contractor.
- § 15 If this Bond is issued for an agreement between a Contractor and subcontractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.





Payment Bond

CONTRACTOR: (Name, legal status and address)	SURETY: (Name, legal status and principal place of business)	
OWNER: (Name, legal status and address)		This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.
		Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.
CONSTRUCTION CONTRACT Date:		AIA Document A312–2010 combines two separate bonds, a
Amount:		Performance Bond and a Payment Bond, into one form.
Description: (Name and location)		This is not a single combined Performance and Payment Bond.
BOND Date: (Not earlier than Construction Contract Date)		
Amount:		
Modifications to this Bond: None	☐ See Section 18	
CONTRACTOR AS PRINCIPAL	SURETY	
Company: (Corporate Seal)	Company: (Corporate Seal)	
Signature:	Signature:	
Name Nam	е	
and Title: (Any additional signatures appear on the last	and Title: t page of this Payment Bond.)	
(FOR INFORMATION ONLY—Name, addr AGENT or BROKER:	ress and telephone) OWNER'S REPRESENTATIVE: (Architect, Engineer or other party:)	


- § 1 The Contractor and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Owner to pay for labor, materials and equipment furnished for use in the performance of the Construction Contract, which is incorporated herein by reference, subject to the following terms.
- § 2 If the Contractor promptly makes payment of all sums due to Claimants, and defends, indemnifies and holds harmless the Owner from claims, demands, liens or suits by any person or entity seeking payment for labor, materials or equipment furnished for use in the performance of the Construction Contract, then the Surety and the Contractor shall have no obligation under this Bond.
- § 3 If there is no Owner Default under the Construction Contract, the Surety's obligation to the Owner under this Bond shall arise after the Owner has promptly notified the Contractor and the Surety (at the address described in Section 13) of claims, demands, liens or suits against the Owner or the Owner's property by any person or entity seeking payment for labor, materials or equipment furnished for use in the performance of the Construction Contract and tendered defense of such claims, demands, liens or suits to the Contractor and the Surety.
- § 4 When the Owner has satisfied the conditions in Section 3, the Surety shall promptly and at the Surety's expense defend, indemnify and hold harmless the Owner against a duly tendered claim, demand, lien or suit.
- § 5 The Surety's obligations to a Claimant under this Bond shall arise after the following:
- § 5.1 Claimants, who do not have a direct contract with the Contractor,
 - .1 have furnished a written notice of non-payment to the Contractor, stating with substantial accuracy the amount claimed and the name of the party to whom the materials were, or equipment was, furnished or supplied or for whom the labor was done or performed, within ninety (90) days after having last performed labor or last furnished materials or equipment included in the Claim; and
 - .2 have sent a Claim to the Surety (at the address described in Section 13).
- § 5.2 Claimants, who are employed by or have a direct contract with the Contractor, have sent a Claim to the Surety (at the address described in Section 13).
- § 6 If a notice of non-payment required by Section 5.1.1 is given by the Owner to the Contractor, that is sufficient to satisfy a Claimant's obligation to furnish a written notice of non-payment under Section 5.1.1.
- § 7 When a Claimant has satisfied the conditions of Sections 5.1 or 5.2, whichever is applicable, the Surety shall promptly and at the Surety's expense take the following actions:
- § 7.1 Send an answer to the Claimant, with a copy to the Owner, within sixty (60) days after receipt of the Claim, stating the amounts that are undisputed and the basis for challenging any amounts that are disputed; and
- § 7.2 Pay or arrange for payment of any undisputed amounts.
- § 7.3 The Surety's failure to discharge its obligations under Section 7.1 or Section 7.2 shall not be deemed to constitute a waiver of defenses the Surety or Contractor may have or acquire as to a Claim, except as to undisputed amounts for which the Surety and Claimant have reached agreement. If, however, the Surety fails to discharge its obligations under Section 7.1 or Section 7.2, the Surety shall indemnify the Claimant for the reasonable attorney's fees the Claimant incurs thereafter to recover any sums found to be due and owing to the Claimant.
- § 8 The Surety's total obligation shall not exceed the amount of this Bond, plus the amount of reasonable attorney's fees provided under Section 7.3, and the amount of this Bond shall be credited for any payments made in good faith by the Surety.
- § 9 Amounts owed by the Owner to the Contractor under the Construction Contract shall be used for the performance of the Construction Contract and to satisfy claims, if any, under any construction performance bond. By the Contractor furnishing and the Owner accepting this Bond, they agree that all funds earned by the Contractor in the performance of the Construction Contract are dedicated to satisfy obligations of the Contractor and Surety under this Bond, subject to the Owner's priority to use the funds for the completion of the work.

- § 10 The Surety shall not be liable to the Owner, Claimants or others for obligations of the Contractor that are unrelated to the Construction Contract. The Owner shall not be liable for the payment of any costs or expenses of any Claimant under this Bond, and shall have under this Bond no obligation to make payments to, or give notice on behalf of Claimants or otherwise have any obligations to Claimants under this Bond.
- § 11 The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.
- § 12 No suit or action shall be commenced by a Claimant under this Bond other than in a court of competent jurisdiction in the state in which the project that is the subject of the Construction Contract is located or after the expiration of one year from the date (1) on which the Claimant sent a Claim to the Surety pursuant to Section 5.1.2 or 5.2, or (2) on which the last labor or service was performed by anyone or the last materials or equipment were furnished by anyone under the Construction Contract, whichever of (1) or (2) first occurs. If the provisions of this Paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.
- § 13 Notice and Claims to the Surety, the Owner or the Contractor shall be mailed or delivered to the address shown on the page on which their signature appears. Actual receipt of notice or Claims, however accomplished, shall be sufficient compliance as of the date received.
- § 14 When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.
- § 15 Upon request by any person or entity appearing to be a potential beneficiary of this Bond, the Contractor and Owner shall promptly furnish a copy of this Bond or shall permit a copy to be made.

§ 16 Definitions

- § 16.1 Claim. A written statement by the Claimant including at a minimum:
 - .1 the name of the Claimant;
 - .2 the name of the person for whom the labor was done, or materials or equipment furnished;
 - .3 a copy of the agreement or purchase order pursuant to which labor, materials or equipment was furnished for use in the performance of the Construction Contract;
 - .4 a brief description of the labor, materials or equipment furnished;
 - .5 the date on which the Claimant last performed labor or last furnished materials or equipment for use in the performance of the Construction Contract;
 - .6 the total amount earned by the Claimant for labor, materials or equipment furnished as of the date of the Claim:
 - .7 the total amount of previous payments received by the Claimant; and
 - .8 the total amount due and unpaid to the Claimant for labor, materials or equipment furnished as of the date of the Claim.
- § 16.2 Claimant. An individual or entity having a direct contract with the Contractor or with a subcontractor of the Contractor to furnish labor, materials or equipment for use in the performance of the Construction Contract. The term Claimant also includes any individual or entity that has rightfully asserted a claim under an applicable mechanic's lien or similar statute against the real property upon which the Project is located. The intent of this Bond shall be to include without limitation in the terms "labor, materials or equipment" that part of water, gas, power, light, heat, oil, gasoline, telephone service or rental equipment used in the Construction Contract, architectural and engineering services required for performance of the work of the Contractor and the Contractor's subcontractors, and all other items for which a mechanic's lien may be asserted in the jurisdiction where the labor, materials or equipment were furnished.
- § 16.3 Construction Contract. The agreement between the Owner and Contractor identified on the cover page, including all Contract Documents and all changes made to the agreement and the Contract Documents.

- § 16.4 Owner Default. Failure of the Owner, which has not been remedied or waived, to pay the Contractor as required under the Construction Contract or to perform and complete or comply with the other material terms of the Construction Contract.
- § 16.5 Contract Documents, All the documents that comprise the agreement between the Owner and Contractor.
- § 17 If this Bond is issued for an agreement between a Contractor and subcontractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.



changes will not be obscured.

SECTION 00 72 12

GENERAL CONDITIONS OF CONTRACT

TABLE OF CONTENTS

1. (CONSTRUCTION DOCUMENTS	2
2. I	DEFINITIONS	2
3. <i>A</i>	ADDITIONAL INSTRUCTIONS AND DRAWINGS	2
	SHOP DRAWINGS, PRODUCT DATA AND SAMPLES	
	CUTTING AND PATCHING	
	CLEANING UP	
	USE OF SITE	
	MATERIALS AND WORKMANSHIP	
	CONTRACTOR'S TITLE TO MATERIALS	
	"OR EQUAL" CLAUSE	
	PATENTS AND ROYALTIES	
	SURVEYS, PERMITS, REGULATIONS AND TAXES	
	CONTRACTOR'S OBLIGATIONS AND SUPERINTENDENCE	
14.	WEATHER CONDITIONS	8
	PROTECTION OF WORK AND PROPERTY	
	INSPECTION AND TESTING OF MATERIALS	
	REPORTS, RECORDS AND DATA	
	CHANGES IN THE WORK	
	EXTRAS	
	TIME FOR COMPLETION	
	CORRECTION OF WORK	
22.	SUBSURFACE CONDITIONS FOUND DIFFERENT	10
	RIGHT OF DEPARTMENT TO TERMINATE CONTRACT	
24.	CONSTRUCTION SCHEDULE AND PERIODIC ESTIMATES	.11
25.	PAYMENTS TO CONTRACTOR	12
26.	WITHHOLDING OF PAYMENTS	13
27.	ACCEPTANCE OF FINAL PAYMENT AS RELEASE	14
28.	PAYMENTS BY CONTRACTOR	14
29.	CONTRACT SECURITY	14
30.	ASSIGNMENTS	14
	MUTUAL RESPONSIBILITY OF CONTRACTORS	
	SEPARATE CONTRACTS	
	SUBCONTRACTS	
34.	PROJECT MANAGER'S AUTHORITY	16
	CONSULTANT'S AUTHORITY	
	STATED ALLOWANCES	
	ESTIMATES OF QUANTITIES	
	LANDS AND RIGHTS-OF-WAY	
39	GENERAL GUARANTEE	17
	CONFLICTING CONDITIONS	
	NOTICE AND SERVICE THEREOF	
	PROTECTION OF LIVES AND HEALTH	
	AFFIRMATIVE ACTION PROVISION AND MINORITY / WOMEN /	10
чэ.		18
11	COMPLIANCE WITH FAIR LABOR STANDARDS	
	DOMESTIC PARTNERSHIP BENEFITS	
	USE AND OCCUPANCY PRIOR TO ACCEPTANCE	
	MINIMUM WAGES	
	CLAIMS	
	ANTITRUST AGREEMENT	
	INSURANCE	
J1.	WISCONSIN LAW CONTROLLING	LL

1. CONSTRUCTION DOCUMENTS

- A. Construction Documents, listed in Table of Contents of this Specification volume shall form part of this Contract and provisions of Construction Documents shall be as binding upon parties as if they were fully set forth in Contract itself.
- B. These shall also be considered as part of Construction Documents: Addenda, including additions and modifications incorporated in such addenda before execution of Contract; requests for information; construction bulletins; change orders; and written interpretations by Architect / Engineer or Public Works Project Manager that are made after execution of Contract.
- C. Construction Documents are complementary, and what is required by one shall be as binding as if required by all. Intent of Construction Documents is to include all labor, materials and equipment necessary for proper execution of the Work.

2. DEFINITIONS

- A. These terms as used in this Contract are respectively defined as follows:
 - 1. All uses of term "County" in Construction Documents shall mean Dane County.
 - 2. All uses of term "Department" in Construction Documents shall mean Department of Public Works, Highway & Transportation, which is a unit of Dane County government. Department is County agency overseeing Contract with Contractor.
 - 3. Public Works Project Manager is appointed by and responsible to Department. Public Works Project Manager has authority to act on behalf of Department and will sign change orders, payment requests and other administrative matters related to projects.
 - 4. Public Works Project Manager is responsible for supervision, administration and management of field operations involved in construction phase of this Work.
 - 5. Term "Work" includes all labor, equipment and materials necessary to produce project required by Construction Documents.
 - 6. Term "Substantial Completion" is date when project or specified area of project is certified by Architect / Engineer that construction is sufficiently completed, in accordance with Construction Documents, and as modified by any subsequent changes agreed to by parties, so that County may occupy project or specified area of project for use for which it was intended subject to permit approval for occupancy.
 - 7. Contractor is person, firm, or corporation with whom County makes Contract. Though multiple contracts may be involved, Construction Documents treat them throughout as if each were of singular number.

3. ADDITIONAL INSTRUCTIONS AND DRAWINGS

A. Contractor may be furnished additional instructions and detail drawings as necessary to carry out the Work included in Contract. Additional drawings and instructions thus supplied to Contractor will coordinate with Construction Documents and will be so prepared that they can be reasonably interpreted as part thereof. Contractor shall carry out the Work in accordance with additional detail drawings and instructions.

Bid No. 320002 General Conditions of Contract rev. 10/19 00 72 13 - 2

4. SHOP DRAWINGS, PRODUCT DATA AND SAMPLES

- A. Unless otherwise specified, Contractor shall submit three (3) copies of all Shop Drawings for each submission, until receiving final approval. After final approval, provide five (5) additional copies for distribution and such other copies as may be required.
- B. Contractor shall submit, on an on-going basis and as directed, Product Data such as brochures that shall contain catalog cuts and specifications of all furnished mechanical and electrical equipment. After Architect / Engineer's approval, one (1) copy shall remain in Architect / Engineer's file, one (1) kept at Department's office and one (1) kept at job site by Contractor for reference purposes.
- C. Samples shall consist of physical examples furnished by Contractor in sufficient size and quantity to illustrate materials, equipment or workmanship, and to establish standards to compare the Work.
 - 1. Submit Samples in sufficient quantity (minimum of two (2)) to permit Architect / Engineer to make all necessary tests and of adequate size showing quality, type, color range, finish, and texture. Label each Sample stating material, type, color, thickness, size, project name, and Contractor's name.
 - 2. Submit transmittal letter requesting approval, and prepay transportation charges to Architect / Engineer's office on samples forwarded.
 - 3. Materials installed shall match approved Samples.
- D. Contractor shall review Shop Drawings and place their dated stamp thereon to evidence their review and approval and shall submit with reasonable promptness and in orderly sequence to cause no delay in the Work or in work of any other contractor. At time of submission, Contractor shall inform Architect / Engineer in writing of any deviation in Shop Drawings or Samples from requirements of Construction Documents. Architect / Engineer will not consider partial lists.
- E. Architect / Engineer will review and approve or reject Shop Drawings with reasonable promptness to cause no delay. Architect / Engineer's approval shall not relieve Contractor from responsibility for errors or omissions in Shop Drawings.
- F. Contractor shall not commence any work requiring Shop Drawing, Product Data or Sample submission until Architect / Engineer has approved submission. All such work shall be in accordance with approved Shop Drawings, Product Data and Samples.
- G. Contractor shall keep on site of the Work, approved or conformed copy of Shop Drawings and shall at all times give Department access thereto.
- H. By stamping and submitting Shop Drawings, Product Data and Samples, Contractor thereby represents that he or she has or will determine and verify all field measurements, field construction criteria, materials, catalog numbers, and similar data and that he or she has checked and coordinated each Shop Drawing, Product Data and Sample with requirements of the Work and of Construction Documents. Architect / Engineer shall return without examination, Shop Drawings, Product Data and Samples not so noted.
- I. All Shop Drawings from any one Contractor should be numbered consecutively and on cover sheet shall bear name and location of project, name of Contractor, date of submittal and date of each correction or revision and associated Specification section and page number.

5. CUTTING AND PATCHING

- A. Contractor shall be responsible for all cutting, fitting or patching required to complete the Work or to make its parts fit together properly.
- B. Contractor shall not damage or endanger portion of the Work or fully or partially completed construction of County or separate contractors by cutting, patching or otherwise altering such construction, or by excavation. Contractor shall not cut or otherwise alter such construction by County or separate contractor except with written consent of County and of such separate contractor; such consent shall not be unreasonably withheld. Contractor shall not withhold unreasonably from County or separate contractor, Contractor's consent to cutting or otherwise altering the Work.

6. CLEANING UP

- A. Contractor shall keep premises and surrounding area free from accumulation of waste materials or rubbish caused by operations under Contract. Contractor shall remove from and about the Work waste materials, rubbish, Contractor's tools, construction equipment, machinery, and surplus materials at completion of the Work. Contractor shall maintain streets and sidewalks around the Work site in clean condition. Contractor shall remove all spillage and prevent tracking of spillage arising from performance of the Work, into, out of, and within the Work site. Contractor shall establish regular maintenance program of sweeping, vacuuming and / or hosing to minimize accumulation of dirt and dust upon such areas.
- B. If Contractor fails to clean up as directed in Construction Documents, County may do so and shall charge Contractor cost thereof.
- C. Contractor shall be responsible for broken windows and glass, and at completion of the Work shall replace such damaged or broken windows and glass. After replacing damaged or broken windows and glass, Contractor shall remove all labels, wash and polish both sides of all windows and glass.
- D. In addition to general cleaning (sweeping, vacuuming and / or hosing, as is appropriate to work surface), Contractor shall perform following final cleaning for all trades at completion of the Work:
 - 1. Remove temporary protections;
 - 2. Remove marks, stains, fingerprints and other soil or dirt from painted, decorated and finished woodwork and wall surfaces;
 - 3. Remove spots, plaster, soil and paint from ceramic tile, marble and other finished materials, and wash or wipe clean;
 - 4. Clean fixtures, cabinet work and equipment, removing stains, paint, dirt and dust, and leave same in undamaged, new condition;
 - 5. Clean aluminum in accordance with recommendations of manufacturer; and
 - 6. Clean resilient floors thoroughly with well-rinsed mop containing only enough moisture to clean off any surface dirt or dust and buff dry by machine to bring surfaces to sheen.

7. USE OF SITE

- A. Contractor shall provide County and Architect / Engineer access to the Work under all circumstances.
- B. Contractor shall confine operations at site to areas permitted by County, law, ordinance, permits and Construction Documents and shall not unreasonably encumber site with materials

or equipment. Contractor shall assure free, convenient, unencumbered, direct and safe access to all properties adjacent to the Work for County, its employees, invitees and guests.

8. MATERIALS AND WORKMANSHIP

- A. Contractor shall perform all work and furnish all supplies and materials, machinery, equipment, facilities and means, necessary to complete the Work required by this Contract, within time specified, in accordance with provisions of Construction Documents.
- B. All equipment and materials incorporated in the Work covered by this Contract are to be new; use recycled and / or recovered materials to extent that such use is technically and economically feasible. Recovered materials are products recovered from solid waste in form identical to original form for use that is same as, or similar to original use. Recycled materials are products manufactured from solid waste.
- C. If requested, Contractor shall furnish satisfactory evidence as to kind and quality of construction materials proposed or used. Contractor shall furnish to Architect / Engineer, for approval, manufacturer name and model, performance capacities and other pertinent information of machinery, mechanical, electrical or other types of equipment, which Contractor plans to install.
- D. If not otherwise provided, materials and labor called for in this Contract shall be provided and performed in accordance with established practice and standards recognized by Architects, Engineers, Department, and construction industry.
- E. Reference to "Standard" specifications of any association or manufacturer, or codes of County authorities, intends most recent printed edition or catalog in effect on date that corresponds with date of Construction Documents.
- F. Whenever reference is made in Specifications that work shall be "performed", "applied", in accordance with "manufacturer's directions or instructions", Contractor to whom those instructions are directed shall furnish three (3) printed copies of such instructions to Architect / Engineer before execution of the Work.

9. CONTRACTOR'S TITLE TO MATERIALS

A. Contractor or any subcontractor shall not purchase materials or supplies for the Work subject to any chattel mortgage or under conditional sale contract or other agreement by which seller retains interest. Contractor warrants that all materials and supplies used in the Work are free from all liens, claims or encumbrances and Contractor has good title to them.

10. "OR EQUAL" CLAUSE

A. Whenever equipment or materials are identified on Drawings or in Specifications by reference to manufacturer's or vendor's name, trade name, catalog number, and other identifying information, it is intended to establish standards; and any equipment or material of other manufacturers and vendors which will perform adequately duties imposed by general design will be considered equally accepted provided equipment or material so proposed is, in opinion of Architect / Engineer, of equal substance and function. Architect / Engineer and Department shall provide written approval before Contractor may purchase or install it.

- B. Equipment or materials of manufacturers, other than those named, may be used only upon following conditions:
 - 1. That, in opinion of Architect / Engineer and Department, proposed material or equipment item is fully equal or superior (in design, materials, construction, workmanship, performance, finish, etc.) to named item. No compromise in quality level, however small, is acceptable.
 - 2. That, in substituting materials or equipment, Contractor assumes responsibility for any changes in system or for modifications required in adjacent or related work to accommodate such substitution despite Architect / Engineer's and Department's approval, and all costs growing out of approval of "or equal" items shall be responsibility of Contractor. No extra costs resulting from such approval shall become responsibility of Department, Architect / Engineer or any other separate Contractor.
 - 3. It shall be understood that use of materials or equipment other than those specified, or approved equal by Architect / Engineer and Department, shall constitute violation of Contract, and that Architect / Engineer and Department shall have right to require removal of such materials or equipment and their replacement with specified materials or equipment at Contractor's expense.
 - 4. Product and manufacturer named first in Specifications or on information shown on Drawings is basis of selection of manufactured items and equipment, particularly mechanical equipment. In using other than first named products or manufacturers, including those specified as additionally approved or acceptable, Contractor assumes responsibility for any changes in system and for modifications in any work required to accommodate them. Architect / Engineer's approval of such additionally acceptable products or manufacturers, either in Specifications or in Addendum, does not relieve Contractor from obligation to coordinate such optional products with other Contractors, whose work may be affected by them, and to pay all additional costs resulting from their inclusion into the Work. Contractor's liability shall include payment of Architect / Engineer's fees for any additional services made necessary by or directly connected to such product changes. No extra costs resulting from such changes shall become responsibility of Department, Architect / Engineer or any other separate Contractor.
- C. No request for approval of "or equal" materials will be entertained except from Contractor. Identify any request for substitution as substitution on Contractor's letter of transmittal and give reasons for substitution. Department may in its sole discretion allow substitutions of materials.

11. PATENTS AND ROYALTIES

- A. If Contractor uses any design, device or material covered by letters, patent or copyright, it is mutually agreed and understood, that, without exception, contract prices shall include all royalties or costs arising from use of such design, device or materials, in any way involved in the Work.
- B. Contractor shall indemnify and save harmless County from any and all claims for infringement by reason of use of such patent or copyright in connection with the Work agreed to be performed under this Contract, and shall indemnify County for any cost, expense or damage which it may be obliged to pay by reason of such infringement at any time during prosecution of the Work or after completion of the Work.

12. SURVEYS, PERMITS, REGULATIONS AND TAXES

A. Department will furnish to Contractor all site, topography and property surveys necessary for execution of the Work.

- B. Contractor shall procure all permits, licenses and approvals necessary for execution of this Contract.
- C. Contractor shall give all notices and comply with all State of Wisconsin, Federal and local laws, codes, rules and regulations relating to performance of the Work, protection of adjacent property, and maintenance of passageways, guard fences or other protective facilities.
- D. Contractor does not need to pay State and local sales & use taxes. See Wisconsin Statute 77.54 (9m).
- E. Contractor shall promptly notify Architect / Engineer of any variances of Drawings or Specifications with that of any State of Wisconsin, federal or local law, code, rule or regulation. Upon such notification, Architect / Engineer will require correction of variance to comply with applicable law, code, rule or regulation at no additional cost to Contractor.
- F. Work under this Contract shall comply with all applicable State of Wisconsin, Federal and local laws, codes and regulations.
- G. Contractor shall pay charges for water, sewer and other utility connections made by municipalities where required by Specifications.

13. CONTRACTOR'S OBLIGATIONS AND SUPERINTENDENCE

- A. Contractor shall provide and pay for all materials, labor, tools, equipment, transportation and superintendence necessary to execute, complete and deliver the Work within specified time. Contractor agrees to secure at their own expense all personnel necessary to carry out the Work. Such personnel shall not be deemed County employees nor shall they have or be deemed to have any direct contractual relationship with County.
- B. Performance of any work necessary after regular working hours, on Sundays or Legal Holidays shall be without additional expense to County. Performance of any work at site at other than normal working hours must be coordinated with Public Works Project Manager.
- C. Contractor shall furnish, erect, maintain and remove such temporary works as may be required.
- D. Contractor shall observe, comply with, and be subject to all terms, conditions, requirements and limitations of Construction Documents.
- E. At the Work site, Contractor shall give personal superintendence to the Work or shall employ construction superintendent or foreman, experienced in character of work covered by Contract, who shall have full authority to act for Contractor. Understand that such superintendent or foreman shall be acceptable to Architect / Engineer and Department.
- F. Remove from project or take other corrective action upon notice from Architect / Engineer or Department for Contractor's employees whose work is considered by Architect / Engineer or Department to be unsatisfactory, careless, incompetent, unskilled or otherwise objectionable.
- G. Contractor and subcontractors shall be required to conform to Labor Laws of State of Wisconsin and various acts amendatory and supplementary thereto and to other laws, ordinances and legal requirements applicable to the Work.

H. Presence and observation of the Work by Architect / Engineer or Public Works Project Manager shall not relieve Contractor of any obligations.

14. WEATHER CONDITIONS

A. In event of temporary suspension of work, or during inclement weather, or whenever Architect / Engineer shall direct, Contractor shall, and shall cause subcontractors to protect carefully all work and materials against damage or injury from weather. If, in opinion of Architect / Engineer or Department, any work or materials that have been damaged or injured due to failure on part of Contractor or any subcontractors so to protect the Work, such materials shall be removed and replaced at expense of Contractor.

15. PROTECTION OF WORK AND PROPERTY

- A. Contractor shall at all times safely guard County's property from injury or loss in connection with this Contract. Contractor shall at all times safely guard and protect the Work, and adjacent property, from damage. Contractor shall replace or make good any such damage, loss or injury unless such is caused directly by errors contained in Contract, or by County, or County's duly authorized representative.
- B. Contractor may act diligently, without previous instructions from Architect / Engineer and / or Department, in emergency that threatens loss or injury of property, or safety of life. Contractor shall notify Architect / Engineer and / or Department immediately thereafter. Promptly submit any claim for compensation by Contractor due to such extra work to Architect / Engineer and / or Department for approval as provided for in Article 18 herein.

16. INSPECTION AND TESTING OF MATERIALS

- A. Authorized representatives and agents of County government shall have access at all times to the Work wherever it is in preparation or progress and Contractor shall provide facilities for such access and for inspection.
- B. Should it be considered necessary or advisable at any time before final acceptance of the Work to make examination of work already completed, by removing or tearing out same, Contractor shall upon request, promptly furnish all necessary facilities, labor and materials. If such work is found to be defective in any aspect, due to fault of Contractor or subcontractors thereof, Contractor shall assume all expenses of such examination and of satisfactory reconstruction. Contractor will be reimbursed for such examination and replacement in accordance with Article 18 A.3., of these General Conditions of Contract if such work is found to meet requirements of Contract.
- C. If Specifications, Architect / Engineer's, or Public Works Project Manager's instructions require any work to be specially tested or approved, Contractor shall give Architect / Engineer and Public Works Project Manager timely notice of its readiness for testing or inspection. Test all materials and equipment requiring testing in accordance with accepted or specified standards, as applicable. Architect / Engineer shall recommend laboratory or inspection agency and Department will select and pay for all initial laboratory inspection services. Should retesting be required, due to failure of initial testing, cost of such retesting shall be borne by Contractor.
- D. Cost of any testing performed by manufacturers or Contractor for substantiating acceptability of proposed substitution of materials and equipment, or necessary conformance testing in

conjunction with manufacturing processes or factory assemblage, shall be borne by Contractor or manufacturer responsible.

17. REPORTS, RECORDS AND DATA

A. Contractor shall submit to Architect / Engineer and Public Works Project Manager such schedule of quantities and costs, progress schedules, payrolls, reports, estimates, invoices, records and other data as either may request concerning work performed or to be performed under this Contract.

18. CHANGES IN THE WORK

- A. Make no changes, except in cases of emergency, in the Work covered by approved Construction Documents without having prior written approval of Department. Charges or credits for the Work covered by approved change shall be determined by one of these methods:
 - 1. Unit bid prices previously approved.
 - 2. Agreed lump sum based on actual cost of:
 - a) Labor, including foremen, and all fringe benefits that are associated with their wages.
 - b) Materials entering permanently into the Work.
 - c) Ownership or rental cost of construction tools and equipment during time of use on extra work.
 - d) Power and consumable supplies for operation of power equipment.
 - e) Workmen's Compensation Insurance, Contractor's Public Liability and Property Damage Insurance, and Comprehensive Automobile Liability Insurance.
 - f) Social Security and old age and unemployment contributions.
 - g) Add to cost under (2), fixed fee to be agreed upon, but not to exceed fifteen percent (15%) of actual cost of work performed with their own labor force. Fee shall be compensation to cover cost of supervision, overhead, bond, profit and any other general expense.
 - h) On that portion of the Work under (2) done under subcontract, Contractor may include not over seven and one-half percent (7½%) for supervision, overhead, bond, profit and any other general expense.
 - i) Department may require correct amount of costs with supporting vouchers; Contractor shall keep and present in such form as directed.
 - 3. Cost-plus work, with not-to-exceed dollar limit, based on actual cost of:
 - a) Labor, including foremen, and all fringe benefits that are associated with their wages.
 - b) Materials entering permanently into the Work.
 - c) Ownership or rental cost of construction tools and equipment during time of use on extra work. Rental cost cannot exceed fifty percent (50%) replacement value of rented equipment.
 - d) Power and consumable supplies for operation of power equipment.
 - e) Workmen's Compensation Insurance, Contractor's Public Liability and Property Damage Insurance, and Comprehensive Automobile Liability Insurance.
 - f) Social Security and old age and unemployment contributions.
 - g) To cost under (3), there shall be added fixed fee to be agreed upon but not to exceed fifteen percent (15%) of actual cost of work performed with their own labor force. Fee shall be compensation to cover cost of supervision, overhead, bond, profit, and any other general expense.
 - h) On that portion of the Work under (3) done under subcontract, Contractor may include not over seven and one-half percent (7½%) for supervision, overhead, bond, profit, and any other general expense.

- i) Contractor shall keep and present, in such form as directed, correct amount of cost together with such supporting vouchers as may be required by Department.
- B. If Contractor claims that by any instructions given by Architect / Engineer, Department, by drawings or otherwise, regarding performance of the Work or furnishing of material under Contract, involves extra cost, Contractor shall give Department written notice of cost thereof within two (2) weeks after receipt of such instructions and in any event before proceeding to execute work, unless delay in executing work would endanger life or property.
- C. No claim for extra work or cost shall be allowed unless it was done in pursuance of written Change Order from Architect / Engineer and approved by Department, as previously mentioned, and claim presented with payment request submitted after changed or extra work is completed.
- D. Negotiation of cost for change in the Work shall not be cause for Contractor to delay prosecution of the Work if Contractor has been authorized in writing by Public Works Project Manager to proceed.

19. EXTRAS

A. Without invalidating Contract, Department may order extra work or make changes by altering, adding to or deducting from the Work, contract sum being adjusted in accordance with Article 18 herein.

20. TIME FOR COMPLETION

A. Contractor agrees that the Work shall be prosecuted regularly and diligently and complete the Work as stated in Construction Documents.

21. CORRECTION OF WORK

- A. All work, all materials whether incorporated in the Work or not, and all processes of manufacture shall at all times and places be subject to inspection of Architect / Engineer and Public Works Project Manager who shall be judge of quality and suitability of the Work, materials, and processes of manufacture for purposes for which they are used. Should they fail to meet Architect / Engineer's and Public Works Project Manager's approval they shall be reconstructed, made good, replaced or corrected, by Contractor at Contractor's expense. Immediately remove all rejected material from site.
- B. If Contractor defaults or neglects to carry out the Work in accordance with Construction Documents or fails to perform any provision of Contract, Department may, after ten (10) business days' written notice to Contractor and without prejudice to any other remedy County may have, make good such deficiencies. In such case, appropriate Change Order shall be issued deducting from Contractor's payments then or thereafter, cost of correcting such deficiencies, including cost of Architect / Engineer's additional services made necessary by such default, neglect or failure.

22. SUBSURFACE CONDITIONS FOUND DIFFERENT

A. If Contractor encounters subsurface or latent conditions at site materially differing from those shown on Drawings or indicated in Specifications, Contractor shall immediately give notice to Architect / Engineer and Public Works Project Manager of such conditions before they are

disturbed. Architect / Engineer will thereupon promptly investigate conditions, and if Architect / Engineer finds that they materially differ from those shown on Drawings or indicated in Specifications, Architect / Engineer will at once make such changes as necessary, any increase or decrease of cost resulting from such changes to be adjusted in manner provided in above Article 18 entitled "Changes in the Work".

23. RIGHT OF DEPARTMENT TO TERMINATE CONTRACT

- A. In event that any provisions of this Contract are violated by Contractor or by any subcontractors, County may serve written notice upon Contractor and Surety of its intention to terminate Contract, such notice to contain reasons for such intention to terminate Contract, and unless within ten (10) business days after serving of such notice upon Contractor, such violation or delay shall cease and satisfactory arrangement or correction be made, Contract shall, upon expiration of said ten (10) business days, cease and terminate.
- B. In event of any such termination, County shall immediately serve notice thereof upon Surety and Contractor, and Surety shall have right to take over and perform Contract subject to County's approval; provided, however, that if Surety does not commence performance thereof within ten (10) business days from date of mailing to such Surety of notice of termination, County may take over the Work and prosecute same to completion by contract, or by force account, at expense of Contractor; Contractor and Surety shall be liable to County for any excess cost occasioned County thereby, and in such event County may take possession of and utilize in completing the Work, such materials and equipment as may be on the Work site and therefore necessary.

24. CONSTRUCTION SCHEDULE AND PERIODIC ESTIMATES

- A. Contractor shall be responsible for Construction Schedule and coordination. Immediately after execution and delivery of Contract and before making first payment, Contractor shall notify all subcontractors to furnish all required information to develop Construction Schedule. Contractor and all subcontractors associated with the Work shall furnish following information from each Division of Specifications:
 - 1. List of construction activities;
 - 2. Start, finish and time required for completion of each activity;
 - 3. Sequential relationships between activities;
 - 4. Identify all long lead-time items, key events, meetings or activities such as required submittals, fabrication and delivery, procurement of materials, installation and testing;
 - 5. Weekly definition of extent of work and areas of activity for each trade or Subcontract; and
 - 6. Other information as determined by Public Works Project Manager.
- B. In addition to above requested items, Contractor shall request delivery dates for all County-furnished equipment, materials or labor. This shall include any work handled by Department under separate contracts such as asbestos abatement, air and water balancing, etc. Indicate on Construction Schedule these associated delivery and installation dates.

C. Progress Reporting:

Contractor shall update and publish Construction Schedule on monthly basis. Revisions
to Schedule shall be by Contractor and made in same detail as original Schedule and
accompanied by explanation of reasons for revision; and shall be subject to approval by
Department.

- 2. Failure of Contractor to keep Schedule in updated format shall result in County hiring firm specializing in construction schedule development and deducting those costs associated with updating process from payments due Contractor.
- 3. Contractor shall submit show actual percentage of each activity completed, estimated future progress, and anticipated completion time.
- D. Responsibility for timely completion requires:
 - 1. Contractor and subcontractors understand that performance of each is interdependent upon performance of others.
 - 2. Whenever it becomes apparent from current schedule, that phasing or progress completion dates will not be met, Contractor must take some or all following actions at no additional cost to County:
 - a) Increase construction labor in such quantities and crafts as will eliminate backlog of work.
 - b) Increase number of working hours per shift, shifts per working day, working days per week, amount of construction equipment, or any combination of foregoing to eliminate backlog of work.
 - c) Reschedule work (yet remain in conformance with Drawings and Specifications).
 - 3. Prior to proceeding with any of above actions, Contractor shall notify Public Works Project Manager.
- E. Maintain current Construction Schedule at all times. Revise Construction Schedule in same detail as original and accompany with explanation of reasons for revision. Schedule shall be subject to approval by Architect / Engineer and Public Works Project Manager.

25. PAYMENTS TO CONTRACTOR

- A. Contractor shall provide:
 - 1. Detailed estimate giving complete breakdown of contract price by Specification Division; and
 - 2. Periodic itemized estimates of work done for purpose of making partial payments thereon.
- B. Submit these estimates for approval first to Architect / Engineer, then to Public Works Project Manager. Costs employed in making up any of these schedules are for determining basis of partial payments and not considered as fixing basis for additions to or deductions from Contract price.
- C. County will make partial payments to Contractor for value, proportionate to amount of Contract, of all labor and material incorporated in the Work during preceding calendar month upon receipt of Application and Certificate for Payment form from Architect / Engineer and approval of Department.
- D. Contractor shall submit for approval first to Architect / Engineer, and then to Public Works Project Manager all Application and Certificate for Payment forms. If requested, Application and Certificate for Payment shall be supported by such additional evidence as may be required, showing Contractor's right to payment claimed.
- E. Application and Certificate for Payment for preparatory work and materials delivered and suitably stored at site to be incorporated into the Work at some future period, will be given due consideration. Requesting payment for materials stored off site, may be rejected, however, if deemed essential for reasons of job progress, protection, or other sufficient cause, requests will be considered, conditional upon submission by Contractor of bills of sale,

photographs and such other procedures as will adequately protect County's interest such as storage in bonded warehouse with adequate coverage. If there is any error in payment, Contractor is obligated to notify Department immediately, but no longer than ten (10) business days from receipt of payment.

- F. Payments by County will be due within forty-five (45) business days after receipt by Department of Application and Certificate for Payment.
- G. County will retain five percent (5%) of each Application and Certificate for Payment until final completion and acceptance of all the Work covered by Contract. However, anytime after fifty percent (50%) of the Work has been furnished and installed at site, County will make remaining payments in full if Architect / Engineer and Public Works Project Manager find that progress of the Work corresponds with Construction Schedule. If Architect / Engineer and Public Works Project Manager find that progress of the Work does not correspond with Construction Schedule, County may retain up to ten percent (10%) of each Application and Certificate for Payment for the Work completed.
- H. All material and work covered by partial payments made shall become sole property of County, but this provision shall not be construed as relieving Contractor from sole responsibility for care and protection of materials and work upon which payments have been made, or restoration of any damaged work, or as waiver of right of County to require fulfillment of all of terms of Contract.
- I. County will make final payment within sixty (60) calendar days after final completion of the Work, and will constitute acceptance thereof. Submit Equal Benefits Compliance Payment Certification with final pay request. Payment may be denied if Certification is not included.
- J. County may make payment in full, including retained percentages and less authorized deductions, upon completion and acceptance of each Division where price is stated separately in Contract.
- K. Every contractor engaged in performance of any contract for Department of Public Works, Highway & Transportation shall submit to this Department, as requested and with final application for payment for work under said contract, affidavit(s) as required to prove that all debts and claims against this Work are paid in full or otherwise satisfied, and give final evidence of release of all liens against the Work and County.

26. WITHHOLDING OF PAYMENTS

- A. County, after having served written notice on said Contractor, may either pay directly any unpaid bills of which Department has written notice, or withhold from Contractor's unpaid compensation sum of money deemed reasonably sufficient to pay any and all such lawful claims until satisfactory evidence is furnished that all liabilities have been fully discharged; whereupon, payment to Contractor shall be resumed in accordance with terms of this Contract, but in no event shall these provisions be construed to impose any obligations upon County to either Contractor or Contractor's Surety.
- B. In paying any unpaid bills of Contractor, County shall be deemed agent of Contractor, and any payment so made by County, shall be considered as payment made under Contract by County to Contractor and County shall not be liable to Contractor for any such payment made in good faith.

- C. Contractor shall indemnify, hold harmless and defend Dane County, its boards, commissions, agencies, officers, employees and representatives from all claims growing out of lawful demands of subcontractors, laborers, workers, mechanics, material men, and furnishers of machinery and parts thereof, equipment, power tools, and all supplies, including commissary, incurred in performance of this Contract.
- D. At Department's request, Contractor shall furnish satisfactory evidence that all obligations of nature designated above have been paid, discharged or waived.

27. ACCEPTANCE OF FINAL PAYMENT AS RELEASE

- A. Making of final payment shall constitute waiver of all claims by County except those arising from:
 - 1. Unsettled lien;
 - 2. Faulty or defective work appearing after substantial completion;
 - 3. Failure of the Work to comply with requirements of Construction Documents; or
 - 4. Terms of any special guarantees required by Construction Documents.
- B. Acceptance of final payment shall constitute waiver of all claims by Contractor.

28. PAYMENTS BY CONTRACTOR

- A. Contractor shall pay following not later than fifth (5th) business day following each payment received from County:
 - 1. All transportation and utility services rendered;
 - 2. All materials, tools, and other expendable equipment that have been delivered at site of the Work to extent of ninety percent (90%) of cost thereof, and balance of cost thereof when said balance is paid to Contractor; and
 - 3. Each subcontractor, respective amount allowed Contractor because of work performed by subcontractor to extent of subcontractor's interest therein.

29. CONTRACT SECURITY

- A. Contractor shall furnish Performance and Payment Bonds in amount at least equal to one hundred percent (100%) of Contract price as security for faithful performance of this Contract and payment of all persons performing labor on project under this Contract and furnishing materials in connection with this Contract.
- B. Sample Performance and Payment Bonds that Contractor will be required to execute is bound into these Construction Documents. Before construction Contract is consummated, completed Performance and Payment Bonds must be approved by Department.

30. ASSIGNMENTS

A. Contractor shall not assign whole or any part of this Contract or any moneys due or to become due hereunder without written consent of Department. In case Contractor assigns all or any part of any moneys due or to become due under this Contract, instrument of assignment shall contain clause substantially to effect that it is agreed that right of assignee in and to any moneys due or to become due to Contractor shall be subject to prior claims of all persons, firms and corporations for services rendered or materials supplied for performance of the Work called for in this Contract.

31. MUTUAL RESPONSIBILITY OF CONTRACTORS

A. If, through acts of neglect on part of Contractor or any subcontractor shall suffer loss or damage on the Work, Contractor agrees to settle with such subcontractor by agreement or arbitration if such other subcontractor will so settle. If such subcontractor shall assert any claim against County on account of any damage alleged to have been sustained, Department shall notify Contractor, who shall indemnify, hold harmless and defend Dane County, its boards, commissions, agencies, officers, employees and representatives against any such claim.

32. SEPARATE CONTRACTS

- A. Department may award other contracts for the Work and all Contractors shall fully cooperate with each other and carefully adjust their work to that provided under other contracts as may be directed by Department. No Contractor shall commit or permit any act that will interfere with performance of the Work by any other Contractor.
- B. Contractor shall coordinate the Work with those of other Contractors. Cooperation will be required in arrangement for storage of materials and in detailed execution of the Work. Contractor, including subcontractors, shall keep informed of progress and detail work of others and shall notify Architect / Engineer or Department immediately of lack of progress or defective workmanship on part of others. Failure of Contractor to keep informed of the Work progressing on site and failure to give notice of lack of progress or defective workmanship by others shall be construed as acceptance by Contractor of status of the Work as being satisfactory for proper coordination with Contractor's own work.

33. SUBCONTRACTS

- A. Contractor may use services of specialty subcontractors on those parts of the Work that, under normal contracting practices, are performed by specialty subcontractors.
- B. Contractor shall not award any work to any subcontractor without prior approval of Department. Qualifications of subcontractors shall be same as qualifications of Contractor. Request for subcontractor approval shall be submitted to Department fifteen (15) business days before start of subcontractor's work. If subcontractors are changed or added, Contractor shall notify Department in writing.
- C. Contractor shall be as fully responsible to County for acts and omissions of subcontractors, and of persons either directly or indirectly employed by them, as Contractor is for acts and omissions of persons directly employed by Contractor.
- D. Contractor shall cause appropriate provisions to be inserted in all subcontracts relative to the Work to bind subcontractors to Contractor by terms of General Conditions of Contract and other Construction Documents insofar as applicable to work of subcontractors and to give Contractor same power as regards terminating any subcontract that Department may exercise over Contractor under any provision of Construction Documents.
- E. Nothing contained in this Contract shall create any contractual relation between any subcontractor and County.
- F. Contractor shall insert in all subcontracts, Articles 26, 33, 43 and 45, respectively entitled: "Withholding of Payments", "Subcontracts", "Affirmative Action Provision and Minority /

Women / Disadvantaged Business Enterprises", and "Minimum Wages", and shall further require all subcontractors to incorporate physically these same Articles in all subcontracts.

34. PROJECT MANAGER'S AUTHORITY

- A. Public Works Project Manager shall:
 - 1. Administer and ensure compliance with Construction Documents;
 - 2. Provide responsible on-site observations of construction and have authority to request work and to stop work whenever necessary to insure proper enforcement of Construction Documents:
 - 3. Convene and chair project meetings and foreman's coordination meetings when necessary to coordinate resolution of conflicts between Contractors, Architects, Engineers, Consultants, and Department; and
 - 4. Check and inspect material, equipment and installation procedures of all trades for proper workmanship and for compliance with Drawings, Specifications and Shop Drawings, permit no material on project site that is not satisfactory and reject work not in compliance with Construction Documents.

35. CONSULTANT'S AUTHORITY

- A. Architect / Engineer is retained by, and is responsible to Department acting for County.
- B. Architect / Engineer shall determine amount, quality, acceptability, and fitness of several kinds of work and materials that are provided under this Contract and shall decide all questions that may arise in relation to said work and construction thereof.
- C. Architect / Engineer shall decide meaning and intent of any portion of Specifications and of any Drawings where they may be found obscure or be in dispute.
- D. Architect / Engineer shall provide responsible observation of construction. Architect / Engineer has authority to stop the Work whenever such stoppage may be necessary to insure proper execution of Construction Documents.
- E. Architect / Engineer shall be interpreter of conditions of Construction Documents and judge of its performance.
- F. Within reasonable time, Architect / Engineer shall make decisions on all matters relating to progress of the Work or interpretation of Construction Documents.
- G. Architect / Engineer's decisions are subject to review by Public Works Project Manager.

36. STATED ALLOWANCES

- A. Stated allowances enumerated in Instructions to Bidders shall cover net cost of materials or equipment, and all applicable taxes. Contractor's cost of delivery and unloading at site, handling costs on site, labor, installation costs, overhead, profit and any other incidental costs shall be included in Contractor's bid, but not as part of cash allowance.
- B. Department will solicit at least two (2) bids on materials or equipment for which allowance is stated and select on basis of lowest qualified responsible bid. Contractor will then be instructed to purchase "Allowed Materials". If actual price for purchasing "Allowed Materials", including taxes, is more or less than "Cash Allowance", Contract price shall be

adjusted accordingly. Adjustment in Contract price shall not contain any cost items excluded from cash allowance.

37. ESTIMATES OF QUANTITIES

A. Whenever estimated quantities of work to be done and materials to be furnished under this Contract are shown in any of Construction Documents, they are given for use in comparing bids and right is especially reserved to increase or diminish them as they may be deemed reasonably necessary or desirable by Department to complete the Work included in this Contract, and cost for such increase or diminution shall be adjusted in manner provided for in General Conditions of Contract Article 18 entitled "Changes in the Work".

38. LANDS AND RIGHTS-OF-WAY

A. Prior to start of construction, County shall furnish all land and rights-of-way necessary for carrying out and completion of the Work to be performed under this Contract.

39. GENERAL GUARANTEE

- A. Neither final certificate of payment nor any provision in Construction Documents nor partial or entire occupancy of premises by County shall constitute acceptance of work not done in accordance with Construction Documents or relieve Contractor of liability in respect to any expressed warranties or responsibility for faulty materials or workmanship.
 - 1. In no event shall making of any payment required by Contract constitute or be construed as waiver by County of any breach of covenants of Contract or waiver of any default of Contractor and making of any such payment by County while any such default or breach shall exist shall in no way impair or prejudice right of County with respect to recovery of damages or other remedy as result of such breach or default.
- B. Contractor shall remedy and make good all defective workmanship and materials and pay for any damage to other work resulting there from, which appear within period of one (1) year from date of substantial completion, providing such defects are not clearly due to abuse or misuse by County. Department will give notice of observed defects with reasonable promptness.
- C. Guarantee on work executed after certified date of substantial completion will begin on date when such work is inspected and approved by Architect / Engineer and Public Works Project Manager.
- D. Where guarantees or warrantees are required in sections of Specifications for periods in excess of one (1) year, such longer terms shall apply; however, Contractor's Performance and Payment Bonds shall not apply to any guarantee or warranty period in excess of one (1) year.

40. CONFLICTING CONDITIONS

- A. Any provision in any of Construction Documents which may be in conflict or inconsistent with any Articles in these General Conditions of Contract or Supplementary Conditions shall be void to extent of such conflict or inconsistency.
- B. In case of ambiguity or conflict between Drawings and Specifications, Specifications shall govern.

C. Printed dimensions shall be followed in preference to measurements by scale. Large-scale drawings take precedence over small-scale drawings. Dimensions on Drawings and details are subject to field measurements of adjacent work.

41. NOTICE AND SERVICE THEREOF

A. Any notice to Contractor from Department relative to any part of this Contract shall be in writing and considered delivered and service thereof completed, when said notice is posted, by certified or registered mail, to Contractor at Contractor's last given address, or delivered in person to said Contractor, or Contractor's authorized representative on the Work.

42. PROTECTION OF LIVES AND HEALTH

- A. In order to protect lives and health of Contractor's employees under Contract, Contractor shall comply with all pertinent provisions of Wisconsin Administrative Code, Rules of Department of Commerce, relating to Safety and Health.
- B. Contractor alone shall be responsible for safety, efficiency and adequacy of Contractor's tools, equipment and methods, and for any damage that may result from their failure or their improper construction, maintenance or operation.

43. AFFIRMATIVE ACTION PROVISION AND MINORITY / WOMEN / DISADVANTAGED BUSINESS ENTERPRISES

A. Affirmative Action Provisions.

- 1. During term of their Contract, Contractor agrees not to discriminate on basis of race, religion, color, sex, handicap, age, sexual preference, marital status, physical appearance, or national origin against any person, whether recipient of services (actual or potential), employee, or applicant for employment. Such equal opportunity shall include but not be limited to following: employment, upgrading, demotion, transfer, recruitment, advertising, layoff, termination, training, rates of pay, and any other form of compensation or level of service(s). Contractor agrees to post in conspicuous places, these affirmative action standards so as to be visible to all employees, service recipients and applicants for this paragraph. Listing of prohibited bases for discrimination shall no be construed to amend in any fashion state or federal law setting forth additional bases and exceptions shall be permitted only to extent allowable in state or federal law.
- 2. Contractor is subject to this Article only if Contractor has ten (10) or more employees and receives \$10,000.00 or more in annual aggregate contracts with County. Contractor shall file and Affirmative Action Plan with Dane County Contract Compliance Officer in accord with Chapter 19 of Dane County Code of Ordinances. Such plan must be filed within fifteen (15) business days of effective date of this Contract and failure to do so by said date shall constitute ground for immediate termination of Contract by County. Contractor shall also, during term of this Contract, provide copies of all announcements of employment opportunities to County's Contract Compliance Office, and shall report annually number of persons, by race, sex and handicap status, who apply for employment, and, similarly classified, number hired and number rejected.
- 3. Contact Dane County Contract Compliance Officer at Dane County Contract Compliance Office, 210 Martin Luther King, Jr. Blvd., Room 421, Madison, WI 53703, 608/266-4114.
- 4. In all solicitations for employment placed on Contractor's behalf during term of this Contract, Contractor shall include statement to affect Contractor is "Equal Opportunity Employer". Contractor agrees to furnish all information and reports required by

County's Contract Compliance Officer as same relate to affirmative action and nondiscrimination, which may include any books, records, or accounts deemed appropriate to determine compliance with Chapter 19, Dane County Code of Ordinances, and provision of this Contract.

- B. Minority / Women / Disadvantaged / Emerging Small Business Enterprises.
 - 1. Chapter 19.508 of Dane County Code of Ordinances is official policy of Dane County regarding utilization of, to fullest extent of, Minority Business Enterprises (MBEs), Women Business Enterprises (WBEs) Disadvantage Business Enterprises (DBEs) and Emerging Small Business Enterprises (ESBEs).
 - 2. Contractor may utilize MBEs / WBEs / DBEs / ESBEs as subcontractors or suppliers. List of subcontractors will be required of low bidder as stated in this Contract. List shall indicate which are MBEs / WBEs / DBEs / ESBEs and percentage of subcontract awarded, shown as percentage of total dollar amount of bid.

44. COMPLIANCE WITH FAIR LABOR STANDARDS

- A. During term of this Contract, Contractor shall report to County Contract Compliance Officer, within ten (10) business days, any allegations to, or findings by National Labor Relations Board (NLRB) or Wisconsin Employment Relations Commission (WERC) that Contractor has violated statute or regulation regarding labor standards or relations. If investigation by Contract Compliance Officer results in final determination that matter adversely affects Contractor's responsibilities under this Contract, and which recommends termination, suspension or cancellation of this Contract, County may take such action.
- B. Contractor may appeal any adverse finding by Contract Compliance Officer as set forth in Dane County Ordinance 25.015(11)(c) through (e).
- C. Contractor shall post this statement in prominent place visible to employees: "As condition of receiving and maintaining contract with Dane County, this employer shall comply with federal, state and all other applicable laws prohibiting retaliation or union organizing."

45. DOMESTIC PARTNERSHIP BENEFITS

A. Not Used.

46. USE AND OCCUPANCY PRIOR TO ACCEPTANCE

- A. Contractor agrees to use and occupancy of portion or unit of the Work before formal acceptance by Department, provided Department:
 - 1. Secures written consent of Contractor; except when in opinion of Public Works Project Manager, Contractor is chargeable with unwarranted delay in final cleanup of punch list items or other Contract requirements.
 - 2. Secures endorsement from insurance carrier and consent of Surety permitting occupancy of building or use of the Work during remaining period of construction, or, secures consent of Surety.
 - 3. Assumes all costs and maintenance of heat, electricity and water.
 - 4. Accepts all work completed within that portion or unit of the Work to be occupied, at time of occupancy.

47. MINIMUM WAGES

- A. Contractor shall post, at appropriate conspicuous point on site of project, schedule showing all determined minimum wage rates for various classes of laborers and mechanics to be engaged in the Work under this Contract and all deductions, if any, required by law to be made from unpaid wages actually earned by laborers and mechanics so engaged.
- B. Supplementary Conditions section in Construction Documents lists wage determinations required by State Law.
- C. If, after award of Contract, it becomes necessary to employ any person in trade or occupation not classified in wage determinations, such person shall be paid at not less than such rate as shall be determined by Wisconsin Department of Workforce Development. Such approved minimum rate shall be retroactive to time of initial employment of such person in such trade or occupation. Contractor shall notify Department of Contractor's intention to employ persons in trades or occupations not so classified in sufficient time for Department to obtain approved rates for such trades or occupations.
- D. Specified wage rates are minimum rates only, and Department will not consider any claims for additional compensation made by Contractor because of payment by Contractor of any wage rate in excess of applicable rate contained in this Contract. Contractor shall adjust any disputes in regard to payment of wages in excess of those specified in this Contract.

48. CLAIMS

A. No claim may be made until Department's Deputy Public Works Director has reviewed Architect / Engineer's decision as provided for in Article 35 of General Conditions of Contract. If any claim remains unresolved after such review by Department's Deputy Public Works Director the claim may be filed under Wisconsin Statute 893.80. Work shall progress during period of any dispute or claim. Unless specifically agreed between parties, venue will be in Dane County, Wisconsin.

49. ANTITRUST AGREEMENT

A. Contractor and County recognize that in actual economic practice, overcharges resulting from antitrust violations are in fact usually borne by County. Therefore, Contractor hereby assigns to County any and all claims for such overcharges as to goods and materials purchased in connection with this Contract, except as to overcharges which result from antitrust violations commencing after price is established under this Contract and any change order thereto.

50. INSURANCE

- A. Contractor Carried Insurance:
 - Contractor shall not commence work under this Contract until Contractor has obtained all
 insurance required under this Article and has provided evidence of such insurance to Risk
 Manager, 425 City-County Building, 210 Martin Luther King Jr. Blvd., Madison, WI
 53703. Contractor shall not allow any subcontractor to commence work until insurance
 required of subcontractor has been so obtained and approved. Company providing
 insurance must be licensed to do business in Wisconsin.
 - 2. Worker's Compensation Insurance:
 - a) Contractor shall procure and shall maintain during life of this Contract, Worker's Compensation Insurance as required by statute for all of Contractor's employees engaged in work at site of project under this Contract and, in case of any such work sublet, Contractor shall require subcontractor similarly to provide Worker's

- Compensation Insurance for all of latter's employees to be engaged in such work unless such employees are covered by protection afforded by Contractor's Worker's Compensation Insurance.
- b) If any claim of employees engaged in hazardous work on project under this Contract is not protected under Worker's Compensation Statute, Contractor shall provide and shall cause each subcontractor to provide adequate Employer's Liability Insurance for protection of such of Contractor's employees as are not otherwise protected.
- 3. Contractor's Public Liability and Property Damage Insurance:
 - a) Contractor shall procure and maintain during life of this Contract, Contractor's Public Liability Insurance and Contractor's Property Damage Insurance in amount not less than \$1,000,000 bodily injury, including accidental death, to any one person, and subject to same limit for each person, in amount not less than \$1,000,000 on account of one accident, and Contractor's Property Damage Insurance in amount not less then \$1,000,000 or combined single limit of at least \$1,000,000 with excess coverage over and above general liability in amount not less than \$5,000,000. Contractor shall add "Dane County" as additional insured for each project.
 - b) Contractor's Public Liability and Property Damage Insurance shall include Products, Completed Operation, and Contractual Liability under Insurance Contract. "Contractor shall in all instances save, defend, indemnify and hold harmless County and Architect / Engineer against all claims, demands, liabilities, damages or any other costs which may accrue in prosecution of the Work and that Contractor will save, defend, indemnify and hold harmless County and Architect / Engineer from all damages caused by or as result of Contractor's operations" and each shall be listed as additional insured on Contractor's and subcontractors' insurance policies.
 - c) Obligations of Contractor under Article 50.A.2.b) shall not extend to liability of Architect / Engineer, agents or employees thereof, arising out of:
 - 1) Preparation or approval of maps, drawings, opinions, reports, surveys, change orders, designs or specifications; or
 - 2) Giving of or failure to give directions or instructions by Architect / Engineer, agents or employees thereof provided such giving or failure to give is primary cause of injury or damage.
 - d) Contractor shall procure and shall maintain during life of this Contract, Comprehensive Automobile Liability Insurance covering owned, non-owned and hired automobiles for limits of not less than \$1,000,000 each accident single limit, bodily injury and property damage combined with excess coverage over and above general liability in amount not less than \$5,000,000.
 - e) Contractor shall either:
 - Require each subcontractor to procure and to maintain during life of subcontract, subcontractor's Public Liability Property Damage Insurance, and Comprehensive Automobile Liability Insurance of type and in same amount specified in preceding paragraphs; or
 - 2) Insure activities of subcontractors in Contractor's own policy.
- 4. Scope of Insurance and Special Hazards: Insurance required under Article 50.A.2 & 50.A.3. hereof shall provide adequate protection for Contractor and subcontractors, respectively, against damage claims which may arise from operations under this Contract, whether such operation be by insured or by anyone directly or indirectly employed by insured and also against any of special hazards which may be encountered in performance of this Contract as enumerated in Supplementary Conditions.
- 5. Proof of Carriage of Insurance: Contractor shall furnish Risk Manager with certificates showing type, amount, class of operations covered, effective dates, dates of expiration of policies and "Dane County" listed as additional insured. Such certificates shall also contain (substantially) following statement: "Insurance covered by this certificate will not be canceled or materially altered, except after ten (10) business days written notice has been received by Risk Manager."

B. Builder's Risk:

1. County shall provide Builder's Risk insurance coverage for its insurable interests in construction or renovation projects with completed value of \$1,000,000 or less. Therefore, if project completed value is more than \$1,000,000, Contractor shall obtain and maintain in force, at its own expense, Builder's Risk Insurance on all risks for amount equal to full completed value of covered structure or replacement value of alterations or additions. Any deductible shall not exceed \$25,000 for each loss. Policy shall include occupancy clause and list Dane County as loss payee.

C. Indemnification / Hold Harmless:

- 1. Contractor shall indemnify, hold harmless and defend Dane County, its boards, commissions, agencies, officers, employees and representatives from and against all claims, damages, losses and expenses including attorneys' fees arising out of or resulting from performance of the Work, provided that any such claim, damage, loss or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself) including loss of use resulting therefrom, and is caused in whole or in part by any act or omission of Contractor, any subcontractor, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, regardless of whether or not it is caused in part by part indemnified hereunder.
- 2. In any and all claims against Dane County, its boards, commissions, agencies, officers, employees and representatives or by any employee of Contractor, any subcontractor, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, indemnification obligation under this Contract shall not be limited in any way by any limitation on amount or type of damages, compensation or benefits payable by or for Contractor or any subcontractor under worker's compensation acts, disability benefits or other employee benefit acts.
- 3. Obligations of Contractor under this Contract shall not extend to liability of Architect / Engineer, its agents or employees arising out of:
 - a) Preparation or approval of maps, drawings, opinion, reports, surveys, change orders, designs or specifications; or
 - b) Giving of or failure to give directions or instruction by Architect / Engineer, its agents or employees provided such giving or failure to give is primary cause of injury or damage.
- 4. Dane County shall not be liable to Contractor for damages or delays resulting from work by third parties or by injunctions or other restraining orders obtained by third parties.

51. WISCONSIN LAW CONTROLLING

A. It is expressly understood and agreed to by parties hereto that in event of any disagreement or controversy between parties, Wisconsin law shall be controlling.

END OF SECTION

SECTION 00 73 00


SUPPLEMENTARY CONDITIONS

1. APPLICATION & CERTIFICATE FOR PAYMENT

A. Every contractor engaged in performance of any contract for Department of Public Works, Highway & Transportation shall submit partial and final Application & Certificate for Payment for work under said contract. Form shall provide similar information as shown on AIA G702TM and G703TM forms (samples shown below). Forms shall be submitted to Public Works Project Manager for approval.

Application and Certificate for P	ayment			
TO OWNER:	PROJECT:		APPLICATION NO:	Distribution to:
			PERIOD TO:	OWNER
			CONTRACT FOR:	ARCHITECT
FROM CONTRACTOR:	VIA ARCHIT	ECT:	CONTRACT DATE:	CONTRACTOR
			PROJECT NOS:	FIELD 🗆
CONTRACTOR'S APPLICATION FOR			The undersigned Contractor certifies that to the best of the Contractor	OTHER
AIÁ Document G703 ³⁴ Continuation Sheet, is attache 1, ORIGINAL CONTRACT SUM 2. NET CHANGE BY CHANGE ORDERS 3. CONTRACT SUM TO DATE (Line 1 = 2) 4. TOTAL COMPLETED & STORED TO DATE (Column G 5. RETAINAGE: 8. % of Completed Work (Columns D + E on G703) b. % of Stored Material (Column F on G703) Total Retainage (Lines 5a + 5b, or Total in Column 5. TOTAL EARNED LESS RETAINAGE (Line 4 minus Line 5 Total) T. LESS PREVIOUS CERTIFICATES FOR PAYMENT (Line 6 from prior Certificate) 8. CURRENT PAYMENT DUE 9. BALANCE TO FINISH, INCLUDING RETAINAGE (Line 3 minus Line 6)	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$		State of: County of: Subscribed and sworn to before me this My commission expires: ARCHITECT'S CERTIFICATE FOR PAYMENT In accordance with the Contract Documents, based on on-site observation this application, the Architect certifies to the Owner that to the best of the information and belief the Work has progressed as indicated, the quaccordance with the Contract Documents, and the Contractor is en AMOUNT CERTIFIED. AMOUNT CERTIFIED AMOUNT CERTIFIED Subscribed and sworn to be fore the Amount applied. If Application and on the Continuation Sheet that are changed to conforms.	as and the data comprising the Architect's knowledge, tality of the Work is in titled to payment of the work and the work of t
CHANGE ORDER SUMMARY	ADDITIONS	DEDUCTIONS	ARCHITECT:	
Total changes approved in previous months by Owner	22.7	S		
Total approved this month	s s	\$	This Certificate is not negotiable. The AMOUNT CERTIFIED is payable	
TOTAL NET CHANGES by Change Order	5	3	named herein. Issuance, payment and acceptance of payment are without the Owner or Contractor under this Contract.	rejudice to any rights of
	2			

RFB No. 320002 rev. 01/2020



2. INSURANCE

A. Not Applicable.

3. ASBESTOS DISPOSAL PROCEDURES

A. Not Applicable.

END OF SECTION

RFB No. 320002 rev. 01/2020



Department of Public Works, Highway & Transportation

Public Works Engineering Division

Gerald J. Mandli, P.E.

Commissioner / Director

Deputy Director Todd Draper 608/266-4018

Joseph T. Parisi
County Executive

1919 Alliant Energy Center Way Madison, Wisconsin 53713 Fax: 608/267-1533 www.countyofdane.com/pwht/public_works.aspx

BEST VALUE CONTRACTING APPLICATION

CONTRACTORS / LICENSURE APPLICANTS

The Dane County Department of Public Works requires contractors & subcontractors to be a Best Value Contractor before being hired. Contractor & subcontractor application documents should be turned in immediately. Contractor approval or exemption must be complete prior to Bid Due Date / Time. All subcontractors must also be approved or prove their exemption before performing any work under a County contract. This document shall be completed, properly executed, along with the necessary attachments and additional information that the County requires for the protection and welfare of the public in the performance of a County contract.

Contractors or subcontractors of any tier who attain qualification status will retain that status for a period of two (2) years from the date of qualification. Contractors shall notify the Dane County Department of Public Works, Highway & Transportation within fifteen (15) days of any changes to its business or operations that are relevant to the application. Failure to do so could result in suspension, revocation of the contractor's qualification, debarment from County contracts for up to three (3) years and / or other sanctions available under the law.

No contracts will be awarded for construction work performed on Dane County projects unless the contractor is currently approved as a Wisconsin Trade Trainer or has applied for approval as an Apprenticeship Trade Trainer to the Wisconsin Department of Workforce Development and agrees to an acceptable apprenticeship program. If you are not currently approved as a Wisconsin Trade Trainer, or have not applied for approval as an Apprenticeship Trade Trainer, please contact the Department of Workforce Development - Bureau of Apprenticeship Standards at 608/266-3133 or visit their web site at: https://dwd.wisconsin.gov/apprenticeship/.

EXEMPTIONS

- Contractors who employ less than five (5) apprenticeable trade workers are not required to qualify.
- Contractors performing work that does not apply to an apprenticeable trade, as outlined in Appendix A.
- The contractor / subcontractor provides sufficient documentation to demonstrate one or more of the following:
 - o apprentices are not available in a specific geographic area;
 - o the applicable apprenticeship program is unsuitable or unavailable; or
 - o there is a documented depression of the local construction market which prevents compliance.

SEC.	PROOF OF RESPONSIBILITY	CHECK IF APPLICABLE
1	Does your firm possesses all technical qualifications and resources,	
	including equipment, personnel and financial resources, necessary to	
	perform the work required for any project or obtain the same through	Yes: No:
	the use of responsible, qualified subcontractors?	
2	Will your firm possess all valid, effective licenses, registrations or	
	certificates required by federal, state, county, or local law, which are	
	necessary for the type of work to be performed including, but not	Yes: No:
	limited to, those for any type of trade work or specialty work?	
3	Will your firm meet all bonding requirements as required by applicable	
	law or contract specifications?	Yes: No:
4	Will your firm meet all insurance requirements as required by	
	applicable law or specifications, including general liability insurance,	
	workers compensation insurance and unemployment insurance	Yes: No:
	requirements?	
5	Will your firm maintain a substance abuse policy for employees hired	v
	for public works contracts that comply with Wis. Stats. Sec. 103.503?	Yes: No:
6	Will your firm fully abide by the equal opportunity and affirmative	
	action requirements of all applicable laws, including County	Yes: No:
	ordinances?	
7	In the past three (3) years, has your firm had control or has another	
	corporation, partnership or other business entity operating in the	Yes: No:
	construction industry controlled it? If so, please attach a statement	If Yes, attach details.
	explaining the nature of the firm relationship?	·
8	In the past three (3) years, has your firm had any type of business,	,
	contracting or trade license, certification or registration revoked or	Yes: No: No:
	suspended?	If Yes, attach details.
9	In the past three (3) years, has your firm been debarred by any federal,	Yes: No:
	state or local government agency?	If Yes, attach details.
10	In the past three (3) years, has your firm defaulted or failed to complete	Yes: No:
	any contract?	If Yes, attach details.
11	In the past three (3) years, has your firm committed a willful violation	Van D
	of federal, state or local government safety laws as determined by a	Yes: No: If Yes, attach details.
	final decision of a court or government agency authority.	ii ies, attacii detaiis.
12	In the past three (3) years, has your firm been in violation of any law	Yes: No:
	relating to your contracting business where the penalty for such	If Yes, attach details.
	violation resulted in the imposition of a penalty greater than \$10,000?	ii 105, attacii detaiis.
13	Is your firm an active Wisconsin Trade Trainer as determined by the	Yes: No:
	Wisconsin Bureau of Apprenticeship Standards?	100.
14	Is your firm exempt from being qualified with Dane County?	Yes: No:
		If Yes, attach reason for exemption.
15	Does your firm acknowledge that in doing work under any County	
	Public Works Contract, it will be required to use as subcontractors only	, , , , , , , , , , , , , , , , , , ,
	those contractors that are also qualified with the County or become so	Yes: No: No:
	within five (5) days after the Bid Due Date?	
16	Contractor has been in business less than one year?	Yes: No:
17	Le confirme Continue Continue Continue	103.
17	Is your firm a first time Contractor requesting a one time exemption,	,,
	but, intend to comply on all future contracts and are taking steps	Yes: No: No:
	typical of a "good faith" effort?	

SIGNATURE SECTION

Your firm's Officer, or the individual who would sign a bid and / or contract documents must sign this document.

I do hereby certify that all statements herein contained are true and correct to the best of my knowledge:

Signature:				
(Application is invalid without signature)				
Print Name:	Date:			
Title:				

NAME AND ADDRESS OF CONTRACTOR		
Name of Firm:		
Address:		
City, State, Zip:		
Phone Number:		
Fax Number:		
E-mail Address:		

REMEMBER!

RETURN ALL TO FORMS AND ATTACHMENTS, OR QUESTIONS TO:

TODD DRAPER EMAIL: DRAPER@COUNTYOFDANE.COM OFFICE: (608) 267-0119, FAX: (608) 267-1533

DANE COUNTY DEPARTMENT OF PUBLIC WORKS, HGHWAY & TRANSPORTATION 1919 ALLIANT ENERGY CENTER WAY MADISON, WI 53713

rev. 07/2020 00 73 07 - 3

APPENDIX A

APPRENTICEABLE TRADES:

- Bricklayer
- Carpenter
- Cement Mason (Concrete Finisher)
- Cement Mason (Heavy Highway)
- Construction Craft Laborer
- Data Communications Installer
- Electrician
- Elevator Mechanic / Technician
- Environmental Systems Technician / HVAC Service Technician / HVAC Install & Service
- Glazier
- Heavy Equipment Operator / Operating Engineer
- Insulation Worker (Heat & Frost)
- Iron Worker (Assembler, Metal Buildings)
- Painter / Decorator
- Plasterer
- Plumber
- Roofer / Waterproofer
- Sheet Metal Worker
- Sprinkler Fitter
- Steamfitter (Service & Refrigeration)
- Taper & Finisher
- Telecommunications (Voice, Data & Video) Installer / Technician
- Tile Setter

END OF SECTION

SECTION 00 73 11

FAIR LABOR PRACTICES CERTIFICATION

The undersigned, for and on behalf of the BIDDER, APPLICANT or PROPOSER named herein, certifies as follows:

A. That he or she is an officer or duly authorized agent of the above-referenced BIDDER, APPLICANT or PROPOSER, which has a submitted a bid, application or proposal for a contract or agreement with the county of Dane.

B. That BIDDER, APPLICANT or PROPOSER has (check one):

______ not been found by the National Labor Relations Board ("NLRB") or the Wisconsin Employment Relations Commission ("WERC") to have violated any statute or regulation regarding labor standards or relations in the seven years prior to the signature date of this Certification.

_____ been found by the National Labor Relations Board ("NLRB") or the Wisconsin Employment Relations Commission ("WERC") to have violated any statute or regulation regarding labor standards or relations in the seven years prior to the signature date of this Certification.

Officer or Authorized Agent Signature

Date

NOTE: You can find information regarding the violations described above at: www.nlrb.gov and www.nlrb.gov and www.nlrb.gov

For reference, Dane County Ordinance 25.09 is as follows:

Printed or Typed Name and Title

Printed or Typed Business Name

(1) BIDDER RESPONSIBILITY. (a) Any bid, application or proposal for any contract with the county, including public works contracts regulated under chapter 40, shall include a certification indicating whether the bidder has been found by the National Labor Relations Board (NLRB) or the Wisconsin Employment Relations Committee (WERC) to have violated any statute or regulation regarding labor standards or relations within the last seven years. The Controller shall investigate any such finding and make a recommendation to the committee, which shall determine whether the conduct resulting in the finding affects the bidder's responsibility to perform the contract.

If you indicated that the NLRB or WERC have found you to have such a violation, you must include copies of any relevant information regarding such violation with your proposal, bid or application.

Include this completed Certification with your bid, application or proposal.

END OF SECTION

Bid No. 320002 Fair Labor Pract rev. 10/19

SECTION 01 00 00

GENERAL REQUIREMENTS

PART 1 GENERAL

1.1 SUMMARY

A	α	т .	1 1
Α.	Section	Inc	ludes:

- 1. Summary
- 2. Summary of the Work
- 3. Contractor Use of Premises
- 4. Applications for Payment
- 5. Change Procedures
- 6. Alternates
- 7. Lump Sum Allowances for Work
- 8. Coordination
- 9. Cutting and Patching
- 10. Conferences
- 11. Progress Meetings
- 12. Job Site Administration
- 13. Submittal Procedures
- 14. Proposed Products List
- 15. Shop Drawings
- 16. Product Data
- 17. Samples
- 18. Manufacturers' Instructions
- 19. Manufacturers' Certificates
- 20. Quality Assurance / Quality Control of Installation
- 21. References
- 22. Interior Enclosures
- 23. Protection of Installed Work
- 24. Parking
- 25. Staging Areas
- 26. Occupancy During Construction and Conduct of Work
- 27. Protection
- 28. Progress Cleaning
- 29. Products
- 30. Transportation, Handling, Storage and Protection
- 31. Product Options
- 32. Substitutions
- 33. Starting Systems
- 34. Demonstration and Instructions
- 35. Contract Closeout Procedures
- 36. Final Cleaning
- 37. Adjusting
- 38. Operation and Maintenance Data
- 39. Spare Parts and Maintenance Materials

40. As-Built and Record Drawings and Specifications

1.2 SUMMARY OF THE WORK

- A. Project Description: Perform the Work as specified and detailed in Construction Documents package. Contractor to provide construction services for a photovoltaic array on the roof of the Dane County Consolidated Food Service Building.
- B. Work by Owner: Not applicable.
- C. Permits: Prior to commencement of the Work, Contractor to secure any and all necessary permits for completion of the Work and facility occupancy. Provide Public Works Project Manager with copies of all permits.
- D. Diggers Hotline:
 - 1. It is General Contractor's responsibility to contact Diggers Hotline to have all utility locations marked prior to excavation and planning excavation so as not to delay the Work.
 - 2. Diggers Hotline shall also be used to obtain information on safe working clearances from overhead lines.
 - 3. Completely comply with all requirements of each affected utility company.
 - 4. It is General Contractor's responsibility to contact & hire private utility locating services if necessary.

1.3 CONTRACTOR USE OF PREMISES

- A. Limit use of premises to allow work by others and work by Owner.
- B. Coordinate utility outages and shutdowns with Owner.

1.4 APPLICATIONS FOR PAYMENT

- A. Submit one (1) original copies with "wet" signatures of each application on AIA G702TM and G703TM forms or approved contractors invoice form.
- B. Content and Format: Utilize Schedule of Values for listing items in Application for Payment.
- C. Payment Period: Monthly.
- D. Submit Applications for Payment to Public Works Project Manager for approval & processing for payment.

1.5 CHANGE PROCEDURES

A. Contractor's costs for Products, delivery, installation, labor, insurance, payroll, taxes, bonding, equipment rental, overhead and profit will be included in Change Orders authorizing expenditure of funds from contingency allowance.

1.6 ALTERNATES

A. Not Applicable.

1.7 LUMP SUM ALLOWANCES FOR WORK

A. Not Applicable.

1.8 COORDINATION

- A. Coordinate scheduling, submittals, and work of various sections of Specifications to assure efficient and orderly sequence of installation of interdependent construction elements.
- B. Verify utility requirement characteristics of operating equipment are compatible with building utilities.
- C. Coordinate space requirements and installation of mechanical and electrical work that are indicated diagrammatically on Drawings.
- D. Refer to Drawings for recommended work sequence and duration.
- E. Contractor shall provide Public Works Project Manager with work plan that ensures the Work will be completed within required time of completion.
- F. Public Works, Waste & Renewables Project Manager may choose to photograph or videotape site or workers as the Work progresses.

1.9 CUTTING AND PATCHING

- A. Employ skilled and experienced installer to perform cutting and patching new work; restore work with new Products.
- B. Submit written request in advance of cutting or altering structural or building enclosure elements.
- C. Fit work tight to adjacent elements. Maintain integrity of wall, ceiling, or floor construction; completely seal voids.
- D. Refinish surfaces to match adjacent finishes.

1.10 CONFERENCES

- A. Project shall have pre-bid conference; see Instructions to Bidders.
- B. Owner will schedule preconstruction conference after Award of Contract for all affected parties.
- C. Contractor shall submit Construction Schedule at pre-construction meeting.
- D. When required in individual Specification section, convene pre-installation conference at project site prior to commencing work of Section.

1.11 PROGRESS MEETINGS

- A. Schedule and administer meetings throughout progress of the Work at minimum of one (1) per week, at time TBD with Public Works, Waste & Renewables Project Manager.
- B. Preside at meetings, record minutes, and distribute copies within two (2) business days to those affected by decisions made.
- C. Attendance at progress meetings by General Contractor, subcontractors, or their authorized representative, is mandatory.
- D. Contractors shall give verbal reports of progress on the Work, discuss schedule for upcoming period and present all conflicts, discrepancies or other difficulties for resolution.
- E. Day & time of progress meetings to be determined at pre-construction meeting.

1.12 JOB SITE ADMINISTRATION

- A. Contractor shall have project superintendent on site minimum of four (4) hours per day during progress of the Work.
- B. Contractor shall not change their project superintendent or project manager for duration of the Work without written permission of Public Works Project Manager.
- C. Architect / Engineer shall have representative on site regularly during progress of the Work.

1.13 SUBMITTAL PROCEDURES

- A. Submittal form to identify Project, Contractor, Subcontractor or supplier; and pertinent Construction Documents references.
- B. Apply Contractor's stamp, signed or initialed, certifying that review, verification of Products required, field dimensions, adjacent construction work, and coordination of information is in accordance with requirements of the Work and Construction Documents.

- C. Identify variations from Construction Documents and Product or system limitations that may be detrimental to successful performance of completing the Work.
- Revise and resubmit submittals as required; identify all changes made since previous submittal.

1.14 PROPOSED PRODUCTS LIST

A. Within fifteen (15) business days after date of Award of Contract, submit complete list of major Products proposed for use, with name of manufacturer, trade name, and model number of each Product.

1.15 SHOP DRAWINGS

A. Submit number of copies that Contractor requires, plus three (3) copies that shall be retained by Public Works Project Manager.

1.16 PRODUCT DATA

- A. Submit number of copies that Contractor requires, plus two (2) copies that shall be retained by Public Works Project Manager.
- B. Mark each copy to identify applicable products, models, options, and other data. Supplement manufacturer's standard data to provide information unique to this Project.

1.17 SAMPLES

- A. Submit samples to illustrate functional and aesthetic characteristics of Product.
- B. Submit samples of finishes from full range of manufacturers' standard colors, textures, and patterns for Public Works Project Manager's selection.

1.18 MANUFACTURERS' INSTRUCTIONS

A. When specified in individual Specification sections, submit manufacturers' printed instructions for delivery, storage, assembly, installation, start-up, adjusting, and finishing, in quantities specified for Product Data.

1.19 MANUFACTURERS' CERTIFICATES

- A. When specified in individual Specification sections, submit manufacturers' certificate to Public Works Project Manager for review, in quantities specified for Product Data.
- B. Indicate material or Product conforms to or exceeds specified requirements. Submit supporting reference data, affidavits, and certifications as appropriate.

Bid No. 320002 General Requirements rev. 01/2020 01 00 00 - 5

1.20 QUALITY ASSURANCE / QUALITY CONTROL OF INSTALLATION

- A. Monitor quality control over suppliers, manufacturers, Products, services, site conditions, and workmanship, to produce work of specified quality.
- B. Comply fully with manufacturers' instructions.
- C. Comply with specified standards as minimum quality for the Work except when more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.

1.21 REFERENCES

- A. Conform to reference standard by date of issue current as of date for receiving bids.
- B. Should specified reference standard conflict with Construction Documents, request clarification from Public Works Project Manager before proceeding.

1.22 INTERIOR ENCLOSURES

A. Provide temporary partitions as required to separate work areas from Owner occupied areas, to prevent distribution of dust and moisture into Owner occupied areas, and to prevent damage to existing materials and equipment.

1.23 PROTECTION OF INSTALLED WORK

A. Protect installed work and provide special protection where specified in individual Specification sections.

1.24 PARKING

- A. Arrange for temporary parking areas to accommodate construction personnel. Parking shall be available at the Work site.
- B. All contractors and their employees shall cooperate with General Contractor and others in parking of vehicles to avoid interference with normal operations and construction activities.
- C. Do not obstruct existing service drives and parking lots with equipment, materials and / or vehicles. Keep accessible for Owner's use at all times.

1.25 STAGING AREAS

- A. Coordinate staging areas with Public Works Project Manager prior to starting the Work.
- B. On-site space for use as staging areas and storage of materials is limited and will be apportioned among various Contractors as their needs dictate with due regard for storage requirements of each Contractor. Each Contractor shall be responsible for safety of equipment and materials that are stored on site.

1.26 OCCUPANCY DURING CONSTRUCTION AND CONDUCT OF WORK

- A. Contractors are asked to not work at facility if they are ill with something contagious.
- B. Owner reserves right at any time to dismiss from premises any Contractor or construction personnel that do not uphold requirements of this Section.
- C. Owner shall not be held liable for any lost time, wages, or impacts to construction schedule by any Contractor or construction personnel dismissed for failure to uphold requirements of this Section.
- D. Work shall be done and temporary facilities furnished so as not to interfere with access to any occupied area and so as to cause least possible interference with normal operation of facility or any essential service thereof.
- E. Contractor shall, at all times, provide approved, safe walkways and facility entrances for use by Owner, employees and public.
- F. Contractor shall provide adequate protection for all parts of facility, its contents and occupants wherever the Work under this Contract is to be performed.
- G. Each Contractor shall arrange with Owner to make necessary alterations, do new work, make connections to all utilities, etc., and at such times as will not cause interruption of utility services to facility. Contractor doing this work shall protect, cap, cut off and / or replace and relocate existing pipes, electrical work and other active utilities encountered which may interfere with new construction work.
- H. New work in extension of existing work shall correspond in all respects with that to which it connects or similar existing work unless otherwise indicated or specified.
 - 1. Existing work shall be cut, altered, removed or replaced as necessary for performance of Contract obligations.
 - 2. Work remaining in place, damaged or defaced by reason of work done under this Contract shall be restored equal to its condition at time of Award of Contract.
 - 3. If removal of work exposes discolored or unfinished surfaces or work out of alignment, such surfaces shall be refinished or materials replaced as necessary to make continuous work uniform and harmonious.
- I. Contractor is not responsible for providing & maintaining temporary toilet facilities.

1.27 PROTECTION

- A. Contractor shall protect from damage / injury all trees, shrubs, hedges, plantings, grass, mechanical, electrical & plumbing equipment, walks and driveways and pay for any damage to same resulting from insufficient or improper protection.
- B. Contractor shall provide and maintain barricades & signage to prohibit public access to construction site.

Bid No. 320002 General Requirements rev. 01/2020 01 00 00 - 7

C. Contractor shall provide and maintain guard lights at all barricades, railings, obstructions in streets, roads or sidewalks and at all trenches adjacent to public walks or roads.

1.28 PROGRESS CLEANING

A. Maintain areas free of waste materials, debris, and rubbish. Maintain site in clean and orderly condition.

1.29 PRODUCTS

- A. Products: Means new material, machinery, components, equipment, fixtures, and systems forming the Work, but does not include machinery and equipment used for preparation, fabrication, conveying and erection of the Work. Products may also include existing materials or components specifically identified for reuse.
- B. Do not use materials and equipment removed from existing premises, except as specifically identified or allowed by Construction Documents.

1.30 TRANSPORTATION, HANDLING, STORAGE AND PROTECTION

A. Transport, handle, store and protect Products in accordance with manufacturer's instructions.

1.31 PRODUCT OPTIONS

- A. Where definite material is specified, it is not intentional to discriminate against "equal" product made by another manufacturer. Intention is to set definite standard of material quality. Should bidder choose to bid materials other than those specified, bidder shall submit said materials specifications to Public Works Project Manager for approval at least seven (7) business days prior to Bid Due Date.
- B. Products and materials that are not specified, but have been approved for use by Public Works Project Manager shall be identified in addenda to all bidding contractors.
- C. Requests for material or product substitutions submitted after Bid Due Date may be considered. Owner reserves right to approve or reject substitutions based on Specification requirements and intended use.

1.32 SUBSTITUTIONS

- A. Public Works Project Manager shall consider requests for Substitutions only within fifteen (15) calendar days after date of Public Works Construction Contract.
- B. Document each request with complete data substantiating compliance of proposed Substitution with Construction Documents.
- C. Submit three (3) copies of requests for Substitution for consideration. Limit each request to one (1) proposed Substitution.

D. Substitutions shall not change contract price established at Bid Due Date.

1.33 STARTING SYSTEMS

- A. Provide written notification prior to start-up of each equipment item or system.
- B. Ensure that each piece of equipment or system is ready for operation.
- C. Execute start-up under supervision of responsible persons in accordance with manufacturers' instructions.
- D. Submit written report that equipment or system has been properly installed and is functioning correctly.

1.34 DEMONSTRATION AND INSTRUCTIONS

- A. Demonstrate operation and maintenance of Products to Owner's personnel prior to date of final inspection.
- B. Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, maintenance, and shutdown of each item of equipment at agreed-upon times, at designated location.
- C. Owner may choose to photograph or videotape demonstration session; demonstration and demonstrator shall be to level of satisfaction of Owner.

1.35 CONTRACT CLOSEOUT PROCEDURES

- A. Submit written certification that Construction Documents have been reviewed, the Work has been inspected, and the Work is complete in accordance with Construction Documents and ready for Public Works Project Manager's inspection.
- B. Submit final Application for Payment identifying total adjusted Contract Sum / Price, previous payments, and amount remaining due.

1.36 FINAL CLEANING

- A. Execute final cleaning prior to final inspection.
- B. Clean interior and exterior surfaces exposed to view.
- C. Remove waste and surplus materials, rubbish, and construction facilities from site.

1.37 ADJUSTING

A. Adjust operating Products and equipment to ensure smooth and unhindered operation.

1.38 OPERATION AND MAINTENANCE MANUAL

A. Provide two (2) bound, hard-copy operation and maintenance manuals that include all systems, materials, products, equipment, mechanical and electrical equipment and systems supplied and installed in the Work. Provide electronic version of operation and maintenance manual also.

1.39 SPARE PARTS AND MAINTENANCE MATERIALS

- A. Provide Products, spare parts, maintenance and extra materials in quantities specified in individual Specification Sections.
- B. Deliver to the Work site and place in location as directed.

1.40 AS-BUILT AND RECORD DRAWINGS AND SPECIFICATIONS

- A. Contractor-produced Drawings and Specifications shall remain property of Contractor whether Project for which they are made is executed or not. Contractor shall furnish Public Works Project Manager with original marked up redlines of Construction Documents' drawings and specifications that shall include all Addendums, Change Orders, Construction Bulletins, on-site changes, field corrections, etc. These are project As-Built Drawings & Specifications.
- B. Architect / Engineer shall update original Construction Documents to include all Addendums & any other changes including those provided by Contractor in As-Built Drawings & Specifications. These updates are project Record Drawings & Specifications.
- C. Architect / Engineer shall furnish Public Works Project Manager with Record Drawings as detailed in Professional Services Agreement.

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

Not Used.

END OF SECTION

SECTION 01 74 19

CONSTRUCTION WASTE MANAGEMENT, DISPOSAL & RECYCLING

PART 1 GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Summary
 - 2. Waste Management Goals
 - 3. Construction and / or Demolition Waste Management
 - 4. Waste Management Plan
 - 5. Reuse
 - 6. Recycling
 - 7. Materials Sorting and Storage On Site
 - 8. Lists of Recycling Facilities Processors and Haulers
 - 9. Waste Management Plan Form

B. Related Sections:

1. Section 01 00 00 - General Requirements

1.2 WASTE MANAGEMENT GOALS

A. Dane County requires that as many waste materials as possible produced as result of this project be salvaged, reused or recycled in order to minimize impact of construction waste on landfills and to minimize expenditure of energy and cost in fabricating new materials. Additional information may be found in Dane County Green Building Policy, Resolution 299, 1999-2000.

1.3 CONSTRUCTION AND / OR DEMOLITION WASTE MANAGEMENT

- A. All construction and demolition waste suitable for recycling may go to Dane County Construction & Demolition Recycling Facility located at 7102 US Hwy 12, Madison, located across from Yahara Hills Golf Course. This facility can receive mixed loads of construction and demolition waste. For complete list of acceptable materials see www.countyofdane.com/pwht/recycle/CD Recycle.aspx.
- B. Dane County Landfill, also at 7102 US Hwy 12, Madison, must receive all other waste from this project. www.countyofdane.com/pwht/recycle/landfill.aspx.

1.4 WASTE MANAGEMENT PLAN

- A. Contractor shall develop Waste Management Plan (WMP) for this project. Dane County's Special Projects & Materials Manager may be contacted with questions. Outlined in RECYCLING section of this specification are examples of materials that can be recycled or reused as well as recommendations for waste sorting methods.
- B. Contractor shall complete WMP and include cost of recycling / reuse in Bid. WMP will be submitted to Public Works Project Manager within fifteen (15)

business days of Bid Due date, with Bid. Copy of blank WMP form is in this Section. Submittal shall include cover letter and WMP form with:

- 1. Information on:
 - a. Types of waste materials produced as result of work performed on site:
 - b. Estimated quantities of waste produced;
 - c. Identification of materials with potential to be recycled or reused;
 - d. How materials will be recycled or reused;
 - e. On-site storage and separation requirements (on site containers);
 - f. Transportation methods; and
 - g. Destinations.

1.5 REUSE

A. Contractors and subcontractors are encouraged to reuse as many waste materials as possible. Salvage should be investigated for materials not reusable on site.

1.6 RECYCLING

- A. These materials may be recycled at Dane County Construction & Demolition Recycling Facility:
 - 1. Wood.
 - 2. Wood Pallets.
 - 3. PVC Plastic (pipe, siding, etc.).
 - 4. Asphalt & Concrete.
 - 5. Bricks & Masonry.
 - 6. Vinyl Siding.
 - 7. Cardboard.
 - 8. Metal.
 - 9. Unpainted Gypsum Drywall.
 - 10. Shingles.
- B. These materials can be recycled elsewhere in Dane County area:
 - 1. Fluorescent Lamps.
 - 2. Foam Insulation & Packaging (extruded and expanded).
 - 3. Carpet Padding.
 - 4. Barrels & Drums.
- C. All materials must be recycled at WDNR permitted waste processing facilities that adhere to all State Statutes.

1.7 MATERIALS SORTING AND STORAGE ON SITE

- A. Contractor shall provide separate containers for recyclable materials. Number of containers will be dependent upon project and site conditions.
- B. Contractor shall provide on-site locations for subcontractors supplied recycling containers to help facilitate recycling.
- C. Mixed loads of recycled materials are allowed only per instructions at www.countyofdane.com/pwht/recycle/CD_Recycle.aspx.

1.8 LISTS OF RECYCLING FACILITIES PROCESSORS AND HAULERS

- A. Refer to www.countyofdane.com/pwht/recycle/CD_Recycle.aspx for information on Dane County Construction & Demolition Recycling Facility.
- B. Web site www.countyofdane.com/pwht/recycle/categories.aspx lists current information for Dane County Recycling Markets. Contractors can also contact Allison Rathsack at 608/266-4990, or local city, village, town recycling staff listed at site www.countyofdane.com/pwht/recycle/contacts.aspx. Statewide listings of recycling / reuse markets are available from UW Extension at https://www.uwgb.edu/shwec/.

PART 2 PRODUCTS	
-----------------	--

Not Used.

PART 3 EXECUTION

Not Used.

END OF SECTION

WASTE MANAGEMENT PLAN FORM

STYOFA	Contractor Name:	
	Address:	
427 (1839) ST	Phone No:	Recycling Coordinator

MATERIAL	ESTIMATED QUANTITY	DISPOSAL METHOD (CHECK ONE)		RECYCLING / REUSE COMPANY OR DISPOSAL SITE	
Salvaged &	cu. yds.	Recycled	Reused		
reused building materials	tons	Landfilled	Other	Name:	
		Recycled	Reused		
Wood	tons	Landfilled	Other	Name:	
		Recycled	Reused		
Wood Pallets	units	Landfilled	Other	Name:	
	cu. ft.	Recycled	Reused		
PVC Plastic	lbs.	Landfilled	Other	Name:	
Asphalt &		Recycled	Reused		
Concrete			Other	Name:	
Bricks &	cu. ft.	Recycled	Reused		
Masonry	lbs.		Other	Name:	
		Recycled	Reused		
Vinyl Siding	lbs.		Other	Name:	
		Recycled	Reused		
Cardboard			Other	Name:	
		Recycled	Reused		
Metals			Other	Name:	
Unpainted		Recycled	Reused		
Gypsum / Drywall			Other	Name:	
·		Recycled	Reused		
Shingles		Landfilled		Name:	
Fluorescent		Recycled	Reused		
Lamps	lbs.	Landfilled	Other	Name:	
	cu. ft.	Recycled	Reused		
Foam Insulation	lbs.	Landfilled	Other	Name:	
	cu. ft.	Recycled	Reused		
Carpet Padding	bts.	Landfilled	Other	Name:	
		Recycled	Reused		
Barrels & Drums	units	Landfilled	Other	Name:	
	cu. yds.	Recycled	Reused		
Glass	tons	Landfilled	Other	Name:	

Bid No. 320002 rev. 08/19

WASTE MANAGEMENT PLAN FORM

Other	 RecycledReuLandfilledOth	used her Name:
Other	 RecycledReuReu	used her Name:
Other	 RecycledReuLandfilledOth	
Other	 RecycledReuReu	
Other	 RecycledReuReu	used her Name:

Bid No. 320002 rev. 08/19

SECTION 26 05 00 - COMMON WORK RESULTS FOR ELECTRICAL

PART 1 GENERAL

1.1 PROJECT OVERVIEW

A. This project consists of construction of new photovoltaic systems for the Dane County Parks Operations building located in Madison, Wisconsin.

1.2 SCOPE

A. The work under this section includes basic electrical requirements, which are applicable to all Division 26 sections. This section includes information common to two or more technical specification sections or items that are of a general nature, not conveniently fitting into other technical sections.

1.3 RELATED WORK

- A. Applicable provisions of Division 1 govern work under this Section.
- B. Section 07 84 00 Fire Stopping

1.4 REFERENCE STANDARDS

A. Abbreviations of standards organizations referenced in this and other sections are as follows:

1. ANSI	American National Standards Institute
2. ASTM	American Society for Testing and Materials
3. EPA	Environmental Protection Agency
4. ETL	Electrical Testing Laboratories, Inc.
5. IEEE	Institute of Electrical and Electronics Engineers
6. IES	Illuminating Engineering Society
7. ISA	Instrument Society of America
8. NBS	National Bureau of Standards
9. NEC	National Electric Code
10. NEMA	National Electrical Manufacturers Association
11. NESC	National Electrical Safety Code
12. NFPA	National Fire Protection Association
13. UL	Underwriters Laboratories Inc.
14. DSPS	Wisconsin Department of Safety and Professional Services

1.5 REGULATORY REQUIREMENTS

- A. All work and materials are to conform in every detail to applicable rules and requirements of the Wisconsin State Electrical Code (SPS 316), the National Electrical Code (NFPA 70), other applicable National Fire Protection Association codes, the National Electrical Safety Code, and present manufacturing standards (including NEMA).
- B. All Division 26 work shall be done under the direction of a currently licensed State of Wisconsin Master Electrician.

1.6 QUALITY ASSURANCE

- A. Where equipment or accessories are used which differ in arrangement, configuration, dimensions, ratings, or engineering parameters from those indicated on the contract documents, the contractor is responsible for all costs involved in integrating the equipment or accessories into the system and the assigned space, and for obtaining the performance from the system into which these items are placed.
- B. Manufacturer references used herein are intended to establish a level of quality and performance requirements unless more explicit restrictions are stated to apply.
- C. All materials shall be listed by and shall bear the label of an approved electrical testing laboratory. If none of the approved electrical testing laboratories has published standards for a particular item, then other national independent testing standards, if available, applicable, and approved by owner, shall apply and such items shall bear those labels. Where one of the approved electrical testing laboratories has an applicable system listing and label, the entire system shall be so labeled.

1.8 PROTECTION OF FINISHED SURFACES

A. Furnish one can of touch-up paint for each different color factory finish furnished by the Contractor. Deliver touch-up paint with other "loose and detachable parts" as covered in the General Requirements.

1.9 APPROVED ELECTRICAL TESTING LABORATORIES

- A. The following laboratories are approved for providing electrical product safety testing and listing services as required in these specifications:
 - 1. Underwriters Laboratories Inc.
 - 2. Electrical Testing Laboratories, Inc.

1.10 SLEEVES AND OPENINGS

A. Refer to Division 1, General Requirements, Sleeves and Openings.

1.11 SEALING AND FIRE STOPPING

A. Sealing and fire stopping of sleeves/openings between conduits, cable trays, wireways, troughs, cablebus, busduct, etc. and the sleeve, structural or partition opening shall be the responsibility of the contractor whose work penetrates the opening. Provide all fire stopping of fire rated penetrations and sealing of smoke rated penetrations in compliance with section 07 84 00 Fire Stopping.

1.12 INTENT

19.0480

- A. The Contractor shall furnish and install all the necessary materials, apparatus, and devices to complete the electrical equipment and systems installation herein specified, except such parts as are specifically exempted herein.
- B. If an item is either called for in the specifications or shown on the plans, it shall be considered sufficient for the inclusion of said item in this contract. If a conflict exists within the Specifications or exists within the Drawings, the Contractor shall furnish the item, system, or workmanship, which is the highest quality, largest, or most closely fits the owner's intent. Refer to the General Conditions of the Contract for further clarification.

26 05 00 - 2

- C. It must be understood that the details and drawings are diagrammatic. The Contractor shall verify all dimensions at the site and be responsible for their accuracy.
- D. All sizes as given are minimum except as noted.
- E. Materials and labor shall be new (unless noted or stated otherwise), first class, and workmanlike, and shall be subject at all times to the owner's and/or A/E's inspections, tests and approval from the commencement until the acceptance of the completed work.
- F. Whenever a particular manufacturer's product is named, it is intended to establish a level of quality and performance requirements unless more explicit restrictions are stated to apply.

1.13 OMISSIONS

A. No later than ten (10) days before bid opening, the Contractor shall call the attention of the owner to any materials or apparatus the Contractor believes to be inadequate and to any necessary items of work omitted.

1.14 SUBMITTALS

- A. Submit for all equipment and systems as indicated in the respective specification sections, marking each submittal with that specification section number. Mark general catalog sheets and drawings to indicate specific items being submitted and proper identification of equipment by name and/or number, as indicated in the contract documents. Failure to do this may result in the submittal(s) being returned to the Contractor for correction and resubmission. Failing to follow these instructions does not relieve the Contractor from the requirement of meeting the project schedule.
- B. On request from the owner, the successful bidder shall furnish additional drawings, illustrations, catalog data, performance characteristics, etc.
- C. Submittals shall be grouped to include complete submittals of related systems, products, and accessories in a single submittal. Mark dimensions and values in units to match those specified. Include wiring diagrams of electrically powered equipment.
- D. The submittals must be approved before fabrication is authorized.
- E. Submit sufficient quantities of submittals to allow the following distribution:

1. Operating and Maintenance Manuals 2 copies

2. A/E 1 copy

1.15 PROJECT/SITE CONDITIONS

- A. Install Work in locations shown on drawings, unless prevented by project conditions.
- B. Prepare drawings showing proposed rearrangement of work to meet project conditions, including changes to work specified in other sections. Obtain permission of owner before proceeding.
- C. Tools, materials and equipment shall be confined to areas designated by the owner.

1.16 WORK SEQUENCE AND SCHEDULING

A. Install work in phases to accommodate owner's occupancy requirements. During the construction period coordinate electrical schedule and operations with owner's Construction Representative.

1.17 WORK BY OTHER TRADES

- A. Every attempt has been made to indicate in this trade's specifications and drawings all work required of this Contractor. However, there may be additional specific paragraphs in other trade specifications and addenda, and additional notes on drawings for other trades which pertain to this trade's work, and thus those additional requirements are hereby made a part of these specifications and drawings.
- B. Electrical details on drawings for equipment to be provided by others are based on preliminary design data only. This Contractor shall lay out the electrical work and shall be responsible for its correctness to match equipment actually provided by others.

1.18 SALVAGE MATERIALS

A. No materials removed from this project shall be reused. All materials removed shall become the property of and shall be disposed of by the Contractor.

1.19 CERTIFICATES AND INSPECTIONS

A. Obtain and pay for all required State installation inspections, in accordance with the Wisconsin Administrative Code. Deliver originals of these certificates to the owner's Project Representative.

1.20 OPERATION AND MAINTENANCE DATA

A. All operations and maintenance data shall comply with the submission and content requirements specified under section GENERAL REQUIREMENTS.

In addition to the general content specified under GENERAL REQUIREMENTS supply the following additional documentation:

1. Manufacturer's wiring diagrams for electrically powered equipment.

1.21 RECORD DRAWINGS

- A. The Contractor shall maintain at least one copy each of the specifications and drawings on the job site at all times.
- B. The owner will provide the Contractor with a suitable set of contract drawings on which daily records of changes and deviations from contract shall be recorded. Dimensions and elevations on the record drawings shall locate all buried or concealed piping, conduit, or similar items.
- C. The daily record of changes shall be the responsibility of Contractor's field superintendent. No arbitrary mark-ups will be permitted.
- D. At completion of the project, the Contractor shall submit the marked-up record drawings to the Architect/Engineer prior to final payment.

PART 2 PRODUCTS

2.1 ACCESS PANELS AND DOORS

A. Lay-in Ceilings:

1. Removable lay-in ceiling tiles in 2 x 2 foot or 2 x 4 foot configuration provided under other divisions are sufficient; no additional access provisions are required unless specifically indicated.

B. Concealed Spline Ceilings:

1. Removable sections of ceiling tile held in position with metal slats or tabs compatible with the ceiling system used will be provided under other divisions.

C. Metal Pan Ceilings:

1. Removable sections of ceiling tile held in position by pressure fit will be provided under other divisions.

D. Plaster Walls and Ceilings:

1. 16 gauge frame with not less than a 20 gauge hinged door panel, prime coated steel for general applications, stainless steel for use in toilets, showers and similar wet areas, concealed hinges, screwdriver operated cam latch for general application, key lock for use in public areas, UL listed for use in fire rated partitions if required by the application. Use the largest size access opening possible, consistent with the space and the equipment needing service; minimum size is 12" by 12".

2.2 **IDENTIFICATION**

A. See Electrical section 26 05 53 – Identification for Electrical Systems.

2.3 SEALING AND FIRE STOPPING

A. FIRE AND/OR SMOKE RATED PENETRATIONS:

1. Provide all fire stopping of fire rated penetrations and sealing of smoke rated penetrations in compliance with section 07 84 00 "Fire Stopping".

B. NON-RATED PENETRATIONS:

- 1. Conduit Penetrations Through Below Grade Walls:
 - In exterior wall openings below grade, use a modular mechanical type seal consisting of interlocking synthetic rubber links shaped to continuously fill the annular space between the uninsulated conduit and the cored opening or water-stop type wall sleeve.

2. Conduit and Cable Tray Penetrations:

a. At conduit and cable tray penetrations of non-rated interior partitions, floors and exterior walls above grade, use urethane caulk in annular space between conduit and sleeve, or the core drilled opening.

PART 3 EXECUTION

3.1 EXCAVATION AND BACKFILL

A. Perform all excavation and backfill work to accomplish indicated electrical systems installation in accordance with section 31 23 16.13 - Trenching. Blasting will not be allowed without written permission of the owner.

3.2 CONCRETE WORK

A. The Division 3 Contractor will perform all cast-in-place concrete unless noted otherwise elsewhere. Provide all layout drawings, anchor bolts, metal shapes, and/or templates required to be cast into concrete or used to form concrete for the support of electrical equipment.

3.3 CUTTING AND PATCHING

A. Refer to Division 1, General Requirements, Cutting and Patching.

3.4 BUILDING ACCESS

A. Arrange for the necessary openings in the building to allow for admittance of all apparatus. When the building access was not previously arranged and must be provided by this contractor, restore any opening to its original condition after the apparatus has been brought into the building.

3.5 EQUIPMENT ACCESS

A. Install all piping, conduit, ductwork, and accessories to permit access to equipment for maintenance. Coordinate the exact location of wall and ceiling access panels and doors with the General Contractor, making sure that access is available for all equipment and specialties. Where access is required in plaster or drywall walls or ceilings, furnish the access doors to the General Contractor and reimburse the General Contractor for installation of those access doors.

3.6 COORDINATION

- A. The Contractor shall cooperate with other trades and owner in locating work in a proper manner. Should it be necessary to raise or lower or move longitudinally any part of the electrical work to better fit the general installation, such work shall be done at no extra cost to the owner provided such decision is reached prior to actual installation. The Contractor shall check location of electrical outlets with respect to other installations before installing.
- B. The Contractor shall verify that all devices are compatible for the surfaces on which they will be used. This includes, but is not limited to light fixtures, panelboards, devices, etc. and recessed or semi-recessed heating units installed in/on architectural surfaces.
- C. Coordinate all work with other contractors prior to installation. Any installed work that is not coordinated and that interferes with other contractor's work shall be removed or relocated at the installing contractor's expense.
- D. Cooperate with the testing consultant in ensuring specification Section 26 05 04 compliance. Verify system completion to the testing consultant. Demonstrate the starting, interlocking and control features of each system so the testing contractor can perform their work.

19.0480 COMMON WORK RESULTS FOR ELECTRICAL

3.7 SLEEVES AND OPENINGS

- A. Conduit penetrations in existing concrete floors: Core drill openings.
- B. Where penetrating conduit weight is supported by floor, provide manufactured product or structural bearing collar designed to carry load.

3.8 SEALING AND FIRE STOPPING

A. FIRE AND/OR SMOKE RATED PENETRATIONS:

1. Provide all fire stopping of fire rated penetrations and sealing of smoke rated penetrations in compliance with section 07 84 00 Fire Stopping.

B. NON-RATED PENETRATIONS:

- 1. In exterior wall openings below grade, assemble rubber links of mechanical seal to the proper size for the conduit and tighten in place, in accordance with the manufacturer's instructions. Install so that the bolts used to tighten the seal are accessible from the interior of the building or vault.
- 2. At all interior walls and exterior walls, conduit penetrations are required to be sealed. Apply sealant to both sides of the penetration in such a manner that the annular space between the sleeve or cored opening and the conduit is completely blocked.

C. PENETRATIONS SUBJECT TO WATER INTRUSION:

- 1. For penetrations (both rated and non-rated) in floors subject to water intrusion or in rooms housing electrical equipment (but not within walls) provide one of the following:
 - a. Conduit penetration where steel pipe sleeve is used extend steel sleeve 2" above the floor.
 - b. Conduit penetration where cast in place fire stopping device/sleeve is used, extend device/sleeve 2" above the floor (provided it meets the device's UL listing).
 - c. Conduit penetration where there is no steel sleeve or cast in place fire stopping device/sleeve, provide 2"x 2" x 1/8" galvanized steel angles fastened to floor surrounding the penetration or group of penetrations to prevent water from getting to penetration. Provide urethane caulk between angles and floor and fasten angles to floor minimum 8"on center. Seal corners water tight with urethane caulk.
- 2. Floors subject to water intrusion or rooms housing electrical equipment include the following locations:
 - a. Food Service/Kitchen Areas
 - b. Restrooms
 - c. Locker/Shower Rooms
 - d. Janitor Rooms w/ Sinks

- e. Mechanical/Plumbing Equipment Rooms
- f. Maintenance/Industrial Shops
- g. Vehicle Storage and Parking Ramps
- h. Data/Telecommunications Rooms
- i. Electrical Equipment Rooms
- 3. Provide waterproof caulk sealant top coating on fire stopping system (or other approved means to protect the fire stopping system from water) in areas subject to wash down such as Food Service and Dish Washing Areas.

3.9 HOUSEKEEPING AND CLEAN UP

A. The Contractor shall clean up and remove from the premises, on a daily basis, all debris and rubbish resulting from its work and shall repair all damage to new and existing equipment resulting from its work. When job is complete, this Contractor shall remove all tools, excess material and equipment, etc., from the site.

3.10 TRAINING

A. Contractor to provide factory authorized representative and/or field personnel knowledgeable with the operations, maintenance and troubleshooting of the system and/or components defined within this section for a minimum period of 8 hours.

END OF SECTION

SECTION 26 05 04 - CLEANING, INSPECTION, AND TESTING OF ELECTRICAL EQUIPMENT

PART 1 GENERAL

1.1 SCOPE

A. The work under this section includes the required cleaning, repair, adjustment, calibration, maintenance and testing of electrical equipment, as specified herein. This applies only to new electrical and existing electrical equipment being furnished, modified, worked on or serviced by this contractor for this project.

1.2 RELATED WORK

A. Applicable provisions of Division 1 govern work under this Section.

PART 2 PRODUCTS

2.1 Not Used.

PART 3 EXECUTION

3.1 GENERAL INSPECTION AND CLEANING OF ALL ELECTRICAL EQUIPMENT

- A. Inspect for physical damage and abnormal mechanical and electrical conditions.
- B. Any item found to be out of tolerance, or in any other way defective as a result of the required inspection or testing, shall be reported to the owner. Procedure for repair and/or replacement will be outlined. After appropriate corrective action is completed the item shall be re-tested.
- C. Compare equipment nameplate information with the latest single line diagram and report any discrepancies.
- D. Verify proper auxiliary device operation and indicators.
- E. Check tightness of accessible bolted electrical joints. Use torque wrench method.
- F. Make a close examination of equipment and remove any shipping brackets, insulation, packing, etc. that may not have been removed during original installation.
- G. Make a close examination of equipment and remove any dirt or other forms of debris that may have collected in existing equipment or in new equipment during installation.

H. Clean All Equipment:

- 1. Vacuum inside of panelboards, switchboards, switchgear, transformer core and coils, bus ducts, MCC's, fire alarm panels, communication/data panels, security panels, etc.
- 2. Loosen attached particles and vacuum them away.
- 3. Wipe all insulators with a clean, dry, lint free rag.
- 4. Clean insulator grooves.
- 5. Re-vacuum inside surfaces as directed by the Inspector.

- I. Inspect equipment anchorage.
- J. Inspect equipment and bus alignment.
- K. Check all heater elements for operation and control.
- L. Lubricate nonelectrical equipment per manufacturer's recommendations.

3.2 GROUNDING SYSTEMS

A. Inspect the ground system for adequate termination at all devices.

3.3 DRY TYPE TRANSFORMERS

- A. Test and adjust the cooling fans, controls and alarm functions.
- B. Measure secondary voltage phase-to-phase and phase-to-ground after final energization and prior to loading.
- C. Verify and/or connect transformer "XO" to ground, load side of "WYE" systems.

3.4 LIGHTNING ARRESTERS/SURGE SUPPRESSION

- A. Inspect for physical damage such as chipped or fractured porcelain. Wipe clean.
- B. Perform a ground continuity test to grounding system.
- C. Verify the proper mounting and adequate clearance.
- D. Verify the voltage of the units with system one line diagram. Report any discrepancies.
- E. Verify the electronic surge protection device is connected properly and status lights are normal.

3.5 BATTERY SYSTEMS

- A. Inspect for physical damage and evidence of corrosion. Clean units.
- B. Measure system charging voltage and each individual cell voltage.
- C. Measure the electrolyte specific gravity and level.
- D. Verify and compare measured values with manufacturer's specifications.

3.6 MECHANICAL AND ELECTRICAL INTERLOCK SYSTEM

- A. Physically test each system to insure proper function, operation and sequencing.
- B. Closure attempt shall be made on locked open devices.
- C. Opening attempt shall be made on locked closed devices.
- D. Key exchange shall be made with devices operated in off normal positions.

3.7 SWITCHBOARDS (LOW VOLTAGE)

- A. Visual and Mechanical Inspection:
 - 1. Inspect for physical, electrical and mechanical conditions. Re-torque all bolted connections.
 - 2. Compare equipment nameplate information with latest single line diagram and report discrepancies.
 - 3. Inspect for proper alignment, anchorage and grounding
 - 4. All doors, panels and sections shall be inspected for paint, dents, scratches, and fit.
 - 5. Inspect cleanliness
- B. Clean switchboard enclosure using the following methods:
 - 1. Loosen attached particles and vacuum them away.
 - 2. Wipe all porcelain with a clean, dry, lint-free rag.
 - 3. Clean all insulator grooves.
 - 4. Vacuum inside of switchgear enclosure.
 - 5. Lubricate per manufacturer's recommendations.
- C. All active components shall be exercised and cleaned where possible.
- D. All indicating devices shall be inspected for proper operation.

3.8 PANELBOARDS

A. Torque all the connections per the manufacturers spec. Verify phase wires, color coding, separate neutral and mechanical bonding. Verify circuit breaker operation. Verify the directory.

3.9 MOTOR STARTERS AND MOTOR CONTROL CENTERS

A. Verify the control circuits. Confirm the fusing and the grounding of the control transformers. Torque all of the connections. Confirm the overload elements and the circuit breakers (fuse) for proper sizing. Verify all grounding. Operate and test each motor starter for proper operation.

3.10 CABLES

A. 600 Volt cable:

- 1. Visually inspect cables, lugs, connectors and all other components for physical damage and proper connections.
- 2. Check all cable connectors for tightness (with a torque wrench) and clearances. Torque test conductor terminations to manufacturer's recommendations.

3. Perform a 1000 Vdc megger test on all secondary cables from the substation transformers to the secondary switchboards and on all switchboard feeders.

3.11 LIGHT FIXTURES

A. Check the bonding and proper lamping. Verify that recessed fixtures are installed with hold down clips. Confirm operation of the fixture with the proper switch or sensor.

3.12 OCCUPANCY SENSORS

A. Confirm operation of the sensor per the manufacturers spec.

3.13 BATTERY PACK EMERGENCY LIGHTING

A. Verify the operation per the manufacturers spec and run all of the diagnostic steps. Confirm proper grounding and location.

3.14 UPS SYSTEM

A. Operate and test the system per the manufacturers spec. Confirm the batteries and liquid level along with the transfer scheme.

3.15 GENERATORS

- A. Run the generator through the standard tests as recommended by the manufacturer including the load bank test. Test the automatic start circuits and run the full diagnostic tests. Verify the fuel and the tank. Check for fuel and coolant leaks.
- B. Provide full load testing utilizing a portable test bank for four hours continuous, minimum. During the first two hours, step increase the load from 0% to 100% in at least six equal steps. At the end of two hours, continue running test at 100% load. Record the following in 20 minute intervals throughout the four hour test: kilowatts, amperes, voltage, coolant temperature, room temperature, generator frequency (Hz), oil pressure, fuel consumption.
- C. After the generator has cooled down from the four hour test, shut it down and then simulate a power failure including operation of the transfer switch, automatic cycle, and automatic shutdown and return to normal.

3.16 AUTOMATIC TRANSFER SWITCHES

- A. Coordinate with the generator and the subsequent tests.
- B. Check the automatic transfer switches and automatic start circuits for proper function.

END OF SECTION

SECTION 26 05 19 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLE

PART 1 GENERAL

1.1 SCOPE

A. The work under this section includes furnishing and installing required wiring and cabling systems including pulling, terminating and splicing.

1.2 RELATED WORK

- A. Applicable provisions of Division 1 govern work under this Section.
- B. Section 26 05 33 Raceway and Boxes for Electrical Systems.
- C. Section 26 05 53 Identification for Electrical Systems.

1.3 REFERENCES

A. Wisconsin Administrative Code SPS 316 - Electrical

1.4 SUBMITTALS

- A. Submit product data: Provide for each cable assembly type.
- B. Submit factory test reports: Indicate procedures and values obtained.
- C. Submit shop drawings for modular wiring system including layout of distribution devices, branch circuit conduit and cables, circuiting arrangement, and outlet devices.
- D. Submit manufacturer's installation instructions. Indicate application conditions and limitations of use stipulated by product testing agency specified under Regulatory Requirements.

1.5 PROJECT CONDITIONS

- A. Verify that field measurements are as shown on Drawings.
- B. Conductor sizes are based on copper.
- C. Wire and cable routing shown on Drawings is approximate unless dimensioned. Route wire and cable as required to meet project conditions.
- D. Where wire and cable routing is not shown, and destination only is indicated, determine exact routing and lengths required.

PART 2 PRODUCTS

2.1 GENERAL

- A. All wire shall be new, delivered to the site in unbroken cartons and shall be less than one year old out of manufacturer's stock.
- B. All conductors shall be copper.

- C. Insulation shall have a 600 volt rating.
- D. All conductors shall be stranded.
 - 1. Stranded conductors may only be terminated with UL OR ETL Listed type terminations or methods: e.g. stranded conductors may not be wrapped around a terminal screw but must be terminated with a crimp type device or must be terminated in an approved back wired method.

2.2 BUILDING WIRE

- A. Description: Single conductor insulated wire 90 degree C.
- B. Insulation: Type THHN/THWN-2, XHHW-2 insulation.

2.3 SERVICE ENTRANCE CONDUCTORS

- A. Description: Single conductor or multi-conductor insulated wire. 90 degree C sized at the 75 degree C table.
- B. Insulation:
 - Type USE-2, XHHW-2 insulation for service entrance conductors routed from exterior source to exterior termination location.
 - 2. Type XHHW-2 insulation for services entrance conductors routed from exterior source to interior termination location.

2.4 PHOTOVOLTAIC WIRE

- A. Description: Single conductor or multi-conductor insulated wire. 90 degree C.
- B. Insulation:
 - Type PV-WIRE for exterior connection and routing along collectors and to combiner boxes.

2.5 ABOVE GROUND WIRE FOR EXTERIOR WORK

- A. Description: Single conductor insulated wire, 90 degree C.
- B. Insulation: Type THHN/THWN-2, XHHW-2 insulation.

2.6 UNDERGROUND WIRE FOR EXTERIOR WORK

- A. Description: Stranded single or multiple conductor insulated wire, 90 degree C.
- B. Insulation: Type USE-2, XHHW-2, RHW-2 insulation.
- C. This wiring shall be used in all underground feeder and branch circuit applications, except THHN/THWN-2 is permitted when run in a concrete-encased ductbank.

2.8 WIRING CONNECTORS

A. Split Bolt Connectors: Not acceptable.

- B. Solderless Pressure Connectors: High copper alloy terminal. May be used only for cable termination to equipment terminals. Not approved for splicing.
- C. Twist Type Wire Connectors: Solderless twist type spring connector (wire-nut) with insulating cover for copper wire splices and taps. Use for conductor sizes 10 AWG and smaller. The manufacturer's wire fill capacity must be followed.
 - 1. All wire connectors used in underground or exterior pull boxes or hand holes shall be gel filled twist connectors or a connector designed for damp and wet locations. Gel filled twist type connectors can be used for copper conductor sizes 6 AWG and smaller for site lighting applications. The manufacturer's wire fill capacity must be followed.
- D. Mechanical Connectors: Bolted type tin-plated; high conductivity copper alloy; spacer between conductors; beveled cable entrances.
- E. Compression (crimp) Connectors: Long barrel; seamless, tin-plated electrolytic copper tubing; internally beveled barrel ends. Connector shall be clearly marked with the wire size and type and proper number and location of crimps. Connector must be installed with a crimper tool listed for use with the manufacturer and type of compression connector.
- F. Insulation Piercing Connectors: Molded insulated body, copper teeth, wrench tightened, UL 486B Listed. May be used only for connection of a tap conductor in run and tap type applications when main conductor is 8 AWG and larger.

PART 3 EXECUTION

3.1 GENERAL WIRING METHODS

- A. All wire and cable shall be installed in conduit.
- B. Do not use wire smaller than 12 AWG for power and lighting circuits.
- C. All phase, neutral and ground conductors shall be sized to prevent excessive voltage drop at rated circuit ampacity. As a minimum use 10 AWG conductors for 20 ampere, 120 volt branch circuit home runs longer than 100 feet (30 m), and for 20 ampere, 277 volt branch circuit home runs longer than 200 feet (61 m).
- D. Make conductor lengths for parallel conductors equal.
- E. Splice only in junction or outlet boxes.
- F. No conductor less than 10 AWG shall be installed in exterior underground conduit.
- G. Identify ALL low voltage wire, 600V and lower, per section 26 05 53.
- H. Neatly train and lace wiring inside boxes, equipment, and panelboards.

3.2 WIRING INSTALLATION IN RACEWAYS

A. Pull all conductors into a raceway at the same time. Use Listed water or silicone based wire pulling lubricant for pulling 4 AWG and larger wires and for other conditions when necessary. Wax based lubricants are not allowed. Pulling lubricant is not required for low friction type products where the cable manufacturer recommends that cables be pulled without lube.

- B. Install wire in raceway after interior of building has been physically protected from the weather and all mechanical work likely to injure conductors has been completed.
- C. Completely and thoroughly swab raceway system before installing conductors.
- D. Place all conductors of a given circuit (this includes phase wires, neutral (if any), and ground conductor) in the same raceway. If parallel phase and/or neutral wires are used, then place an equal number of phase and neutral conductors in same raceway or cable.
- E. VFD Installations: Install VFD input wiring and output wiring in separate conduit systems. Do not mix VFD input power and output power, or control wiring in a common raceway.
- F. In high ambient spaces, mechanical rooms, utility rooms and exterior exposed conduit, 90 degree C conductors shall be utilized.

3.3 WIRING CONNECTIONS AND TERMINATIONS

- A. Splice only in accessible junction boxes.
- B. Wire splices and taps shall be made firm, and adequate to carry the full current rating of the respective wire without soldering and without perceptible temperature rise.
- C. All splices shall be so made that they have an electrical resistance not in excess of two feet (600 mm) of the conductor.
- D. Use solderless twist type spring connectors (wire nuts) with insulating covers for wire splices and taps, 10 AWG and smaller.
- E. Use mechanical or compression connectors for wire splices and taps, 8 AWG and larger. Tape uninsulated conductors and connectors with electrical tape to 150 percent of the insulation value of the wiring.
- F. Thoroughly clean wires before installing lugs and connectors.
- G. At all splices and terminations, leave tails long enough to cut splice out and completely resplice.

3.4 FIELD QUALITY CONTROL

A. Field inspection and testing will be performed under provisions of Section 26 05 04.

3.5 WIRE COLOR

A. General:

- 1. Solid colored insulation is required for all THHN/THWN-2 wire. For other wire types use colored wire or identify wire with colored tape at all terminals, splices and boxes. Wire shall be colored as indicated below.
- 2. In existing facilities, use existing color scheme.
- 3. In new facilities, use black and red for single phase circuits at 120/240 volts, use Phase A black, Phase B red and Phase C blue for circuits at 120/208 volts single or three phase, and use Phase A brown, Phase B orange and Phase C yellow for circuits

- at 277/480 volts single or three phase. Note: This includes fixture whips except for Listed whips mounted by the fixture manufacturer on the fixture and Listed as a System.
- 4. Switch legs shall be the same color as their associated circuit, except for the second switch leg used for dual-level switching. The second switch leg shall be the next phase color, e.g. if the first switch leg is brown (277/480V phase A), the second switch leg shall be orange (277/480V phase B).
- 5. Traveler conductors run between 3 and 4 way switches shall be colored pink or purple.
- B. Neutral Conductors: White for 120/208V and 120/240V systems, Gray for 277/480V systems. Where there are two or more neutrals in one conduit, each shall be individually identified with a different stripe.
- C. Branch Circuit Conductors: Three or four wire home runs shall have each phase uniquely color coded.
- D. Feeder Circuit Conductors: Each phase shall be uniquely color coded.
- E. Ground Conductors: Green colored insulation for THHN/THWN-2 wire. For other wire types use green colored wire or identify wire with green tape at both ends and at all access points, such as panelboards, motor starters, disconnects and junction boxes. When isolated grounds are required, contractor shall provide green with yellow tracer.

3.6 BRANCH CIRCUITS

A. The use of single-phase, multi-wire branch circuits with a common neutral is not permitted. All single-phase branch circuits shall be furnished and installed with an individual accompanying neutral, sized the same as the phase conductors.

3.7 EMERGENCY CIRCUITS

- A. All Emergency, Legally Required Standby and Optional Standby system wiring shall be installed in separate raceways after their associated transfer switches. The wiring shall be separate from each other and from all normal system wiring.
- B. All emergency wiring serving fire pumps, requiring minimum 2 hour fire rating shall comply with NEC 695.6(B).
- C. All emergency wiring serving NEC 700 loads, requiring minimum 2 hour fire rating shall comply with NEC 700.10(D)(1).
- D. All generator control conductors installed between transfer equipment and the emergency generator serving Emergency, Legally Required Standby and Optional Standby systems shall be kept entirely independent of all other wiring. This shall require a dedicated conduit system between each transfer switch and the emergency generator. If a Fire Pump is served off the emergency generator, a separate conduit shall be provided between fire pump controller and generator.

END OF SECTION

SECTION 26 05 26 - GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.1 SCOPE

- A. The work under this section includes grounding electrodes and conductors, equipment grounding conductors, and bonding.
- B. All hardware, cables and related termination and support hardware shall be furnished, installed, wired, tested, labeled, and documented by the Contractor, as detailed in this and related sections.

1.2 RELATED WORK

A. Applicable provisions of Division 1 govern work under this Section.

1.3 REFERENCES

- A. Wisconsin Administrative Code SPS 316 Electrical
- B. ANSI/IEEE 142 (Latest edition) Recommended Practice for Grounding of Industrial and Commercial Power Systems
- C. UL 467 Electrical Grounding and Bonding Equipment
- D. IEEE 837 IEEE Standard for Qualifying Permanent Connections Used in Substation Grounding
- E. ANSI J-STD-607-B Commercial Building Grounding (Earthing) and Bonding Requirements for Telecommunications
- F. TIA/EIA-606-A Administration Standard for Commercial Telecommunications Infrastructure

1.4 PERFORMANCE REQUIREMENTS

- A. Grounding System Resistance:
 - 1. Equipment Rated 500 KVA and Less: 10 ohms maximum at building service entrance.
 - 2. Equipment Rated 500 to 1000 KVA: 5 ohms maximum at building service entrance.
 - 3. Equipment Rated more than 1000 KVA: 3 ohms building service entrance.
 - 4. Communications Busbars: 5 ohms maximum.
- B. Testing of grounding system resistance is to be witnessed by the electrical inspector and/or owner's Field Representative. Provide test report of grounding system resistance in final O&M manuals.

1.5 SUBMITTALS

- A. Product Data: Provide data for grounding electrodes and connections.
- B. Test Reports: Indicate overall resistance to ground [and resistance of each electrode].
- C. Manufacturer's Instructions: Include instructions for preparation, installation and examination of exothermic connectors.

1.6 PROJECT RECORD DOCUMENTS

A. Accurately record locations of all ground rods and other grounding electrodes.

1.7 REGULATORY REQUIREMENTS

- A. Conform to requirements of NFPA 70.
- B. Furnish products listed and classified by Underwriters Laboratories, Inc. or testing firm acceptable to authority having jurisdiction as suitable for purpose specified and shown.

PART 2 PRODUCTS

2.1 ROD ELECTRODE

- A. Material: Copper-clad steel.
- B. Diameter: 3/4 inch (19 mm) minimum.
- C. Length: 10 feet (3.5 m) minimum. Rod shall be driven at least 9' 6" deep.

2.2 CONCRETE-ENCASED GROUNDING ELECTRODE FOR POLE BASES

A. Fabricate per NFPA 70, Article 250.52 (A)(3) using 20 feet (6m) of bare copper wire not smaller than #4 AWG. If concrete foundation is less than 20 feet (6m) long, coil excess conductor within the base of the foundation. Bond grounding conductor to reinforcing steel in at least four locations and to anchor bolts.

2.3 MECHANICAL CONNECTORS

- A. The mechanical connector bodies shall be manufactured from high strength, high conductivity cast copper alloy material. Bolts, nuts, washers and lock washers shall be made of Silicon Bronze and supplied as a part of the connector body and shall be of the two bolt type.
- B. Split bolt connector types are NOT allowed. Exception: the use of split bolts is acceptable for grounding of wire-basket type cable tray.
- C. The connectors shall meet or exceed UL 467 and be clearly marked with the catalog number, conductor size and manufacturer.

2.4 COMPRESSION CONNECTORS

- A. The compression connectors shall be manufactured from pure wrought copper. The conductivity of this material shall be no less than 99% by IACS standards.
- B. Each connector shall be factory filled with an oxide-inhibiting compound.

- C. The connectors shall meet or exceed the performance requirements of IEEE 837, latest revision.
- D. The connectors shall be clearly marked with the manufacturer, catalog number, conductor size and the required compression tool settings.
- E. The installation of the connectors shall be made with a compression tool and die system, as recommended by the manufacturer of the connectors, and shall be irreversible.
- F. Pre-crimping of the ground rod is required for all irreversible compression connections to a ground rod.
- G. Terminal lug for communication system grounding shall be compression type and conform to the following:
 - 1. Material: Tin Plated Copper (aluminum not permitted).
 - 2. Wire Size: to match conductor
 - 3. Number of Stud Holes: 2
 - 4. Stud Hole Size: 3/8"
 - 5. Bolt Hole Spacing: per ANSI Joint Standard J-STD-607-A
 - 6. Tongue Angle: Straight

2.5 EXOTHERMIC CONNECTIONS

A. As manufactured by Cadweld or similar.

2.6 CONDUCTORS

- A. Material: Stranded copper (aluminum not permitted).
- B. Grounding Electrode Conductor: Size as shown on drawings, specifications or as required by NFPA 70, whichever is larger.
- C. Foundation Electrodes: As shown on drawings.
- D. Primary Manhole, Main Switchgear room and Vault Bonding: No. 4/0 minimum.
- E. Feeder and Branch Circuit Equipment Ground: Size as shown on drawings, specifications or as required by NFPA 70, whichever is larger. Differentiate between the normal ground and the isolated ground when both are used at the same facility.
- F. Branch Circuit Equipment Grounds shall be increased in size when routed with phase conductors increased in size due to voltage drop calculations.
- G. Conductors for Telecommunications shall be as follows:
 - 1. Telecommunications Bonding Conductor: No. 3/0 minimum or as shown on drawings.

- 2. Telecommunications Bonding Backbone: No. 3/0 minimum or as shown on drawings.
- 3. Telecommunications Grounding Equalizer (GE): No. 3/0 minimum or as shown on drawings.
- 4. Bonding Conductors shall be insulated with a Green Jacket or jacket marked with Green Tape or labeled per NEC Guidelines

2.7 BUS/BUSBAR

- A. Material: Copper (aluminum not permitted).
- B. Size:
 - 1. All Power systems: 1/4" X 2", length as needed (24" minimum).
 - 2. Telecommunications Main Ground Busbar (TMGB): 1/4" x 4" x 20" long (minimum).
 - 3. Telecommunications Grounding Busbar (TGB): 1/4" x 2" x 12" long (minimum).

C. Busbars:

- 1. Be pre-drilled to accommodate two-hole lugs.
- 2. 3/8" stud hole size; hole spacing per ANSI J-STD-607-A.
- 3. Incorporate insulators and stand-off brackets that electrically isolate busbar from mounting surface.
- D. Provide main ground busbar located adjacent to main electrical service equipment to terminate all ground conductors.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that final backfill and compaction has been completed before driving rod electrodes.

3.2 GENERAL

- A. Install Products in accordance with manufacturer's instructions.
- B. Mechanical connections shall be accessible for inspection and checking. No insulation shall be installed over mechanical ground connections.
- C. Ground connection surfaces shall be cleaned and all connections shall be made so that it is impossible to move them.
- D. Attach grounds permanently before permanent building service is energized.
- E. Terminate each grounding conductor on its own terminal lug. Sharing a single lug by multiple conductors is not allowed.

F. All grounding electrode conductors and individual grounding conductors shall be installed in PVC conduit, in exposed locations.

3.3 LESS THAN 600 VOLT ELECTRICAL SYSTEM GROUNDING

- A. Supplementary Grounding Electrode: Use driven ground rod on exterior of building.
- B. Provide code sized copper grounding electrode conductor from electrical room ground bus to secondary switchboard ground bus, each separately derived system neutral, secondary service system neutral to street side of water meter, building steel, ground rod, and any concrete encased electrodes. Provide bonding jumper around water meter.
- C. Equipment Grounding Conductor: Provide separate, insulated equipment grounding conductor within each raceway. Terminate each end on suitable lug, bus, enclosure or bushing. Provide a ground wire from each device to the respective enclosure.
- D. Bond together system neutrals, service equipment enclosures, exposed non-current carrying metal parts of electrical equipment, metal raceway systems, grounding conductor in raceways and cables, receptacle ground connectors, and plumbing systems.
- E. Install ground grid under access floors where indicated. Construct grid of #4 AWG bare copper wire installed on 72 inch centers both ways. Bond each access floor support pedestal to grid.
- F. Bond together each metallic raceway, pipe, duct and other metal object entering space under access floors. Bond to under floor ground grid. Use #4 AWG bare copper conductor.

3.4 COMMUNICATION SYSTEM GROUNDING

- A. Grounding and Bonding System for Communications shall be an isolated grounding system with a single ground point. That ground point is to be the common grounding electrode system at the building electrical service entrance (main ground bar located in electrical room).
- B. The system shall be compliant with ANSI J-STD-607-B with the exception that the ground cable shall not be bonded to building steel except at the electrical service entrance.
- C. Provide Grounding Busbar for Telecommunications at each Telecommunications Room, the Main Equipment Room and at the electrical service entrance per project drawings. Coordinate Busbar location(s) and conductor routing per drawings with Division 27 contractor.
- D. Provide Telecommunications Bonding Conductor from Telecommunications Main Grounding Busbar (TMGB) at the Communications Entrance Facility to building common grounding electrode system. Attach grounding conductor to building steel as allowed only at the main electrical service entrance.
- E. Provide Telecommunications Bonding Backbone (TBB) conductor from the TMGB to Telecommunications Grounding Busbar (TGB) at each Telecommunication Room, Telecommunications Equipment Room and Telecommunications Enclosure.
- F. TBB shall be continuous and not connected through Telecommunications Grounding Busbars (TGBs).
- G. Bond TGBs to TBB via tap off of TBB. Gauge of conductor to be same at TBB.

- H. Leave 10 feet slack in conductor from TBB to TGB at TGB location(s).
- I. Do not bond TBB or TGB to building steel at TGB location(s).
- J. Provide Grounding Equalizer(s) (GE) per project drawings. Connect GE conductor directly to TGBs being interconnected.

3.5 FIELD QUALITY CONTROL

- A. Inspect grounding and bonding system conductors and connections for tightness and proper installation.
- B. Testing of grounding system resistance is to be witnessed by the DSF electrical inspector or Field Representative. Provide test report of grounding system resistance in final O&M manuals.

3.6 IDENTIFICATION AND LABELING

- A. Label Grounds at point of termination.
- B. Label the connections from the Telecommunications Bonding Backbone (TBB) conductor to the Telecommunications Main Grounding Busbar (TMGB) and the Telecommunications Grounding Busbar TGB(s). The label shall be plastic and include the following:

IF THIS CONNECTOR OR CABLE IS LOOSE OR MUST BE REMOVED, PLEASE CALL THE BUILDING TELECOMMUNICATIONS MANAGER.

END OF SECTION

SECTION 26 05 29 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.1 SCOPE

A. The work under this sections includes conduit and equipment supports, straps, clamps, steel channel, etc., and fastening hardware for supporting electrical work.

1.2 RELATED WORK

- A. Applicable provisions of Division 1 govern work under this Section.
- B. Section 26 05 53 Identification for Electrical Systems

1.3 SUBMITTALS

A. Product Data: Provide data for support channel.

1.4 QUALITY ASSURANCE

A. Support systems shall be adequate for weight of equipment and conduit, including wiring, which they carry.

PART 2 PRODUCTS

2.1 MATERIAL

- A. Support Channel: Steel, Galvanized, Enameled or other corrosion resistant.
- B. Hardware: Corrosion resistant.
- C. Minimum sized threaded rod for supports shall be 3/8" for trapezes and single conduits 1-1/4" and larger, and 1/4" for single conduits 1" and smaller.
- D. Conduit clamps, straps, supports, etc., shall be steel or malleable iron. One-hole straps shall be heavy duty type. All straps shall have steel or malleable backing plates when rigid steel conduit is installed on the interior or exterior surface of any exterior building wall.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Fasten hanger rods, conduit clamps, outlet, junction and pull boxes to building structure using pre-cast insert system, preset inserts, beam clamps, expansion anchors, or spring steel clips (interior metal stud walls only).
- B. Use toggle bolts or hollow wall fasteners in hollow masonry, plaster, or gypsum board partitions and walls; expansion anchors or preset inserts in solid masonry walls; self-drilling anchors or expansion anchors on concrete surfaces; sheet metal screws in sheet metal studs and wood screws in wood construction. If nail-in anchors are used, they must be removable type anchors.

- C. Powder-actuated fasteners are not permitted. Compressed-air power-actuated fasteners may ONLY be used for the installation of separate ceiling wires required for support of conduits and aircraft cable hung light fixtures.
- D. File and de-bur cut ends of support channel and spray paint with cold galvanized paint to prevent rusting.
- E. Do not fasten supports to piping, ductwork, mechanical equipment, cable tray or conduit. Do not fasten to suspended ceiling grid system.
- F. Support wires that are installed in addition to the ceiling grid support wires to provide secure support for raceways, cables assemblies, boxes, cabinets, and fittings shall be secured at both ends (e.g. the ceiling structure at the top and the ceiling grid at the bottom) per NEC 300.11(A).
- G. Support wires shall be identified per specification section 26 05 53.
- H. Do not drill structural steel members unless approved by A/E.
- I. Fabricate supports from galvanized structural steel or steel channel, rigidly welded or bolted to present a neat appearance. Use hexagon head bolts with spring lock washers under all nuts.
- J. In wet locations, mechanical rooms, and electrical rooms, install free-standing electrical equipment on 3.5-inch (89 mm) concrete pads.
- K. Install surface-mounted cabinets and panelboards with a minimum of four anchors. At all cabinet and panelboard locations on concrete or concrete block walls, and at ALL locations below grade, provide steel channel supports to stand cabinet one inch (25 mm) off wall (7/8" Uni-strut or 3/4" painted fire-retardant plywood is acceptable). In above-grade equipment rooms that have drywall walls, the cabinets and panelboards may be mounted to the drywall if backing is provided in the stud walls behind the equipment.
- L. Bridge studs top and bottom with channels to support flush-mounted cabinets and panelboards in stud walls.
- M. Furnish and install all supports as required to fasten all electrical components required for the project, including free standing supports required for those items remotely mounted from the building structure, catwalks, walkways etc.

END OF SECTION

SECTION 26 05 33 - RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.1 SCOPE

A. This section describes the products and execution requirements relating to furnishing and installing raceways and boxes and related systems as part of a raceway system for electrical, communications, and other low-voltage systems for the project.

1.2 RELATED WORK

- A. Applicable provisions of Division 1 govern work under this section.
 - 1. Section 26 05 26 Grounding and Bonding for Electrical Systems
 - 2. Section 26 05 29 Hangers and Supports for Electrical Systems.
 - 3. Section 26 27 02 Equipment Wiring Systems.
 - 4. Section 26 27 26 Wiring Devices.
 - 5. Section 27 10 00 Technology Cabling System

1.3 SUBMITTALS

- A. Surface Raceway System submit product data and catalog sheets for all components.
- B. Boxes provide product data showing configurations, finishes, dimensions, and manufacturer's instructions.
- C. Conduits in Concrete Slabs Above Grade provide proposed conduit routing and sizing to Structural Engineer prior to approval of installation to verify structural integrity and fire rating of concrete slab.

PART 2 PRODUCTS

2.1 GENERAL

- A. All steel fittings and conduit bodies shall be galvanized.
- B. No cast metal or split-gland type fittings permitted.
- C. Mogul-type condulets larger than 2 inch (50 mm) not permitted except as approved or detailed.
- D. All condulet covers must be fastened to the condulet body with screws and be of the same manufacture.
- E. C-condulets shall not be used in lieu of pull boxes.

F. All boxes shall be of sufficient size to provide free space for all conductors enclosed in the box and shall comply with NEC requirements.

2.2 RIGID METAL CONDUIT (RMC) AND FITTINGS

- A. Conduit: Heavy wall threaded, galvanized steel, schedule 40.
- B. Fittings and Conduit Bodies: Use all steel threaded fittings and conduit bodies.
- C. Expansion Fittings/Expansion Joints: Expansion Fittings shall be Internal Grounding type and shall not rely on external bonding jumpers to maintain grounding continuity between raceway components.

2.3 PVC COATED RIGID METAL CONDUIT

- A. PVC Externally Coated Conduit: Rigid heavy wall, schedule 40, steel conduit with external 40 mil (0.1 mm) PVC coating. Conduit must be hot dipped galvanized inside and out including threads. The PVC coating bond to the galvanized steel conduit shall be stronger than the tensile strength of the coating itself.
- B. Fittings and Conduit Bodies: Threaded type, material to match conduit. PVC coated fittings and couplings shall have specially formed sleeves to tightly seal to conduit PVC coating. The sleeves shall extend beyond the fitting or coupling a distance equal to the pipe outside steel diameter or two inches (50 mm) whichever is greater.

2.4 INTERMEDIATE METAL CONDUIT (IMC) AND FITTINGS

- A. Conduit: Galvanized steel, threaded.
- B. Fittings and Conduit Bodies: Use all steel threaded fittings and conduit bodies.
- C. Expansion Fittings/Expansion Joints: Expansion Fittings shall be Internal Grounding type and shall not rely on external bonding jumpers to maintain grounding continuity between raceway components.

2.5 ELECTRICAL METALLIC TUBING (EMT) AND FITTINGS

- A. Conduit: Steel, galvanized tubing.
- B. Fittings: All steel, set screw type. No push-on or indenter types permitted.
- C. Conduit Bodies: All steel threaded conduit bodies.

2.6 FLEXIBLE METAL CONDUIT (FMC) AND FITTINGS

- A. Conduit: steel, galvanized, spiral strip.
- B. Fittings and Conduit Bodies: All steel, galvanized, or malleable iron (except as allowed in specification 26 51 13).

2.7 LIQUIDTIGHT FLEXIBLE METAL CONDUIT (LFMC) AND FITTINGS

- A. Conduit: flexible, steel, galvanized, spiral strip with an outer Liquidtight, nonmetallic, sunlight-resistant jacket.
- B. Fittings and Conduit Bodies: ANSI/NEMA FB 1, compression type. There shall be a metallic cover/insert on the end of the conduit inside the connector housing to seal the cut conduit end.

2.8 RIGID POLYVINYL CHLORIDE CONDUIT (PVC) AND FITTINGS

- A. Conduit: Rigid non-metallic conduit, Schedule 40 PVC minimum, Listed, sunlight resistant, rated for 900 C conductors. Schedule 80 for locations exposed to physical damage or as required.
- B. Fittings and Conduit Bodies: NEMA TC 2, Listed.

2.9 FIBERGLASS RESIN CONDUIT (RTRC) AND FITTINGS

- A. Conduit: Reinforced Thermosetting Resin Conduit RTRC, Type AG (Above Ground) and XW (Exposed), and UL 2515 AG (Above Ground) or UL 2420 BG (Below Ground) listed.
- B. Fittings, Factory Elbows and Conduit Bodies: Match Conduit.

2.10 HIGH DENSITY POLYETHYLENE CONDUIT (HDPE) AND FITTINGS

- A. Conduit: Continuous length smooth-wall HDPE conduit for electrical applications produced to ASTM F2160. Conduit shall be listed by a Nationally Recognized Testing Laboratory to UL Standard 651-A for smooth-wall duct to be used as electrical conduit for the installation of Listed electrical cables underground.
- B. The recommended HDPE color is black or black with red stripes. Red identifies the conduit as electrical and black provides UV protection for storage and at points where the conduit may exit the ground.
- C. Fittings: Threaded Mechanical Fittings: Aluminum reverse-threaded conduit couplers designed for use with HDPE conduit. Compression Fittings and Socket Couplings designed for use with HDPE conduit may also be used.

2.11 CONDUIT SUPPORTS

A. See section 26 05 29.

2.14 CONDUIT WATER SEALANT

A. Description: Conduit sealant used to prevent water from entering buildings via conduits.

- B. Sealant shall seal conduits against water and gas intrusion, such as Polywater® FSTTM-250 Foam Duct Sealant, Raychem RDSS Rayflate Duct Sealing System, or approved alternate. Sealant shall be re-enterable, shall be compatible with the conduit and conductor types being used, and shall comply with NEC 225.27, 230.8, and 300.5(G).
- C. Manufacturer names and catalog numbers are used to develop quality and performance requirements only. Products manufactured by others may be acceptable provided they meet or exceed the specifications.

2.15 PULL AND JUNCTION BOXES

- A. Interior Sheet Metal Boxes: code gauge galvanized steel, screw covers, flanged and spot welded joints and corners.
- B. Interior Sheet Metal Boxes larger than 12 inches (300 mm) in any dimension shall have a hinged cover or a chain installed between box and cover.
- C. Exterior Boxes and Wet Location Installations: Type 4 and Type 6, flat-flanged, surface-mounted junction box, UL listed as rain-tight. Galvanized cast iron, Aluminum, box and cover with ground flange, neoprene gasket, and stainless steel cover screws.
- D. Box extensions and adjacent boxes within 48 inches of each other are not allowed for the purpose of creating more wire capacity.
- E. Junction boxes 6 inch-by-6 inch or larger size shall be without stamped knock-outs.
- F. Wireways shall not be used in lieu of junction boxes.

PART 3 EXECUTION

3.1 CONDUIT SIZING, ARRANGEMENT, AND SUPPORT

- A. EMT is permitted to be used in sizes 4 inch (100 mm) and smaller for power and low-voltage systems. See CONDUIT INSTALLATION SCHEDULE below for other limitations for EMT and other types of conduit.
- B. Size power conductor raceways for conductor type installed. Conduit size shall be 1/2 inch (16 mm) minimum except all homerun conduits shall be 3/4 inch (21 mm), or as specified elsewhere. Caution: Per the NEC, the allowable conductor ampacity is reduced when more than three current-carrying conductors are installed in a raceway. Contractor must take the NEC ampacity adjustment factors into account when sizing the raceway and wiring system.
- C. Size communications and other low-voltage systems raceways as follows:
 - 1. Communications, including Outlet Box: 1 1/4 inch minimum. Conduit used for single device locations (e.g. Wireless Access Point, Video Surveillance Camera, and Wall mounted telephone) may be 3/4 inch minimum.

- 2. Control, security, signal, video, and other low-voltage applications: 3/4 inch minimum.
- 3. Fire Alarm: 1/2 inch minimum.
- 4. Floor Box and Poke-Through Assemblies:
 - a. Power: 3/4 inch minimum or as indicated on drawings.
 - b. Low-voltage: 1 inch minimum or as indicated on drawings.
- D. Provide one raceway from each communications outlet box to above accessible ceiling.
- E. Arrange conduit to maintain 6'-8" clear headroom and present a neat appearance.
- F. Route exposed conduit and conduit above accessible ceilings parallel and perpendicular to walls and adjacent piping.
- G. Maintain minimum 6 inch (150 mm) clearance between conduit and piping. Maintain 12 inch (300 mm) clearance between conduit and heat sources such as flues, steam pipes, and heating appliances.
- H. Arrange conduit supports to prevent distortion of alignment by wire pulling operations. Fasten conduit using galvanized pipe straps, conduit racks (lay-in adjustable hangers), clevis hangers, or bolted split stamped galvanized hangers.
- I. Group conduit in parallel runs where practical and use conduit rack (lay-in adjustable hangers) constructed of steel channel with conduit straps or clamps. Provide space for 25 percent additional conduit.
- J. Do not fasten conduit with wire or perforated pipe straps. Before conductors are pulled, remove all wire used for temporary conduit support during construction.
- K. Support and fasten metal conduit at a maximum of 8 feet (2.4 m) on center.
- L. Supports shall be independent of the installations of other trades, e.g. ceiling support wires, HVAC pipes, other conduits, etc., unless so approved or detailed.
- M. Conceal all conduits except where noted on the drawings or approved by the Architect/Engineer. Contractor shall verify with Architect/Engineer all surface conduit installations except in mechanical rooms.
- N. Changes in direction shall be made with symmetrical bends, cast steel boxes, stamped metal boxes or cast steel conduit bodies.
- O. For indoor conduits, no continuous conduit run shall exceed 100 feet (30 meters) without a junction box.

P. All conduits installed in exposed areas shall be installed with a box offset before entering box.

3.2 CONDUIT INSTALLATION

- A. Cut conduit square; de-burr cut ends.
- B. Conduit shall not be fastened to the corrugated metal roof deck.
- C. Bring conduit to the shoulder of fittings and couplings and fasten securely.
- D. Use conduit hubs for fastening conduit to cast boxes. Use sealing locknuts or conduit hubs for fastening conduit to sheet metal boxes in damp or wet locations.
- E. Terminate all conduit (except for terminations into conduit bodies) using conduit hubs, or connectors with one locknut, or utilize double locknuts (one each side of box wall).
- F. Provide bushings for the ends of all conduit not terminated in box walls. Refer to Section 26 05 26 Grounding and Bonding for Electrical Systems for grounding bushing requirements.
- G. Provide insulated bushings where raceways contain 4 AWG or larger conductors.
- H. Install no more than the equivalent of:
 - 1. Three 90 degree bends between boxes for electrical systems.
 - 2. Two 90 degree bends between boxes for communications and other low voltage systems.
 - 3. No single bend may exceed 90 degrees.
- I. Use hydraulic one-shot conduit bender or factory elbows for bends in conduit larger than 2 inch (50 mm) size unless sweep elbows are required.
- J. Bend conduit according to manufacturer's recommendations. Torches or open flame shall not be used to aid in bending of PVC conduit.
- K. Use suitable conduit caps or other approved seals to protect installed conduit against entrance of dirt and moisture.
- L. Provide 1/8 inch (3 mm) nylon pull string in empty conduit, except sleeves and nipples.
- M. Install expansion-deflection joints where conduit crosses building expansion joints. Note: expansion-deflection joints are not required where conduit crosses building control joints if the control joint does not act as an expansion joint.

- N. Install expansion joints where direct-buried conduit is subject to Earth Movement by settlement or frost per NEC 300.5(J), especially where conduit exits the ground exposed and enters a box, cabinet, or enclosure attached to a building or structure.
- O. Install expansion fitting in exterior PVC conduit runs per NEC table 352.44 utilizing a minimum temperature change of 120 degree F.
- P. Avoid moisture traps where possible. Where moisture traps are unavoidable, provide junction boxes with drain fittings at conduit low points.
- Q. Where conduit passes between areas of differing temperatures such as into or out of cool rooms, freezers, unheated and heated spaces, buildings, etc., provide condulet or box with duct seal or other means to prevent the passage of moisture and water vapor through the conduit.
- R. Route conduit through roof openings for piping and ductwork where possible.
- S. Where communication cabling is to be installed in conduit to the wiring hub (e.g. Telecom Room), multiple conduits may be consolidated into fewer, larger conduits. Capacity of shared conduits shall equal the capacity of the individual conduits unless otherwise noted.
- T. Use NRTL listed metallic grounding clamps when terminating conduit to cable tray.
- U. Ground and bond conduit under provisions of Section 26 05 26.
- V. Conduit is not permitted in any slab topping of two inches (50 mm) or less.
- W. Conduits in Concrete Slab Above Grade: Provide proposed conduit routing and sizing to Structural Engineer for approval prior to installation to verify structural integrity and fire rating of concrete slab.
- X. Maximum Size Conduit in Concrete Slabs Above Grade: 1 inch (25 mm). Do not route conduits to cross each other in slabs above grade. Minimum conduit spacing shall be 6 inches on center.
- Y. PVC conduit in concrete pole bases shall transition to galvanized rigid metal conduit 12 inches before it enters a concrete pole base. Inside the pole base, the elbow shall be galvanized rigid metal conduit. From the elbow, the conduit shall transition back to PVC as it continues up and out the top of the concrete pole base.
- Z. PVC conduit shall transition to galvanized rigid metal conduit before it enters a foundation wall or up through a concrete floor.
- AA. Identify conduit under provisions of Section 26 05 53.
- BB. All conduit installed underground (exterior to building) shall be buried a minimum of 24 inches below finished grade, whether or not the conduit is concrete encased. Install warning tape 12" below finish grade over all buried conduits. Underground warning tape shall be detectable, 2" wide minimum, 5 mil thickness, containing a

foil core. Tape color shall be red and labeled with the words "CAUTION-BURIED ELECTRIC LINE BELOW" as manufactured by Presco or similar.

- CC. Conduits penetrating underground foundation walls: Individual conduits or each conduit as part of a ductbank penetrating underground foundation walls (excluding manholes) shall be sealed against water intrusion into the building.
- DD. Clean PVC conduit with solvent, and dry before application of glue. The temperature rating of glue/cement shall match weather conditions. Apply full even coat of cement/glue to entire area that will be inserted into fitting. The entire installation shall meet manufacturer's recommendations.

3.3 CONDUIT INSTALLATION SCHEDULE

- A. Conduit other than that specified below for specific applications shall not be used.
 - Horizontal Directional Drilling (Directional Boring) Installations: HDPE conduit.
 - Underground Installations That Penetrate Foundation Walls: Rigid metal conduit within five feet (1.5 m) of the foundation wall. Conduit may transition to Fiberglass Resin Conduit (BG) or PVC conduit five feet (1.5 m) from the foundation walls.
 - Underground Installations That Do Not Penetrate Foundation Walls: Rigid metal conduit, Fiberglass Resin Conduit (BG), or PVC conduit.
 - Underground Installations Emerging from Grade: Buried conduit emerging from grade shall be Rigid metal conduit extending from the minimum cover distance of 24 inches below grade to the conduit termination point above grade.
 - Underground Installations Under Concrete Slab: Rigid metal conduit or Schedule 40 PVC conduit.
 - Underground Installations Emerging through Concrete Slab: Rigid metal conduit.
 - Concealed in Poured Concrete Walls: Rigid Metal Conduit, PVC conduit, or Electrical Nonmetallic Tubing (ENT).
 - Concealed in Concrete Block Walls: Electrical metallic tubing, PVC conduit. Electrical Nonmetallic Tubing (ENT).
 - Within Concrete Slab: Rigid Metal conduit or PVC conduit.
 - Emerging from Within Concrete Slab: Rigid metal conduit.
 - Exposed Outdoor Locations: Rigid metal conduit, IMC.
 - Wet Interior Locations: Exposed: Rigid metal conduit, Schedule 80 PVC conduit, PVC coated rigid metal conduit, Fiberglass Resin Conduit (XW).
 - Concealed Dry Interior Locations: Rigid metal conduit, Intermediate metal conduit, Electrical metallic tubing, and PVC conduit (Ground conductor).
 - Interior Building Grounding Electrode Conductor: Schedule 80 PVC.

- Exposed Dry Interior Locations: Rigid metal conduit, Intermediate metal conduit, Electrical metallic tubing.
- Motor and equipment connections: Liquidtight flexible metal conduit (LFMC) (all locations). Minimum length shall be one foot (300 mm); maximum length shall be three feet (900 mm). Conduit must be installed perpendicular to direction of equipment vibration to allow conduit to freely flex.
- Light fixtures: Refer to specification section 26 51 13.

3.4 PVC COATED RIGID METAL CONDUIT INSTALLATION

A. Installers of PVC Coated Rigid Metal Conduit shall be factory trained and certified in the proper installation methods for this type of conduit. Proof of such certification shall be kept on the project site at all times and shall be produced upon request.

3.5 HIGH DENSITY POLYETHYLENE CONDUIT (HDPE) INSTALLATION

- A. HDPE conduit may only be used in horizontal directional drilling applications. Installation must be in accordance with NFPA 70National Electrical Code and be direct buried or encased in concrete.
- B. Approved joining methods for HDPE include Threaded Mechanical Fittings, Compression Fittings, and/or Heat Fusion. Heat Fusion joints shall be made using "hot irons" designed specifically for joining HDPE conduit. Any joining method employed shall be manufacturer approved. Glue and/or solvents are NOT approved.

3.6 SURFACE METAL RACEWAY INSTALLATION

- A. Use flat-head screws to fasten channel to surfaces every twenty-four (24) inches. Mount plumb and level.
- B. Use suitable insulating bushings and inserts at connections to outlets and corner fittings.
- C. Maintain grounding continuity between raceway components to provide a continuous grounding path under provisions of Section 26 05 26.
- D. Fastener Option: Use clips and straps suitable for the purpose.

3.7 NONMETALLIC SURFACE RACEWAY INSTALLATION

- A. Use flat headed screws with appropriate anchors to fasten channel to surfaces secured every twenty-four (24) inches. Mount plumb and level. All surface mounted devices shall be fastened to the wall utilizing flat head screws along with appropriate anchors. No device shall be adhered to the wall surface using two-faced tape or any means other than as described above.
- B. Use suitable insulating bushings and inserts at connections to outlets and corner fittings.

- C. In areas where the walls cannot be fished, the station cable serving these outlets shall be covered with raceways. No exposed wire shall be permitted within offices, laboratories, and conference rooms or like facilities.
- D. Non-metallic raceway shall have a screw applied base. Both the base and cover shall be manufactured of rigid PVC materials.
- E. The raceway shall originate from a surface mounted box mounted adjacent to and at the same height as existing electrical boxes in the room, be attached to the wall and terminate above the ceiling.
- F. All fittings including, but not limited to, extension boxes, elbows, tees, fixture bodies shall match the color of the raceway.
- G. The raceway and all systems devices shall be UL listed and exhibit nonflammable self-extinguishing characteristics, tested to specifications of UL94V-0.
- H. The communications and other low voltage systems raceway and devices shall adhere to the EIA/TIA Category 6 bend radius standard.

3.8 COORDINATION OF BOX LOCATIONS

- A. Provide electrical boxes as shown on Drawings, and as required for splices, taps, wire pulling, equipment connections, and code compliance.
- B. Electrical box locations shown on Contract Drawings are approximate unless dimensioned. Verify location of floor boxes and outlets in offices and work areas prior to rough-in.
- C. No outlet, junction, or pull boxes shall be located where it will be obstructed by other equipment, piping, lockers, benches, counters, etc.
- D. Conduit and boxes shall not be fastened to the metal roof deck. If conduit and boxes are required to be located and installed on roof decks, the conduit and boxes are required to be spaced minimum 1-5/8 inch off the lowest part of the metal roof decking material, per NEC 300.4 (E).
- E. It shall be the Contractor's responsibility to study drawings pertaining to other trades, to discuss location of outlets with workmen installing other piping and equipment and to fit all electrical outlets to job conditions.
- F. In case of any question or argument over the location of an outlet, the Contractor shall refer the matter to the Architect/Engineer and install outlet as instructed by the Architect/Engineer.
- G. The proper location of each outlet is considered a part of this contract and no additional compensation will be paid to the Contractor for moving outlets which were improperly located.

- H. Locate and install boxes to allow access to them. Where installation is inaccessible, coordinate locations and provide 18 inch (450 mm) by 24 inch (600 mm) access doors. Boxes must be installed within 12" from edge of the access door.
- I. Locate and install to maintain headroom and to present a neat appearance.
- J. Install boxes to preserve fire resistance rating of partitions and other elements, using approved materials and methods.

3.9 PULL AND JUNCTION BOX INSTALLATION

- A. Pull boxes and junction boxes shall be minimum 4 inches square (100 mm) by 2 1/8 inches (54 mm) deep for use with 1 inch (25 mm) conduit and smaller. On conduit systems using 1 1/4 inch (31.75 mm) conduit, minimum junction box size shall be 4 11/16 inches square by 2 1/8 inches deep.
- B. Where used with raceway(s) containing conductors of 4 AWG or larger, pull box shall be sized as required unless otherwise noted on the drawings.
- C. Where used with raceway(s) containing conductors on systems over 600V, pull box shall be sized per NEC 314 Part IV unless otherwise noted as larger on the drawings.
- D. Locate pull boxes and junction boxes above accessible ceilings, in unfinished areas or furnish and install approved access panels in non-accessible ceilings where boxes are installed. All boxes are to be readily-accessible.
- E. Provide Pull and Junction boxes for communications and other low voltage applications (a) in any section of conduit longer than 100 feet, (b) where there are bends totaling more than 180 degrees between pull points or pull boxes and (c) wherever there is a reverse bend in run. Locate boxes on straight section of raceway (e.g. do not use boxes in place of raceway bends).
- F. Support pull and junction boxes independent of conduit.

3.10 OUTLET BOX INSTALLATION

A. Do not install boxes back-to-back in walls. Provide minimum 6 inch (150 mm) separation, except provide minimum 24 inch (600 mm) separation in acoustic-rated walls.

B. Power:

- 1. Recessed (1/4 inch maximum) outlet boxes in masonry, concrete, tile construction, or drywall shall be minimum 4 inch square, with device rings. Device covers shall be square-cut except rounded corner plaster rings are allowed in drywall applications. Angle cut plaster rings are not permitted. Coordinate masonry cutting to achieve neat openings for boxes. A single gang box can be used in drywall and masonry, for a single device location, when a single conduit enters box.
- 2. Shallow 4 inch square by 1 1/2 inch deep boxes can be used as device boxes for power provided the box and plaster ring is sized for installed device and conductors.

C. Low Voltage:

- Recessed (1/4 inch maximum) outlet boxes in masonry, concrete, tile construction or drywall shall be minimum 4 11/16 inch square by 2 1/8 inch deep with single gang device ring (unless noted otherwise on drawings). Device covers shall be square-cut except rounded corner plaster rings are allowed in drywall applications. Angle cut plaster rings are not permitted. Coordinate masonry cutting to achieve neat openings for boxes.
- D. Provide one conduit from each communications outlet box. Conduit runs between outlet boxes for communications are not allowed. Terminate conduit above accessible ceiling.
- E. Provide knockout closures for unused openings.
- F. Support boxes independently of conduit except for cast boxes that are connected to two rigid metal conduits, both supported within 12 inches (300 mm) of box.
- G. Use multiple-gang boxes where more than one device are mounted together; do not use sectional boxes.
- H. Install boxes in walls without damaging wall insulation.
- I. Coordinate mounting heights and locations of outlets mounted above counters, benches, and backsplashes.
- J. Ceiling outlets shall be 4 inch square, minimum 2 1/8 inch (54 mm) deep except that concrete boxes and plates will be approved where applicable. Position outlets to locate luminaires as shown on reflected ceiling plans.
- K. In inaccessible ceiling areas, position outlets and junction boxes within 6 inches (150 mm) of recessed luminaire, to be accessible through luminaire ceiling opening.
- L. Provide recessed outlet boxes in finished areas; secure boxes to interior wall and partition studs, accurately positioning to allow for surface finish thickness. Use stamped steel stud bridges for flush outlets in hollow stud wall, and adjustable steel channel fasteners for flush ceiling outlet boxes.
- M. Align wall-mounted outlet boxes for switches, thermostats, and similar devices.
- N. Provide cast ferroalloy or aluminum outlet boxes in exterior and wet locations.
- O. Surface wall outlets shall be 4 inch (100 mm) square with raised covers for one and two gang requirements. For three gang or larger requirements, use gang boxes with non-overlapping covers.

3.11 FLOOR BOX INSTALLATION

A. Set boxes level and flush with finish flooring material.

B. Floor boxes for communications shall each be served by conduit(s) dedicated to that box. Conduit runs between floor boxes for communications are not allowed. Conduit shall be part of path that allows for cable to be terminated at wiring hub (e.g. Telecom Room) on same floor on which floor box appears unless noted otherwise.

END OF SECTION

SECTION 26 24 16 - PANELBOARDS

PART 1 GENERAL

1.1 **SCOPE**

A. The work under this section includes main, distribution and branch circuit panelboards.

1.2 **RELATED WORK**

- A. Applicable provisions of Division 1 govern work under this Section.
- B. Section 26 43 13 Surge Protective Devices for Low Voltage Electrical Power Circuits

1.3 **REFERENCES**

- A. ANSI C57.13 Instrument Transformers
- B. NEMA AB 1 Molded Case Circuit Breakers
- C. NEMA KS 1 Enclosed Switches
- D. UL-891 Dead Front Switchboards
- E. Wisconsin Administrative Code SPS 316 Electrical

1.4 **SUBMITTALS**

- A. Include outline and support point dimensions, voltage, main bus ampacity, circuit breaker arrangement and sizes, and interrupting ratings confirming a fully-rated system for all equipment and components.
- B. Submit required short circuit coordination study per specification section 26 05 73 to the consulting engineer for review and approval. Submittal shall be on or before date of panelboard equipment submittal.

1.5 OPERATION AND MAINTENANCE DATA

A. All operations and maintenance data shall comply with the submission and content requirements specified under section GENERAL REQUIREMENTS.

1.6 SPARE PARTS

- A. Keys: Furnish 2 keys for each panelboard to Owner.
- B. Handle lock-off: Furnish (2) 20/1 circuit breaker handle lock-off devices for each panelboard to Owner.
- C. One set of three spare fuses of each size and type utilized

19.0480 **PANELBOARDS** 26 24 16 - 1

PART 2 PRODUCTS

2.1 BRANCH CIRCUIT PANELBOARDS

- A. Lighting and Appliance Branch Circuit Panelboards: Circuit breaker type.
- B. The panelboard and overcurrent devices contained within shall be fully-rated.
- C. Enclosure: Type 1. Minimum cabinet size: 5-3/4 inches (144 mm) deep; 20 inches (508 mm) wide with 5" minimum gutter space top and bottom. Constructed of galvanized code gauge steel. Panel enclosure (back box) shall be of non-stamped type (without KO's) to avoid concentric break out problem.
- D. Cabinet front cover and cabinet shall be Type 4X, 304 stainless steel in wet and damp locations including kitchen, food service and therapeutic/pool applications.
- E. Provide surface cabinet front with concealed trim clamps, concealed hinge and flush cylinder lock all keyed alike. Front cover shall be hinged to allow access to wiring gutters without removal of panel trim. Hinged trim shall be held in place with screw fasteners. Finish in manufacturer's standard gray enamel.
- F. Provide metal directory holders with clear plastic covers.
- G. Provide panelboards with copper bus (phase buses, bus fingers, etc.), ratings as scheduled on Drawings.
- H. Provide ground bars in all panelboards. Phase, neutral and ground bar terminations can be dual rated ALCU9. All spaces shall have bus fully extended and drilled for the future installation of breakers.
- I. Incoming conductors shall terminate at lug landing pads rated for the panelboard.
- J. Provide compression type lugs to accommodate the conductor shown on drawings.
- K. Minimum System (i.e. individual component) Short Circuit Rating: As shown on the Drawings and as required by short circuit/ coordination study.
- L. Molded Case Circuit Breakers: Bolt-on type thermal magnetic trip circuit breakers. Provide UL Class A ground fault interrupter circuit breakers where shown on Drawings. Provide circuit breakers UL listed as Type HACR for air conditioning equipment branch circuits.
- M. Do not use tandem circuit breakers.
- N. Circuit breakers shall be bolt-on type with common trip handle for all poles. No handle ties of any sort will be approved.
- O. Provide a minimum of 10% spare circuit breakers in branch panelboards.
- P. All of the panelboards provided under this section shall be by the same manufacturer.
- Q. All sub-feed panelboards installed side by side shall utilize same enclosure height.

19.0480 PANELBOARDS 26 24 16 - 2

PART 3 EXECUTION

3.1 INSTALLATION

- A. See section 26 05 29 for support requirements.
- B. Install panelboards plumb with wall finishes.
- C. Height:
 - a. Power Distribution panelboards: Minimum 12" above finished floor and maximum of 6'-7" to center of the grip of the operating handle of the top most mounted switch or circuit breaker, when at its highest position.
 - b. Branch panelboards: 6'-0" to top of panelboard.
- D. Install a crimp type stud termination to stranded conductor when terminating on circuit breakers without a captive assembly rated for terminating stranded conductors.
- E. Provide filler plates for unused spaces in panelboards.
- F. See section 26 05 53 for identification requirements. Provide typed circuit directory for each branch circuit panelboard. Revise directory to reflect circuiting changes required to balance phase loads.
- G. Stub three (3) empty 3/4" conduits to accessible location above ceiling or below floor out of each recessed panelboard. Cap these conduits to prevent material from entering them.

3.2 FIELD QUALITY CONTROL

- A. The Contractor shall circuit the panelboards as shown on the drawings. Measure steady state load currents at each panelboard feeder. Should the difference at any panelboard between phases exceed 10 percent, rearrange circuits in the panelboard to balance the phase loads within 10 percent.
- B. Visual and Mechanical Inspection: Inspect for physical damage, proper alignment, anchorage, and grounding. Check proper installation and tightness of connections.

END OF SECTION

19.0480 **PANELBOARDS** 26 24 16 - 3

SECTION 26 27 28 - DISCONNECT SWITCHES

PART 1 GENERAL

1.1 SCOPE

A. The work under this section includes disconnect switches, fuses and enclosures.

1.2 RELATED WORK

- A. Applicable provisions of Division 1 govern work under this Section.
- B. Section 26 27 02- Equipment Wiring Systems

1.3 REFERENCES

- A. NECA (National Electrical Contractors Association) "Standard of Installation."
- B. NEMA ICS 2 Industrial Control Devices, Controllers, and Assemblies.
- C. NEMA KS 1 Enclosed Switches.
- D. UL 50 Enclosures for Electrical Equipment.
- E. UL 98 Enclosed and Dead-front Switches.
- F. NFPA 70 National Electrical Code
- G. Wisconsin Administrative Code SPS 316 Electrical

1.4 SUBMITTALS

A. Include outline drawings with dimensions, and equipment ratings for voltage, ampacity, horsepower, and short circuit.

1.5 OPERATION AND MAINTENANCE DATA

A. All operations and maintenance data shall comply with the submission and content requirements specified under section GENERAL REQUIREMENTS.

1.6 GENERAL

A. Provide disconnect switches for loads required by code. Review HVAC and Plumbing specifications to determine what equipment is furnished with disconnect switches. Install disconnect switches whether furnished under this contract or not. It is the Electrical Contractors responsibility to determine the need for a disconnect switch for each load. The contractors shall include in their bid the code required disconnect switches whether indicated on the drawings or not.

PART 2 PRODUCTS

2.1 DISCONNECT SWITCHES

- A. Fusible Switch Assemblies (use only when overcurrent protection is required): NEMA Type Heavy Duty; quick-make, quick-break, load interrupter, enclosed knife switch with externally operable handle interlocked to prevent opening front cover with switch in ON position. Handle lockable in OFF position. Fuse Clips: designed to accommodate Class R, Class J or Class CC (motors) cartridge type fuses.
- B. Nonfusible Switch Assemblies: NEMA Type Heavy Duty; quick-make, quick-break, load interrupter, enclosed knife switch with externally operable handle interlocked to prevent opening front cover with switch in ON position. Handle lockable in OFF position.

C. Enclosure:

- 1. Outdoors: NEMA 3R code gauge zinc coated steel with baked enamel finish or NEMA 4 when indicated on drawings.
- D. Provide manufacturer's equipment ground kit in all disconnect switches.
- E. In applications where the switch serves as the service entrance disconnect, provide service ground kit, label as service disconnect and provide UL listing for service disconnect.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Install disconnect switches where indicated on Drawings or required by NEC.
- B. Provide identification as specified in Section 26 05 53.
- C. Provide label on inside of disconnect cover identifying the type and size of fuse to be utilized.

END OF SECTION

SECTION 263100 - PHOTOVOLTAIC COLLECTORS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. PV modules (laminates in mounting frames).
 - 2. Inverters.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For PV modules.
 - 1. Include plans, elevations, sections, and mounting details.
 - 2. Include details of equipment assemblies.
 - 3. Include diagrams for power, signal, and control wiring.
 - 4. Ballasted mounting system layout plan and ballast loading.

1.3 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.
- B. Sample warranty.

1.4 CLOSEOUT SUBMITTALS

A. Operation and maintenance data.

1.5 WARRANTY

- A. Manufacturer's Special Warranty: Manufacturer agrees to repair or replace components of PV modules that fail in materials or workmanship within specified warranty period.
 - 1. Warranty Period: Ten years from date of Substantial Completion.
- B. Manufacturer's Special Minimum Power Output Warranty: Manufacturer agrees to repair or replace components of PV modules that fail to exhibit the minimum power output within specified warranty period. Special warranty, applying to modules only, applies to materials only, on a prorated basis, for period specified.

- 1. Manufacturer's minimum power output warranties include, but are not limited to, the following warranty periods, from date of Substantial Completion:
 - a. Specified minimum power output to 80 percent or more, for a period of 25 years.

PART 2 - PRODUCTS

2.1 PHOTOVOLTAIC MODULES

- A. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by of the following:
 - 1. Heliene, Inc.
 - 2. Or approved Equal

2.2 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled by a qualified testing agency, and marked for intended location and application.

2.3 PV SYSTEMS DESCRIPTION

- A. Interactive PV System: Collectors connected in parallel to the electrical utility; and capable of providing power for Project and supplying power to a distributed network.
 - 1. System Components:
 - a. PV modules.
 - b. Array frame.
 - c. Utility-interactive inverter.
 - d. Ballasted Mounting System.
 - e. Cable Management.

2.4 MANUFACTURED PV UNITS – Heliene, Inc

- A. Cell Materials: Monocrystalline.
 - 1. c-Si.
 - 2. Gallium arsenide (GaAs).
- B. Module Construction:
 - 1. Nominal Size: 39.0 inches (992 mm) wide by 77.0 inches (1956 mm) long.
 - 2. Weight: 48.28 lb (21.9 kg).
- C. Encapsulant: Ethyl vinyl acetate.
- D. Front Panel: 0.125-inch- (3.2-mm-) thick tempered glass.

- E. Backing Material: Tempered glass.
- F. Backing Material: 0.125-inch- (3.2-mm-) thick glass; white.
- G. Backing Material: Polyester film.
 - 1. Layers: 1.
 - 2. Color: White.
- H. Junction Box:
 - 1. Size: 1.56 by 3.96 by 0.52 inch (39.6 by 100.6 by 13.2 mm).
 - 2. Fully potted, vandal resistant.
 - 3. IP Code: IP67.
 - 4. Flammability Test: UL 1703.
- I. Output Cabling:
 - 1. 0.158 inch (4 mm).
 - 2. Quick, multiconnect, polarized connectors.
 - 3. Two-Conductor Harness: No traditional return wire is needed from the end of a row back to the source combiner.
- J. Series Fuse Rating: 20 amps.

2.5 PV CAPACITIES AND CHARACTERISTICS –

- A. Minimum Electrical Characteristics:
 - 1. Rated Open-Circuit Voltage: 48.66 V dc.
 - 2. Maximum System Voltage: 1000 V dc.
 - 3. Maximum Power at Voltage (Vpm): 40.22 V dc.
 - 4. Rated Short-Circuit Current (Isc): 9.77.
 - 5. Rated Operation Current (Imp): 9.26.
 - 6. Maximum Power at STC (Pmax): 370.
- B. Normal Operating Temperature Characteristics (NOTC):
 - 1. Temperature at Nominal Operating Cell Temperature: 45 deg C.
 - 2. Temperature Coefficient (NOTC Nominal Power): .-0.39%/ deg C
 - 3. Temperature Coefficient (NOTC Open-Circuit Voltage): .-0.31%/ deg C
 - 4. Temperature Coefficient (NOTC Short Circuit Current): 0.045%/ deg C

2.6 PV MODULE FRAMING

- A. PV laminates mounted in anodized extruded-aluminum frames.
 - 1. Entire assembly UL listed for electrical and fire safety, Class A, according to UL 1703, and complying with IEC 61215.
 - 2. Frame strength exceeding requirements of certifying agencies in subparagraph above.
 - 3. Finish: Anodized aluminum.

- a. Alloy and temper recommended by framing manufacturer for strength, corrosion resistance, and application of required finish.
- b. Color: As indicated by manufacturer's designations.

2.7 PV ARRAY CONSTRUCTION

A. Framing:

- 1. Material: Extruded aluminum.
- 2. Maximum System Weight: Less than 4 lb/sq. ft. (19.53 kg/sq. m).
- 3. Raceway Cover Plates: Plastic.

2.8 INVERTER

A. MANUFACTURER:

- 1. SolarEdge, Inc
- 2. Or Approved Equal
- B. Inverter Type: Central.
- C. Control Type: Maximum power point tracker control.
- D. Inverter Electrical Characteristics:
 - 1. Maximum Recommended PV Input Power: 33,300 watts.
 - 2. Maximum Open-Circuit Voltage: 600 V dc.
 - 3. PV Start Voltage: 300 V
 - 4. MPPT Voltage Range: 300-600 V dc.
 - 5. Maximum Input Current: 40 Amps
 - 6. Nominal Output Voltage: 480V.
 - 7. Maximum Output Current: 40 amps.
 - 8. Peak Efficiency: 98 percent.
 - 9. CEC Weighted Efficiency: 97.5 percent.
 - 10. DC/AC Terminal Range (AWG): 14 thru-6.
 - 11. Communications Interface: RS 485.
 - 12. Utility Interface: Utility-interactive inverter.

E. Operating Conditions:

- 1. Operating Ambient Temperatures: Minus 4 to plus 122 deg F (20 to plus 50 deg C).
- 2. Storage Temperature: Minus 40 to plus 122 deg F (minus 40 to plus 50 deg C).
- 3. Relative Humidity: Zero to 95 percent, noncondensing.

F. Charge controllers shall have the following:

- 1. Overcurrent protection.
- 2. Generator input breaker box.
- 3. Automatic transfer relay.
- 4. Digital display.

- 5. Transformer.
- 6. Disconnect switch.
- 7. Shunt controller.
- 8. Shunt regulator.
- 9. Surge overload protection.

G. Enclosure:

- 1. NEMA 250, Type 3R.
- 2. Enclosure Material: Galvanized steel.
- 3. Cooling Methods:
 - a. Passive cooling.
- 4. Protective Functions:
 - a. AC over/undervoltage.
 - b. AC over/underfrequency.
 - c. Ground overcurrent.
 - d. Overtemperature.
 - e. AC and dc overcurrent.
 - f. DC overvoltage.
- H. Disconnects: Rated for system voltage and conductor.
- I. Regulatory Approvals:
 - 1. IEEE 1547.1.
 - 2. IEEE 1547.3.
 - 3. UL 1741.

2.9 BALLASTED MOUNTING SYSTEM

- A. Manufacturer:
 - 1. Ironridge
 - 2. Or approved equal
- B. Provide a ballasted mounting system as indicated on the drawings.
- C. System shall be compliant with UL 2703.
- D. Glass-Reinforced composite corrosion-free and engineered for long-term structural performance.
- E. Class A fire rating certified to maintain the fire resistance rating of the existing roof.

2.10 CABLE MANAGEMENT

- A. Manufacturer:
 - 1. Snake Tray

- 2. Or approved equal
- B. Pathway shall have a single wire spine located above the cable pathway.
- C. Cable pathway rungs shall overlap "trapping" cables once installed.
- D. Pathway shall be designed in such a way as to be secured to the wall every four (4) feet via built-in integrated vertical mounting rings spaced every four (6) inches along the center spine.
- E. Pathway shall be designed in such a way as to allow the pathway to attach directly to a vertical or horizontal surface without additional mounting brackets.
- F. Pathway to be Stainless Steel in accordance with applicable ASTM standards.
- G. All dimensions are for available cable pathway. Overall physical dimension may or may not be greater than the cable pathway.
 - 1. Depth: Pathway depth shall be (unless otherwise shown on the drawings) 2.0 inches (50mm)
 - 2. Width: Pathway width shall be (unless otherwise shown on the drawings) 2.0 inches (50mm)
 - 3. Length: Pathway section length will be 120 inches (3050mm) unless otherwise drawings.

H. Accessories

- 1. Part Number CM 407-T-SS-KIT, Single TEE Intersection for Solar Snake Tray, Stainless Steel
- 2. Part Number CB-10, Universal Connector Bolt, Bolted and Grounded Connection as per ANSI/NFPA 70/250 National Electric Code Ground and Bonding
- 3. Part Number CB-12-SS, Universal Inline Connector Bolt, Stainless Steel

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Comply with NECA 1.
- B. Examine modules and array frame before installation. Reject modules and arrays that show shipping damage, are wet, are moisture damaged, or are mold damaged.
- C. Coordinate layout and installation of PV panels with support assembly and other construction.
- D. Support PV panel assemblies independent of supports for other elements such as roof and support assemblies, enclosures, vents, pipes, and conduits. Support assembly to prevent twisting from eccentric loading.
- E. Install PV inverters, in locations indicated on Drawings.
- F. Install weatherseal fittings and flanges where PV panel assemblies penetrate exterior elements such as walls or roofs. Seal around openings to make weathertight. See Section 079200 "Joint Sealants" for materials and application.

- G. Wiring Method: Install cables in raceways.
- H. Wiring within Enclosures: Bundle, lace, and train conductors to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Install lacing bars and distribution spools.

3.2 BALLASTED MOUNTING SYSTEM

- A. Provide pads as required by roofing manufacture in order to maintain roof warranty.
- B. Coordinate any anchor points with roofing contractor and retain services of roofing contractor in order to maintain roof warranty.

3.3 CABLE MANAGEMENT

- A. Install pathway/trays in accordance with recognized industry practices, to ensure that the cable pathway/tray equipment complies with requirements of the NEC, and applicable portions of NFPA 70B and NECA "Standards of Installation" pertaining to general electrical
- B. Coordinate installation with other trades.
- C. Field verification is required before installation.
- D. Install cable management system at locations indicated on the drawings and in accordance with manufacturer's instructions.
- E. All pathways shall be grounded per NEC Article 250.
- F. Provide external grounding strap at expansion joints, sleeves and crossover and at other locations where pathway/tray continuity is interrupted.
- G. Install cable tray level and straight unless noted on the construction drawings.

3.4 CONNECTIONS


- A. Coordinate installation of utility-interactive meter with utility.
- B. Make splices, terminations, and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.

END OF SECTION 263100


REQUEST FOR BIDS NO. 320002

CONSOLIDATED FOOD SERVICE PV SOLAR ARRAY

ISSUED: JULY 14, 2020







ELECTRICAL JDR ENGINEERING, INC.

5525 NOBEL DRIVE SUITE 110 MADISON, WI 53711 PHONE: 608-277-1728 JDR PROJECT NO.: 19.0479

1000 E VERONA AVE VERONA, WISCONSIN 53593

SHEET INDEX

TITLE SHEET

LOWER LEVEL FLOOR PLAN - ELECTRICAL

FIRST FLOOR PLAN - ELECTRICAL

ROOF PLAN - ELECTRICAL

ELECTRICAL ONE-LINE DIAGRAM

5525 NOBEL DRIVE MADISON, WI 53711

CONSULTANTS

ISSUED		
REVISIONS /	/ Al	DDENDA

PROJECT#:	19.0480
DRAWN:	
CHECKED:	
DATE:	14 JULY, 2020
PHASE :	CD

CONSOLIDATED FOOD SERVICE

PROJECT

PV SOLAR ARRAY 1000 E VERONA AVE VERONA, WISCONSIN

TITLE SHEET

ABBRE	EVIATIONS:
ABV	ABOVE
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AIC	AVAILABLE INTERRUPTING CURRENT
AIE	ARCHITECT/ENGINEER
ALT	ALTERNATE
ALT SW	ALTERNATOR SWITCH
ARCH	ARCHITECT
ATS	AUTOMATIC TRANSFER SWITCH
BFG	BELOW FINAL GRADE
BLDG	BUILDING
BPC	BOLTED PRESSURE CONTACT SWITCH
BKR	BREAKER
BOL	BUILT IN OVERLOAD
CATV	CABLE TELEVISION
CCTV	CLOSED CIRCUIT TELEVISION
CB	CIRCUIT BREAKER
CKT	CIRCUIT
CLG	CEILING
CP	CONTROL PANEL
CS CT	COMBINATION STARTER CURRENT TRANSFORMER
DE	DUAL ELEMENT FUSES
DIR	DIRECT
DISC	DISCONNECT
DN	DOWN
EC	ELECTRICAL CONTRACTOR
ELEV	ELEVATION
EM	EMERGENCY
ENT EMT	ELECTRICAL NON-METALLIC TUBING ELECTRIC METALLIC TUBING
EOL	END OF LINE RESISTOR
EP ER	EXPLOSION PROOF EXISTING TO BE REMOVED
ERL ERLD	EXISTING TO BE RELOCATED EXISTING RELOCATED
ETR	EXISTING TO REMAIN
EXIST	EXISTING
EWC	ELECTRIC WATER COOLER
F	FLUSH
FAAP	FIRE ALARM ANNUNCIATOR PANEL
FACP	FIRE ALARM CONTROL PANEL
FBO	FURNISHED BY OTHERS
FDR	FEEDER
FIXT	FIXTURE
FLR	FLOOR
FLA	FULL LOAD AMPS
FLUOR	FLUORESCENT
FS	FLOW SWITCH
FVNR	FULL VOLTAGE NON-REVERSING
GC	GENERAL CONTRACTOR
GFI GRC	GROUND FAULT INTERRUPTER GALVANIZED RIGID CONDUIT
GRD	GROUND
GYP	GYPSUM BOARD
HID	HIGH INTENSITY DISCHARGE
HOA	HAND-OFF-AUTO SWITCH
HP	HORSEPOWER
HPS	HIGH PRESSURE SODIUM
HV	HIGH VOLTAGE
HVAC	HEATING & VENTILATING - AIR CONDITIONIN
HVC HW	HEATING VENTILATING CONTRACTOR HEAVYWALL
ID	INDIRECT
IL	INTERLOCK
IMC INC	INTERMEDIATE METAL CONDUIT INCANDESCENT
IU	IN UNIT
J-BOX	JUNCTION BOX
LG	LAY-IN GRID
LTG	LIGHTING
LV	LOW VOLTAGE
LVT	LINE VOLTAGE THERMOSTAT MAGNETIC STARTER
MAG MAN	MANUAL STARTER
MCC MDP	MOTOR CONTROL CENTER MAIN DISTRIBUTION PANEL
MLO	MAIN LUGS ONLY
MSB	MAIN SWITCHBOARD
MTD	MOUNTED
NIC	NOT IN CONTRACT
NU	NEAR UNIT
OU	ON UNIT
P	POLE
PB	PUSHBUTTON
PEND	PENDANT
PC	PHOTO CONTROL
PE SW PLBG	PNEUMATIC SWITCH PLUMBING CONTRACTOR
PNL	PANEL
R	RELAY
RAI	REMAIN AS IS
REC	RECESS
RECEPT	RECEPTACLE
RM	ROOM
RVS	REDUCED VOLTAGE STARTING
S	SPLINE
SELSW	SELECTOR SWITCH

SEL SW SP SW SURF SW TC TCP TCC

TS TYP UG UNIV USS WP XFMR

SWITCH TIME CLOCK

TAMPER SWITCH TYPICAL UNDERGROUND

UNIVERSAL UNIT SUBSTATION

WEATHERPROOF TRANSFORMER

ROOM
REDUCED VOLTAGE STARTING
SPLINE
SELECTOR SWITCH
SPEED SWITCH
SURFACE

TEMPERATURE CONTROL PANEL
TEMPERATURE CONTROL CONTRACTOR

EQUIPMENT SUPPORT RACK:


STRUT RACKING SYSTEM, DESIGN TO ACCOMMODATE LOAD OF ALL

EQUIPMENT, WIREWAYS, CONDUITS THAT WILL BE MOUNTED ON

PROVIDE CROSS BRACING AS REQUIRED TO PREVENT LATERAL DEFLECTION AND TWISTING.

PROVIDE BALLASTS AS REQUIRED TO PREVENT RACK FROM

LIFTING AND OVERTURNING.



EQUIPMENT SCHEDULE					
DESCRIPTION	QTY	MANUFACTURER	MODEL#	TYPE AND SIZE	LISTING
PHOTOVOLTAIC PANELS	199	HELIENE	72M-370	370W MONOCRYSTALLINE PANEL	UL1703
POWER OPTIMIZER	199	SOLAREDGE	P400	400W DC POWER OPTIMIZER, RAPID SHUTDOWN COORDINATED	UL1741
BALLASTED	-	IRONRIDGE	ВХ	10-DEGREE TILT ANGLE	UL2703
CABLE MANGEMENT	-	SNAKE-TRAY	CM-407-22-10-xx-SS- S6	STAINLESS STEEL CABLE CONVEYANCE, COVERS WHERE INDICATED	UL2239
INVERTER WITH DC DISCONNECT	2	SOLAREDGE	SE33.3KUS	33,300W @480V, RAPID SHUTDOWN KIT, DC DISCONNECT	UL1741, UL1699B, UL19
REC METER	1	-	-	PER ALLIANT ENERGY REQUIREMENTS	UL50, UL414, UL486B
AC DISCONNECT	1	SQUARE D	H363RB	600V 100A NEMA3R FUSIBLE SAFETY SWITCH	UL2875

PANELBOARD SC	HEDULE							DESIGN	IATION -	PV-1
					LOAD (VA)					
				PHASE	PHASE	PHASE]			
DESCRIPTION	BREAKER	LOAD	CKT#	Α	В	С	CKT#	LOAD	BREAKER	DESCRIPTION
		11,000	1	11,000	-	-	2			
INVERTER #1	50A/3P	11,000	3	-	11,000	-	4			
		11,000	5	-	-	11,000	6			
		11,000	7	11,000	-	-	8			
INVERTER #2	50A/3P	11,000	9	-	11,000	-	10			
		11,000	11	-	-	11,000	12			
			13	0	-	-	14			
			15	-	0	-	16			
			17	-	-	0	18			
VOLTS (L/L):	480				TOTAL (VA)				18	: # Single Pole Spaces
VOLTS (L/N):			Section 1	22,000	22,000	22,000	1			_
PHASE:			Section 2	•		,	†		X	: NEMA 3R
MAIN BUSSING (AMPS):			TOTAL	22,000	22,000	22,000	1			: Recessed
MAIN BREAKER (AMPS):				FACTURER:		are D	_		Х	: Surface
MAIN BREAKER AIC:				INTERIOR:		I8L1C	_		0.0	KVA Continuous Load (25%
BRANCH BREAKER AIC:	<u> </u>			BOX:		_	_		66.0	DESIGN LOAD (KVA
				COVER:	MH3	8WP	_		79.4	DESIGN AMPS
Sub-Feed Lugs :			20	00 VEIX:			Plated Alum	ninum Buss :	7 9.7	
Through Feed Lugs :		Bran		Construction:		-		per Neutral :	X	_
Isolated Neutral Bar:				Construction:		- -		ckable Door :		-
Cu Equipment Ground Bar:				opper Buss :	X			oor in Door :		_

ENGINEERING, INC. 5525 NOBEL DRIVE SUITE 110 MADISON, WI 53711 PH: 608.277.1728 FAX: 608.271.7046

CONSULTANTS

ISSUED

REVISIONS / ADDENDA

PROJECT#: 19.0480

CD

DRAWN:

CHECKED:

DATE: 14 JULY, 2020

PHASE:

PROJECT

CONSOLIDATED FOOD SERVICE PV SOLAR ARRAY 1000 E VERONA AVE VERONA, WISCONSIN

SCHEDULES, ABBREVIATIONS AND LEGEND





ISSUED		

CONSULTANTS

	_	
•		
	-	
·	_	

REVISIONS / ADDENDA

PROJECT#:	19.048
DRAWN:	-
CHECKED:	-
DATE :	14 JULY, 202

PHASE :


CONSOLIDATED FOOD

PROJECT

SERVICE
PV SOLAR ARRAY
1000 E VERONA AVE

VERONA, WISCONSIN

LOWER LEVEL FLOOR PLAN - ELECTRICAL





CONSULTANTS

ISSUED	
REVISIONS / A	ADDENDA
-	
-	
-	
-	
PROJECT#:	19.04
DRAWN :	
CHECKED:	
DATE :	14 JULY, 20
PHASE :	(

CONSOLIDATED FOOD SERVICE

PROJECT


PV SOLAR ARRAY

1000 E VERONA AVE

VERONA, WISCONSIN

FIRST FLOOR PLAN -ELECTRICAL





1 ROOF PLAN - ELECTRICAL

SCALE: 1/8" = 1'-0"

ENGINEERING, INC

5525 NOBEL DRIVE SUITE 110 MADISON, WI 53711 PH: 608.277.1728 FAX: 608.271.7046

CONSULTANTS

BALLASTED RACKS:

BALLAST TRAYS TO BE EQUIVALENT TO IRON-RIDGE BX SYSTEM. PV PANELS

• CONTRACTOR SHALL GENERATE A BALLAST RACKING LAYOUT AND LOADING

TO HAVE A 10° CONFIGURATION.

REPORT AS PART OF THE SUBMITTAL.

ISSUED

REVISIONS / ADDENDA

PROJECT #: 19.0480

DRAWN:


DATE: 14 JULY, 2020

PROJECT

CONSOLIDATED FOOD SERVICE PV SOLAR ARRAY 1000 E VERONA AVE VERONA, WISCONSIN

> **ROOF PLAN -**ELECTRICAL





Module Specifications			
199x Heliene 72M-370W (Rev.02)			
STC Rating	370 W		
Vmp	40.233 V		
Imp	9.26 A		
Voc	48.66 V		
Isc	9.77 A		

Power Optimizer			
199x SolarEdge P400			
Rated Input DC Power	400 W		
Max Allowed System Voltage	1,000 V		
Max DC Input Current	12.5 A		
Max Efficiency	99.5%		

Inverter Specifications			
2x SolarEdge Technologies SE33.3KUS			
Max AC Power Rating	33.4 kW		
Max Input Voltage	1000 V		
Min Input Voltage	790 V		

1 ELECTRICAL ONE-LINE DIAGRAM
E401 SCALE: None

CONSOLIDATED FOOD
SERVICE

ENGINEERING, INC. 5525 NOBEL DRIVE SUITE 110 MADISON, WI 53711

PH: 608.277.1728 FAX: 608.271.7046

CONSULTANTS

ISSUED

REVISIONS / ADDENDA

PROJECT#:

DRAWN:

CHECKED:

DATE:

PHASE:

PROJECT

19.0480

14 JULY, 2020

CD

PV SOLAR ARRAY 1000 E VERONA AVE

VERONA, WISCONSIN

ELECTRICAL ONE-LINE DIAGRAM