DANE COUNTY PUBLIC WORKS 1919 Alliant Energy Center Way **ENGINEERING DIVISION**

Madison, Wisconsin 53713 Office: 608/266-4018

ADDENDUM

JULY 14, 2022

ATTENTION ALL REQUEST FOR BIDS (RFB) HOLDERS

RFB NO. 322012 - ADDENDUM NO. 3

BUILDINGS & SITE DEMOLITION - COUNTY PROPERTY

BIDS DUE: TUESDAY, JULY 19, 2022, 2:00 PM. DUE DATE AND TIME ARE NOT CHANGED BY THIS ADDENDUM.

This Addendum is issued to modify, explain or clarify the original Request for Bid (RFB) and is hereby made a part of the RFB. Please attach this Addendum to the RFB.

PLEASE MAKE THE FOLLOWING CHANGES:

1. Section 00 01 10 - Table of Contents

Delete current Section 00 01 10; replace with new Section 00 01 10, issued with this Addendum.

2. Section 01 00 00 - General Requirements

Page 1 - Item 1.2.C.: Delete the current paragraph & insert the following:

"Permits: Prior to commencement of the Work, Contractor to secure any and all necessary permits for completion of the Work and facility occupancy. Owner shall provide proof of asbestos remediation data to Contractor. Contractor shall submit this information to Town of Westport with Demolition Permit application. Provide Public Works Project Manager with copies of all permits."

3. Section 02 41 16 - Structure Demolition

Page 7 - Delete current Page 7; replace with new Pages 7 & 8, issued with this Addendum.

4. Section 31 00 00

Delete current Section 31 00 00; replace with new Section 31 00 00, issued with this Addendum.

PLEASE NOTE THE FOLLOWING CONTRACTOR SUBMITTED QUESTIONS:

- Q1: Wondering what the fill spec is for the basement fill?
- A1: Refer to Section 31 00 00, issued with this Addendum.
- Q2: For restoration it does not say if we're to topsoil seed and mat site or are we to just leave it as on site dirt?
- A2: Refer to Section 31 00 00, issued with this Addendum.

If any additional information about this Addendum is needed, please contact Scott Carlson at 608/266-4179, carlson.scott@countyofdane.com.

Sincerely,

Scott Carlson

Project Manager

Enclosures:

Section 00 01 10 Section 02 41 16 - 7 & 8 Section 31 00 00 Attachment A Attachment B Attachment C Figure 1

H:\Shared\ENGINEERING DIVISION\Scott Carlson\322012 - Hwy Bldgs Demo\04 - Addenda\322012-Addendum 3.docx

SECTION 00 01 10

TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

00 01 01 - Project Manual Cover Page

- 00 01 10 Table of Contents
- 00 11 16 Invitation to Bid
- 00 21 13 Instructions to Bidders

00 41 13 - Bid Form

00 43 36 - Proposed Subcontractors List

00 52 96 - Sample Public Works Construction Contract

00 61 12 - Sample Bid Bond

00 61 13.13 - Sample Performance Bond

00 61 13.16 - Sample Payment Bond

00 72 13 - General Conditions of Contract

00 73 00 - Supplementary Conditions

00 73 07 - Best Value Contracting

00 73 11 - Fair Labor Practices Certification

DIVISION 01 - GENERAL REQUIREMENTS

01 00 00 - General Requirements

01 74 19 - Construction Waste Management, Disposal & Recycling

DIVISION 02 - EXISTING CONDITIONS

02 41 16 - Structure Demolition

DIVISION 31 - EARTHWORK

31 00 00 - Earthwork

DRAWINGS

Plot drawings on 11" x 17" (ANSI B) paper for correct scale or size. Figure 1 - Site Plan

ATTACHMENTS

A - Private Onsite Wastewater Treatment System (POWTS) Information

B - Septic System Abandonment Information

C - Erosion Control Plan Information

END OF SECTION

Page Intentionally Left Blank

- 2. Maintain fire watch during and for at least two (2) hours after flame cutting operations.
- 3. Maintain adequate ventilation when using cutting torches.
- 4. Locate building demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors or framing.
- C. Remove all foundation walls and footings entirely below finished grade on site.
 - 1. Arrange for Public Works Project Manager to witness final removal of all subgrade structures. Allow minimum 48 hours notice.
- D. Remove concrete slabs-on-grade.
- E. Remove any bollards, above & below grade, or any similar structures.
- F. Remove mobile lighting station at the site.
- G. Empty underground tanks located within demolition area.
- H. Remove any underground tanks, components, and piping from site.
- I. Demolish existing septic system.
 - 1. Follow directions detailed in Attachment B.
 - 2. Break the top of the existing septic tank & fill it. Arrange for Public Works Project Manager & Town of Westport Building Inspector to witness filled tank before it is backfilled & covered. Allow minimum 48 hours' notice.
 - 3. Completely remove all system vents from the ground.
 - 4. Submit required forms to Public Health Madison & Dane County & copy Public Works Project Manager & Town of Westport Building Inspector.
- J. Demolish existing water well system.
 - 1. Remove all mechanical components.
 - 2. Caisson to be cut off & removed minimum of 18" below grade. Fill remaining structure with bentonite & seal the top.
 - 3. Only State of Wisconsin licensed well drillers or pump installers may perform this work. Qualified contractors are listed at these websites:
 - a. <u>https://dnr.wi.gov/topic/Wells/documents/WellDrillers.pdf</u>
 - b. <u>https://dnr.wi.gov/topic/Wells/documents/pumpinstallers.pdf</u>
 - 4. Report & fill out required forms to WDNR & Public Health Madison & Dane County & copy Public Works Project Manager & Town of Westport Building Inspector.
- K. Backfill areas excavated and open pits and holes resulting from demolition.
- L. Rough grade and compact areas affected by demolition to accommodate subsequent construction operations.
- M. Continuously clean-up and remove demolished materials from site. Do not allow materials to accumulate in building or on site.

N. Do not burn or bury materials on site. Leave site in clean condition.

3.7 SCHEDULES

A. Determine and verify schedule with Owner at pre-construction meeting minimum one (1) week prior to commencing the Work.

END OF SECTION

SECTION 31 00 00

EARTHWORK

PART 1 GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Site preparation before demolition.
 - 2. Site maintenance during demolition.
 - 3. Site restoration after demolition.
- B. Related Sections:
 - 1. Section 01 00 00 General Requirements
 - 2. Section 01 74 19 Construction Waste Management, Disposal & Recycling
 - 3. Section 02 41 16 Structure Demolition

1.2 SUMMARY OF THE WORK

- A. Contractor shall prepare everything necessary for site work to commence. This includes all interactions & work preparation with utility companies, protecting designated trees, shrubs & other plant life, obtaining & conforming with all necessary permits (including Erosion Control Plan) & equipment tracking pad requirements from Section 02 41 16 Structure Demolition.
- B. Contractor shall keep & maintain all erosion control measures, remove surface debris, designated paving & curbs & remove abandoned utilities.
- C. After demolition is complete, restore site as described herein. Contractor shall provide fill & compaction where needed, shall rough & fine grade site & shall seed & mulch site.

1.3 SUBMITTALS

A. Section 01 00 00 - General Requirements: Submittal Procedures.

1.4 EROSION CONTROL PLAN

- A. Attachments to this Project Manual:
 - 1. Erosion Control Plan Site Map.
 - 2. Erosion Control Plan Soils & Contours Map.
 - 3. Universal Soil Loss Equation for Construction Sites Table.
 - 4. Other related Erosion Control Plan information.

1.5 MATERIAL OWNERSHIP

A. Except for stripped topsoil and other materials indicated to be stockpiled or otherwise remain Owner's property, cleared materials shall become Contractor's property and shall be removed from the Work site.

1.6 PROJECT CONDITIONS

- A. Traffic: Minimize interference with adjoining roads, streets, walks, and other adjacent occupied or used facilities during site-clearing operations.
 - 1. Do not close or obstruct streets, walks, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction.
 - 2. Provide alternate routes around closed or obstructed traffic ways if required by Owner or authorities having jurisdiction.
- B. Do not commence site-clearing operations until erosion control measures are in place.
- C. These practices are prohibited within protection zones (area on site where no demolition is taking place):
 - 1. Storage of construction materials, debris, or excavated material.
 - 2. Parking vehicles or equipment.
 - 3. Erection of sheds or structures.
 - 4. Impoundment of water.
 - 5. Excavation or other digging unless otherwise indicated.
 - 6. Attachment of signs to or wrapping materials around trees or plants unless otherwise indicated

1.7 QUALITY ASSURANCE

- A. Conform to applicable codes for environmental requirements & disposal of debris.
- B. Perform the Work in accordance with State of Wisconsin, Dane County Public Works & Town of Westport standards.
- C. Maintain one copy of each document on site.

PART 2 PRODUCTS

2.1 MATERIALS

- A. Erosion Control Measures: WDNR Standards 1057, 1059, 1060 & 1071.
- B. General Fill: Requirements for general fill are specified in Section 3.3.
 - 1. Obtain approved borrow soil material off site when general fill is not available on site.
 - 2. Granular Fill: Sand and/or gravel soil free of rock or gravel larger than 6 inches in any dimension, debris, waste, frozen materials, vegetation, and other deleterious matter.

- C. Seed:
 - 1. Seed Selection:
 - a. Seed mixtures that will produce dense vegetation shall be selected based on soil and site conditions and intended final use. Section 3.3.E.9. References, lists sources containing suggested seed mixtures.
 - b. All seed shall conform to requirements of Wisconsin Statutes and of Administrative Code Chapter ATCP 20.01 regarding noxious weed seed content and labeling.
 - c. Avoid seed mixtures that contain potentially invasive species or species that may be harmful to native plant communities.
 - d. Use no seed later than one year after test date that appears on label.
 - e. Test seed for purity, germination and noxious weed seed content and shall meet minimum purity and germination requirements as prescribed in current edition of Rules for Testing Seed, published by Association of Official Seed Analysts.
- D. Mulch: WDNR Standards 1058.

PART 3 EXECUTION

- 3.1 SITE PREPARATION
 - A. Verify existing conditions before starting the Work.
 - B. Implement all pre-demolition measures dictated in Erosion Control Plan. Continue all required measures throughout entirety of the Work.
 - C. Obtain demolition & erosion control permits from Dane County. Owner shall provide necessary information to aid application(s) completion.
 - D. Verify with Owner, tag & identify existing trees, shrubs & plant life designated to remain.
 - E. Protect benchmarks, survey control points, and existing structures from damage or displacement.
 - F. Protect all existing site improvements such as fencing, trees, shrubs, plant life, sidewalks & asphalt parking areas from damage or displacement.
 - G. Restore any damaged site improvements to their original condition as acceptable to Owner.
 - H. Contact utility companies serving or crossing site to plan for demolition work:
 - 1. Call Diggers Hotline not less than three working days before performing the Work:
 - a. Request underground utilities to be located and marked within and surrounding construction areas.
 - b. Locate, identify, and protect utilities indicated to remain, from damage.

2. Disconnect, remove and / or isolate any remaining utilities serving buildings as dictated by utility companies.

3.2 SITE MAINTENANCE

- A. Erosion control measures:
 - 1. Provide erosion control measures to prevent soil erosion and discharge of sediment or airborne dust to adjacent properties and walkways, according to Erosion Control Plan.
 - 2. Verify that flows of water redirected from construction areas or generated by construction activity do not enter or cross protection zones.
 - 3. Inspect, maintain, and repair erosion control measures during construction until permanent vegetation has been established.
 - 4. Notify Owner when site is fully stabilized:
 - a. Do not remove any erosion control measures until Owner has authorized their removal upon final site stabilization.
- B. Waste removal:
 - 1. Remove debris, rock and only designated plant life from site.
 - 2. Remove paving and curbs as indicated on Drawings. Neatly saw cut edges at right angle to surface.
 - 3. Remove abandoned utilities. Indicated removal termination point for underground utilities on Record Documents.
 - 4. Continuously clean-up and remove waste materials from site. Do not allow materials to accumulate on site.
 - 5. Do not burn or bury materials on site. Leave site in clean condition.
- C. Disposal of surplus and waste materials:
 - 1. Remove surplus soil material, unsuitable topsoil, obstructions, demolished materials, and waste materials including trash and debris, and legally dispose of them off Owner's property.
 - 2. Separate recyclable materials produced during site clearing from other nonrecyclable materials. Store or stockpile without intermixing with other materials and transport them to recycling facilities. Do not interfere with other construction or non-construction related work on-site.
- D. Identification & disposal of residual contaminated soils:
 - 1. Dane County's environmental consultant shall be on site to review conditions & facilitate any necessary soils and / or groundwater testing.
 - 2. Environmental consultant will provide a disposal profile and waste manifests for all previously identified contaminated materials on the site.
 - 3. Environmental consultant will field screen and identify materials that will need to be removed for disposal.
 - 4. Contractor will transport & dispose of all identified contaminated soil, under manifest, to Dane County's Landfill as per WDNR standards and regulations.
 - 5. Any contamination that is encountered that does not meet the disposal profile shall be identified by the environmental consultant on site and will be stockpiled on polyethylene sheeting away from other stockpiled or removed material. Cover all contaminated material with additional polyethylene sheeting and

maintained on site until the environmental consultant has developed a new disposal profile for the material. Contractor will transport & dispose of all identified contaminated soil, under manifest, to Dane County's Landfill as per WDNR standards and regulations.

3.3 SITE RESTORATION

A. Definitions:

- 1. Backfill: Soil material used to fill excavation.
- 2. Borrow Soil: Suitable soil imported from off-site for use as fill or backfill.
- 3. Excavation: Removal of material encountered above subgrade elevations and to lines and dimensions indicated.
- 4. Fill: Soil materials used to raise existing grades.
- 5. Structures: Buildings, footings, foundations, retaining walls, slabs, tanks, curbs, mechanical and electrical appurtenances, or other man-made stationary features constructed above or below ground surface.
- 6. Subgrade: Uppermost surface of excavation or top surface of fill or backfill immediately below subbase, drainage fill, drainage course, or topsoil materials.
- B. General Excavation:
 - 1. Unclassified Excavation: Excavate to subgrade elevations regardless of character of surface and subsurface conditions encountered. Unclassified excavated materials may include rock, soil materials, and obstructions. No changes in Contract Sum or Contract Time will be authorized for rock excavation or removal of obstructions.
 - 2. If excavated materials intended for fill and backfill include unsuitable soil materials and rock, replace with suitable soil materials.
- C. Backfill:
 - 1. All labor, materials, equipment, and related services necessary to furnish and install all subgrade preparation, excavation and backfill for site as indicated on drawings or specified herein.
 - 2. Compaction of soil fills:
 - a. Place fill soil materials in layers not more than 10 inches in loose depth for material compacted by heavy compaction equipment, and not more than 4 inches in loose depth for material compacted by hand-operated tampers.
 - b. Place fill soil materials evenly on all sides of structures to required elevations, and uniformly along full length of each structure.
 - c. Compact fill materials to not less than these percentages of maximum dry unit weight according to ASTM D 1557:
 - 1) Compact each fill layer to minimum of 90 percent.
- D. Grading:
 - 1. Match existing grades.
 - 2. Taper toward site drainage features & not toward streets or surrounding properties.

- 3. General: Uniformly grade areas to smooth surface, free of irregular surface changes. Comply with compaction requirements and grade to cross sections, lines, and elevations indicated.
- 4. Site Rough Grading: Slope grades to direct water away from buildings and to prevent ponding.
- E. Seed & mulch:
 - 1. Definition:
 - a. Planting seed to establish temporary or permanent vegetation for erosion control.
 - 2. Purpose:
 - a. Purpose of *permanent seeding* is to permanently stabilize areas of exposed soil.
 - 3. Conditions Where Practice Applies:
 - a. This practice applies to areas of exposed soil where establishment of vegetation is desired. Permanent seeding applies to areas where perennial vegetative cover is needed.
 - 4. Federal, State and Local Laws:
 - a. Users of this standard shall be aware of all applicable federal, state and local laws, rules, regulations or permit requirements governing seeding. This standard does not contain text of federal, state or local laws.
 - 5. Criteria:
 - a. This section establishes minimum standards for design, installation and performance requirements.
 - b. Site and Seedbed Preparation:
 - 1) Site preparation activities shall include:
 - a) Permanent Seeding:
 - (1) *Topsoil* installation shall be completed prior to permanent seeding.
 - (2) Permanent seeding requires seedbed of loose topsoil to minimum depth of 4 inches with ability to support *dense* vegetative cover.
 - (3) Application rates of fertilizer or lime shall be based on soil testing results.
 - (4) Prepare tilled, fine, but firm seedbed. Remove rocks, twigs foreign material and clods over two inches that cannot be broken down.
 - (5) Soil shall have pH range of 5.5 to 8.0.
 - c. Seeding:
 - 1) Permanent Seeding Rates:
 - a) Rates shall be based on pounds or ounces of Pure Live Seed (PLS) per acre. Section 3.3.E.9 contains some possible reference documents that provide seeding rates. Permanent seeding rates may be increased above minimum rates shown in reference documents to address land use and environmental conditions.

- b) If nurse crop is used in conjunction with permanent seeding, nurse crop shall not hinder establishment of permanent vegetation.
- c) Nurse crop shall be applied at 50% its temporary seeding rate when applied with permanent seed.
- 2) Inoculation:
 - a) Legume seed shall be inoculated in accordance with manufacturer's recommendations. Inoculants shall not be mixed with liquid fertilizer.
- 3) Sowing:
 - a) Seed grasses and legumes no more than ¼ inch deep. Distribute seed uniformly. Mixtures with low seeding rates require special care in sowing to achieve proper seed distribution.
 - b) Seed may be broadcast, drilled, or hydroseeded as appropriate for site.
 - c) Seed when soil temperatures remain consistently above 53° F. *Dormant seed* when soil temperature is consistently below 53° F (typically Nov. 1st until snow cover). Seed shall not be applied on top of snow.
- 6. Considerations:
 - a. Consider seeding at lower rate and making two passes to ensure adequate coverage.
 - b. Compacted soil areas may need special site preparation prior to seeding to mitigate compaction. This may be accomplished by chisel plowing to depth of 12 inches along contour after heavy equipment has left site.
 - c. Site assessment should be conducted to evaluate soil characteristics, topography, exposure to sunlight, proximity to natural plant communities, proximity to nuisance, noxious and/or invasive species, site history, moisture regime, climatic patterns, soil fertility, and previous herbicide applications.
 - d. Use *introduced species* only in places where they will not spread into existing natural areas.
 - e. Lightly roll or compact area using suitable equipment when seedbed is judged to be too loose, or if seedbed contains clods that might reduce seed germination.
 - f. See Section 3.3.E.9. References for suggested seed mixes (NRCS, WisDOT, UWEX) or use their equivalent.
 - g. Turf seedlings should not be mowed until stand is at least 6 inches tall. Do not mow closer than 3 inches during first year of establishment.
 - h. Seeding should not be done when soil is too wet.
 - i. Consider watering to help establish seed. Water application rates shall be controlled to prevent runoff and erosion.
 - j. Prairie plants may not effectively provide erosion control during their establishment period without nurse crop.
 - k. Topsoil originating from agricultural fields may contain residual chemicals. Seedbed should be free of residual herbicide or other contaminants that will prevent establishment and maintenance of

vegetation. Testing for soil contaminants may be appropriate if there is doubt concerning soil's quality.

- 1. Consider using mulch or nurse crop if selected species are not intended for quick germination. When mulching refer to WDNR Conservation Practice Standard Mulching for Construction Sites (1058).
- 7. Plans and Specifications:
 - a. Plans and specifications for seeding shall be in keeping with this standard and shall describe requirements for applying this practice.
 - b. All plans, standard detail drawings, or specifications shall include schedule for installation, inspection, and maintenance. Responsible party shall be identified.
- 8. Operation and Maintenance:
 - a. During construction, areas that have been seeded shall at minimum be inspected weekly and within 24 hours after every precipitation event that produces 0.5 inches of rain or more during 24-hour period. Inspect weekly during growing season until vegetation is densely established or permit expires. Repair and reseed areas that have erosion damage as necessary.
 - b. Limit vehicle traffic and other forms of compaction in areas that are seeded.
 - c. Fertilizer program should begin with soil test. Soil tests provide specific fertilizer recommendations for site and can help to avoid over-application of fertilizers.
- 9. References:
 - a. Seed Selection References:
 - United States Department of Agriculture Natural Resource Conservation Service Field Office Technical Guide Section IV, Standard 342, Critical Area Planting.
 - 2) UWEX Publication A3434 Lawn and Establishment & Renovation.
 - WisDOT, 2003. State of Wisconsin Standard Specifications for Highway and Structure Construction. Section 630, Seeding.
 - b. General References:
 - 1) Association of Official Seed Analysts, 2003. Rules for Testing Seed. http://www.aosaseed.com.
 - Metropolitan Council, 2003. Urban Small Sites Best Management Practice Manual, Chapter 3, Vegetative Methods 3-85 – 3-91. Minneapolis.
 - 3) State of Wisconsin list of noxious weeds can be found in Statute 66.0407.
 - United States Department of Agriculture Natural Resources Conservation Service. Engineering Field Handbook, Chapters 16 and 18.
 - 5) UWEX Publication GWQ002 Lawn & Garden Fertilizers.
- 10. Definitions:
 - a. *Dense* (3.3.E.5.b.1)a)(2)): Stand of 3-inch high grassy vegetation that uniformly covers at least 70% of representative 1 square yard plot.

- b. *Dormant seed* (3.3.E.5.c.3)): Seed is applied after climatic conditions prevent germination until following spring.
- c. *Introduced Species* (3.3.E.6.d.) Plant species that historically would not have been found in North America until they were brought here by travelers from other parts of the world. This would include smooth bromegrass and alfalfa. Some of these species may have wide distribution such as Kentucky bluegrass.
- d. *Nurse Crop* (3.3.E.5.c.1)): Also known as companion crop; is application of temporary (annual) seed with permanent seed.
- e. *Permanent seeding* (3.3.E.2) Seeding designed to minimize erosion for indefinite period after land disturbing construction activities have ceased on site.
- f. Topsoil (3.3.E.5.b.1)a)(1) Consists of loam, sandy loam, silt loam, silty clay or clay loam humus-bearing soils adapted to sustain plant life with pH range of 5.5 8.0. Manufactured topsoil shall through addition of sand or organic humus material, peat, manure or compost meet above criteria.
- F. Mulch: WDNR Standards 1058.
- G. Long term care:
 - 1. Contractor shall be responsible for all repairs & replacement of seeded & mulched areas during warranty period. This shall also include existing trees, shrubs & plant life that may have damaged during construction but damage was not noticed or obvious immediately.
 - 2. If Owner determines compaction or grading is insufficient (i.e., stormwater runoff not moving as expected, areas showing signs of sinking).
 - 3. Owner shall do maintenance such as mowing & weeding. Owner shall care for site after warranty period has expired.

END OF SECTION

Page Intentionally Left Blank

ATTACHMENT A

PRIVATE ONSITE WASTEWATER TREATMENT SYSTEM (POWTS) INFORMATION

Refer to the following pages for additional information on the project site.

Page 2
DANE COUNTY HUMAN SERVICES DEPARTMENT DB 15066 ENVIRONMENTAL HEALTH DIVISION PTS-15581 OK6-
Owner MADIGAN REFRÉERATION AND ENERGY Parcel No0809-282-8680-8
Mailing Address5305 HWY M, WAUNAKEE WI 53597
Property Address 5305 CTH M Strumakee
Subdivision/CSM Lot Block
Section 28 NW 1/4 NE 1/4
Township/CityWESTPORT
3/28/95 Issued Sentary Permit for Repair + Reconnection 227189/ 95-0067 THM letter to anel
4-17-95 FINAL INSPECTION OF BUILDING SEWER HOOK-UP FOR EMPLOTEE
BATTLEOSIM TO EXISTING P.S.S RCH, Maintain 3/96 recall
NOTE: THE EXISTING IN-GROUND PRESSURE DISTRIBUTION DRAINFIELD IS FULL OF PONDED EFFLUENT WATER -NOT FAILED, BUT DRAINFIELD IS
FULL AS OBJERVED IN OBJERVATION PIPES TO WITHIN 2" OF GROUND
SURFACE.
4-18-95 letter whitten to Richard Madigun about existing condition of ponded IN-GROWND RESSURE DISTRIBUTION DRAWFIED, FUTURE OPTIONS Rtc RCH
4/24/95 Onsite report sent to 5. Ceasby - hole clasure notice to anne
8-2-95 Letter to Dick Madegon re well enop - 7/31/95 Inspection - No Vid (well)
4/9/94 Regid This your ifee - placed on 3/99 recall
4/9/96 Regid TAM form i fee - placed on 3/99 recel 5-8-96 Sanitary permit issued 245903 96-0163 Mound TAM letter to owner
7-8-96 MOUND CONST. INSP- DOLL MOISTURG OK TO PLOW- SAND OK- SAND & AGGRGAR FROM CAPITAL SAND & GRAVEL - ASUND COMPLETE -
OK TO Backfill - Rett
1-7-97 RECEIVED REPORT OF SISTER MARTING - Riff
12/7/78 new THM notice sent 3-9-99 Read TAM report & fee - Placed on 03/02 reall 76/9/200 TH Inspection Letter Sent - Complying System BMH 16/8/200 TH Inspection Peter med EMIP 1/02 The point & fee read - Placed on 3/05 recall
1/2/02 john prepart & fee reco - placed on 3/05 recall

231-1-15 (6/90)

DANE COUNTY PUBLIC HEALTH DEPARTMENT Environmental Health Division 33-089-282-8680-8 1206 Northport Drive, Room 101 Madison, Wisconsin 53704 Telephone 241-8223 33-28-537.1 StopN BO #257 Modigan Refugeration and En Establishment Name______ Richard Date Operator: M.E. Madigan Phone Owner: NE NW, Section 28 Premise Location NW2, 5305 Hwy M, Waunakee, WI 53597 (City - Village - Town) File WESTPORT Premise Establishment 6-20-83 Soil suitability report sent to Joe Meinholz, hole closure notice sent to owner 6-20-83 Orders issued to Richard Madigan P454 345 863 FUND WI soil suitability report, 115 ch! #15 6-28-83 Copy B. Serean y Plumber orwarde de c 7-72-83 Revid Plb 100a ed Capy of maile report. θ 7-21-83 Sign to. 1e J.P 8-8-83 Re 36816 lanitary permit is 6-83 83-0383 Ø eled for a bott 7-13-83 (I The be Q - 5 R. the lled Page S OKtop JAC 0 A 9-14-83 Con Bed 9:00 Rm. U ita P to 11-10-83 eed all Donen Unone m. 3-6-84 mad igan re -20-84 Mr Madia 3-28-84 Fi I.also ٩ 4-4-84 mum delin Cove rdia Co 8:700-10 4 -ou rave an proscible retu 100 on DAR (7)845 re: vert location too In 84 nn 19 structu to elti all ·24-84 I Cm n Do. D NP 9-13-85 88385 Þ 546.00 H for 2 ann of Maint. info der -5-86 12.4-86 213833 Plac on 1990 Ner 12-23-86 TAM ee reco J ORN 12-4-89 193 3-19-90 Reci 0 Mar *rec* TAN 00 f Da vz Cle 2/11/91 e МĠ - 91 Ò 2/11/93 231-1-15 (6/79)

Wisconsin Department Of Industry, Labor and Human Relations P.O. Box 7969

ı,

ON SITE SEWAGE SYSTEM **INSPECTION REPORT** N. 11

Safety & Buildings Division 1xF57 PODT - 70

Madison, WI, 53707	County: <u>p</u>	ANE	,		28
CONVENTIONAL AT-GRADE	☐ IN-GROUND PRESSUR				
Permit Holder's Name:	· ·			OTHER (SPECIF	Y)
MADIGAN REFRIGERATION	Permit Holder's Address:			Inspection Date:	
	5305 CTH "M", h	AUNAKEE	WA	7-8-96	
Bench Mark, Describe if Different From Plan: Botton of Siding on Si	4ED - SEE PLAN	Parcel Tax I.D. No. 33-0804-28	(Optional)	Ref. Pt. Elev.:	CST Ref. Pt. Elev.:
Plumber's Name:	MP/MPRSW No -	State Plan ID No. (I			SAME
STEVE CROSBY	3375	96-011		Sanitary Permit N	-
SEPTIC TANK/HOLDING TANK:				24590	3
Manufacturer:	Liquid Capacity: Tank		-0163		
EXISTING - MEADE Bedding: Vent Dia: Vent Mat'l	2000		Outlet Elev.:	Warning Label Provided:	Locking Cover Provided:
	: High Water Alarm: NUMB FEET F		Property Line		
		ST>	ļ		
DOSING CHAMBER:	ANKS ARE EXI	STING - SE	E FILL	9-14-8-	3 INSTALLATION
	apacity: Pump Model: Pump/Si	phon Manufacturer:	High Water Ala	arm Warning Lab	Del Locking Cover
MEADE XYes INO 2000	WPOJE Ga	PULDS	-∰Yes □ No	Provided	Provided:
Gallons Per Cycle: (difference between $3^{(l)}$ 3 k/ a. l	/ Pump and Controls Operation		Property Line		
pullip unallu ull) = $\int 277 q\alpha$	Yes □ No	FEET FROM			
Vent Installed: Vent Diameter	: Vent Material: FOR	CE Length:	Diameter: M	aterial and Markini	
VENT Ares INO 411	PVC MAI	N 150'E	2//	G1 40 1	orr 1
SOIL ABSORPTION SYSTEM. Check the soil m the soil is dry enough to continue.)	oisture at the depth of plowing c	or excavation. (If soil	I can be rolled in	to a wire, construct	tion shall cease until
DISTRIBUTION STSTEM:					
BED/TRENCH Width: Length: No. Tren	ches: Lateral Spacing: Cover	Material:		· · · · · · · · · · · · · · · · · · ·	
DIMENSIONS 10 65			Inside Dia:	No. Pits:	Liquid Depth:
	End Elev.; Pipe Material No				
6" 18" 101.08			FROM I	ty Line: Well: B	uilding: Air Vent:
Manifold Flows 1 Mar - 4	old Dia.: Manifold Material:	NEAR	EST -> S	50+	14 —
ELEVATION AND DISTRIBUTION	11	011-	No. Distr. Pij		· //
INFORMATION Hole Size: Hole Spacing:	Drilled Correctly: Permanen	VC	12	///	
1/4" 43"			000	p Elev.: Vertical	Lift Corresponds To ed Plans:
1 13	Yes No Yes	No Ves	<u> </u>	T Apploy	
MOUND SYSTEM: 28'+ 85'	MOUND	· · · · · · · · · · · · · · · · · · ·			
Mound site plowed perpendicular to	Check the texture o	f the fill material for	F	ROVIDE A DIAGRA	M OF SYSTEM
slope and furrows thrown unslope	mound systems to m			ON REVERSE SIDE.	
Yes No	meets the criteria fo			LEVATIONS MEAS	URED.
SOIL COVER SIL & CL		Permanent		Observatio	
	-		res 🗍 No	D DY	es 🗌 No
18 (hs Of Topsoil: S	odded:	Seeded:	Mulched:
		s''t	Ves ANO	Yes No	Yes No
COMMENTS: (Sketch System On Reverse Side)		```	TOBE	DATE
INSTALLATION APPR	oved - OK -	TO BACK	FILL		
GROUND AT MOUND	- 99 4' EI				
. .					
SYSTEM ELEVATION	· ·				
DISTO PIPES IN MO	ND = 101.08				
C. L	0				

EXISTING SEPTIC TANK, PUMP CHAMBER AND IN-GROUND PRESSURE SEEPAGE WERE INSTALLED 9-14-83. NEW MOUND SYSTEM IN STALLED 7-8-96 WITH SWITCHING VALVE BETWEEN OLD IGP BED & NEW MOUND.

Menho INSTALLER

SEHIOR SANITARIAN Signature: Title:


SBD-6710 (R 09/90)

(Keep'a copy in your file for audit)


đ > NORTH NOT DRAWN TO SCALE MADIGAN REFRIGERATION 5305 CTH "M" WESTPORT - 28 NEW 28't 85" MOUND 124. DRAWFIELD RW \sim イエ 5460 -7 DN 14't. о SLAB -÷. EXISTING BROAM 3" FEM. #GP shetchent 1983 VALVE. Ň 2000 CAL PT. 2000 GN 57 1 PHKS 5-15-1ALLED 5-1983 11/2 570P-N-60K 71/2 221 BOTH BULLAN 75 INTERSECTS 151 WITH CTH "M" Richard C Herns SENIOR SANITARIAN 7-8-96

	SA		VIT APPLICATI 83.05, Wis. Adm. Code	ON		Burea 201 E P.O. B	su of Bui . Washin Iox 7969	ildings Div Iding Wate Igton Ave. 53707-796	er Syste
 Attach complete plan than 8 1/2 x 11 inches 		copy only) for the s	ystem, on paper not		ty an C	90	5-0	163	
See reverse side for in	nstructions for co	ompleting this appli	cation		Sanitary P			2	
The information you provide m Privacy Law, s. 15.04 (1) (m)].	nay be used by other	government agency pro	grams	5	eck il revisio		YU_ ous applic) ation	
. APPLICATION INFO	ORMATION - P	I FASE PRINT AI			Plan I.D. N 9 L	umber	119	5	
Property Owner Name Richard Madiga		2 ()	 Property I 	_ocation				 E (o r) ₩	
Property Owner's Mailing Add	ress 🗸	Keriyeraii	Lot Number	<u> </u>		ck Numb			• • •
<u>5305</u> CTY H	, Zip Code	Phone Number	r Subdivision Na	ame or CSM Nu	ımber				
<u>Uaunakee</u> (U) I. TYPE OF BUILDING	5359-	7 () □ State Owned	City			Nearest	Road		
🛛 Public 🗌 1 or 2	Family Dwelling	- No. of bedrooms	☐ City ☐ Village ——— ☑ Town OF		17	HU		K	
II. BUILDING USE: (If building type is pub	olic, check <u>all</u> that apply)	Parcel Tax Nur		01	00	0		
1 🔲 Apartment / Conc	do		33-08	09-282	2 – 86	,80-	5		
 2 Assembly Hall 3 Campground 		/ledical Facility / Nu /lerchandise: Sales /			Dutdoor			-	
4 Church / School		Aobile Home Park	Repairs		Restaurar Service St				
5 🔲 Hotel / Motel		Office / Factory •			Other: spe				
/	· (Check only on	اھ					1 × ×	nue	-
V. TYPE OF SYSTEM Non-Pressurized Distrib 11 Seepage Bed 12 Seepage Trench	pution	e) Pressurized Distribu 21 🔀 Mound 22 🗍 In-Ground Pre	30 [erimental] Specify Ty	/pe	41		Iding Ta	
Non-Pressurized Distrib 11 Seepage Bed 12 Seepage Trench 13 Seepage Pit	pution	Pressurized Distribu 21 🔀 Mound	30 [/pe	41 42	l 🗌 Ho 2 🗌 Pit	Iding Ta	nk
Non-Pressurized Distrib	pution	Pressurized Distribu 21 🖾 Mound 22 📋 In-Ground Pre	30 [/pe	41 42	l 🗌 Ho 2 🗌 Pit	lding Ta Privy	nk
Non-Pressurized Distrib 11 Seepage Bed 12 Seepage Trench 13 Seepage Pit 14 System-In-Fill	STEM INFORM 2. Absorp. Area Required (sq. ft.	Pressurized Distribu 21 🖾 Mound 22 🗍 In-Ground Pre MATION: 3. Absorp. Area Proposed (sq. ft.)	30 [ssure 4. Loading Rate (Gals/day/sq. ft.)		te 6. Sy	41 42 43	[] Ho 2 [] Pit 3 [] Va 3 [] Va 4 1 Ev. 7 E	Iding Ta Privy ult Privy 7. Final C Elevation	nk Grade
Non-Pressurized Distrib 11 Seepage Bed 12 Seepage Trench 13 Seepage Pit 14 System-In-Fill VI. ABSORPTION SY I. Gallons Per Day 753	STEM INFORM	Pressurized Distribu 21 ⊠ Mound 22 ☐ In-Ground Pre AATION: 3. Absorp. Area Proposed (sq. ft.) 6 5 0 Total Gallons Tanks	30 [ssure 4. Loading Rate	Specify Ty 5. Perc. Ra (Min./inch	te 6. Sy	41 42 43 ystem E	[] Ho 2 [] Pit 3 [] Va 3 [] Va 4 1 Ev. 7 E	Iding Ta Privy ult Privy 7. Final (nk Grade Fee Expe
Non-Pressurized Distrib 11 Seepage Bed 12 Seepage Trench 13 Seepage Pit 14 System-In-Fill VI. ABSORPTION SY I. Gallons Per Day 753 VII. TANK INFORMATION	STEM INFORM 2. Absorp. Area Required (sq. ft. (030 Capacity in gallons New Existir	Pressurized Distribut 21 \boxtimes Mound 22 \square In-Ground Pre 1ATION: 3. Absorp. Area Proposed (sq. ft.) 650 Total Gallons Tanks 3	30 [ssure 4. Loading Rate (Gals/day/sq. ft.) <i>1. 2</i> Manufacturer's Na <i>Meade</i>	Specify Ty 5. Perc. Ra (Min./inch ame Prefat Concre	te 6. Sy	41 42 43 ystem E	Ho Pit Pit Va Va Iev. 7 Feet Fiber-	lding Ta Privy ult Privy 7. Final (Elevatior しつうエ	nk Grade Fee Expe
Non-Pressurized Distrib 11 Seepage Bed 12 Seepage Trench 13 Seepage Pit 14 System-In-Fill VI. ABSORPTION SY I. Gallons Per Day 753 VII. TANK INFORMATION eptic Tank or Holding Tank If Pump Tank /Siphon Chamb	STEM INFORM 2. Absorp. Area Required (sq. ft. (030) Capacity in gallons New Existin Tanks Tank 	Pressurized Distribut 21 \boxtimes Mound 22 \square In-Ground Present ATION: 3. Absorp. Area Proposed (sq. ft.) 650 Total Gallons 5 2000 / 2000 /	30 [ssure 4. Loading Rate (Gals/day/sq. ft.) 1. 2 Manufacturer's Na	Specify Ty 5. Perc. Ra (Min./inch ame Prefat Concre	te 6. Sy	41 42 43 ystem E	Ho Pit Pit Va Va Iev. 7 Feet Fiber-	lding Ta Privy ult Privy 7. Final (Elevatior しつうエ	nk Grado Fee Expo
Non-Pressurized Distrib 11 Seepage Bed 12 Seepage Trench 13 Seepage Pit 14 System-In-Fill VI. ABSORPTION SY I. Gallons Per Day 753 VII. TANK INFORMATION eptic Tank or Holding Tank If Pump Tank /Siphon Chamb /III. RESPONSIBILITY	STEM INFORM 2. Absorp. Area Required (sq. ft. (030 Capacity in gallons New Existin Tanks Tank 	Pressurized Distribut 21 \boxtimes Mound 22 \square In-Ground Present 1ATION: 3. Absorp. Area Proposed (sq. ft.) 650 Total # of Gallons Tanks 2000 / 2000 /	30 [ssure 4. Loading Rate (Gals/day/sq. ft.) 1. 2 Manufacturer's Na Meade Meade	Specify Ty 5. Perc. Ra (Min./inch ame Prefat Concre	te 6 . Sy b. Site Con- structed	41 42 43 ystem E Steel	lev. Feet	Iding Ta Privy ult Privy 7. Final (Elevation 7. OJ 1 Plastic	nk Grade Fee
Non-Pressurized Distrib 11 Seepage Bed 12 Seepage Trench 13 Seepage Pit 14 System-In-Fill VI. ABSORPTION SY I. Gallons Per Day 753 VII. TANK INFORMATION eptic Tank or Holding Tank If Pump Tank /Siphon Chamb /III. RESPONSIBILITY I, the undersigned, as	STEM INFORM 2. Absorp. Area Required (sq. ft. (030) Capacity in gallons New Existin Tanks Tank 	Pressurized Distribut 21 \boxtimes Mound 22 \square In-Ground Present 1ATION: 3. Absorp. Area Proposed (sq. ft.) 650 Total g Gallons Tanks 2000 / 2000 / D 2000 / D 2000 / Ity for installation	30 [ssure 4. Loading Rate (Gals/day/sq. ft.) 1. 2 Manufacturer's Na Meade Meade	Specify Ty 5. Perc. Ra (Min./inch ame Prefat Concre	te 6. Sy b. Site Con- structed	41 42 43 ystem E Steel	lev. 7 Feet 7 Fiber- glass	Iding Ta Privy ult Privy . Final C Elevation ひろエ Plastic	nk Grade Fee Expe
Non-Pressurized Distrib 11 Seepage Bed 12 Seepage Trench 13 Seepage Pit 14 System-In-Fill VI. ABSORPTION SY 1. Gallons Per Day 753 VII. TANK INFORMATION Septic Tank or Holding Tank Sighton Chamb VIII. RESPONSIBILITY	STEM INFORM 2. Absorp. Area Required (sq. ft. (030) Capacity in gallons New Existin Tanks Tank 	Pressurized Distribut 21 X Mound 22 In-Ground Present ATION: 3. Absorp. Area Proposed (sq. ft.) 6 5 0 Total # of Gallons Tanks 2000 / 2000 / 12000 / 11ty for installation Proposed (sq. ft.) 6 5 0 1 X Notesting the stallation Meter's Signature: Notesting the stallation	30 [ssure 4. Loading Rate (Gals/day/sq. ft.) 1. 2 Manufacturer's Na Meade Meade of the onsite sewage amps) MP/MPf	Specify Ty 5. Perc. Ra (Min./inch ame Prefat Concre	te 6. Sy b. Site Con- structed	41 42 43 ystem E 5teel 5teel he atta	lev. 7 Feet 7 Fiber- glass	Iding Ta Privy ult Privy 7. Final C Elevation ひろエ Plastic lans.	nk Grade Fee Apr
Non-Pressurized Distrib	STEM INFORM 2. Absorp. Area Required (sq. ft. (030) Capacity in gallons New Existin Tanks Tank 	Pressurized Distribut 21 \boxtimes Mound 22 \square In-Ground Present 1ATION: 3. Absorp. Area Proposed (sq. ft.) 6.50 Total # of Gallons Tanks 2000 / 2000 / 12000 / 11ty for installation mber's Signature: DioSi	30 [ssure 4. Loading Rate (Gals/day/sq. ft.) 1. 2 Manufacturer's Na Meade Meade Meade Meade 33	Specify Ty 5. Perc. Ra (Min./inch ame Prefat Concre	te 6. Sy Site Con- structed Down on tl Bus Con- Con- Con- Con- Structed	41 42 43 ystem E 5teel 5teel he atta	lev. 7 Feet 7 Fiber- glass	Iding Ta Privy ult Privy . Final C Elevation ひろエ Plastic	nk Grade Fee Apr
Non-Pressurized Distrib	STEM INFORM 2. Absorp. Area Required (sq. ft. (030) Capacity in gallons New Existin Tanks Tank 	Pressurized Distribut 21 \boxtimes Mound 22 \square In-Ground Present 1ATION: 3. Absorp. Area Proposed (sq. ft.) 6.50 Total # of Gallons Tanks 2000 / 2000 / 10 2000 / 10 2	30 [ssure 4. Loading Rate (Gals/day/sq. ft.) 1. 2 Manufacturer's Na Meade Meade Meade Meade 33	Specify Ty 5. Perc. Ra (Min./inch ame Prefat Concre	te 6. Sy Site Con- structed Down on tl Bus Con- Con- Con- Con- Structed	41 42 43 ystem E 5teel 5teel he atta	lev. 7 Feet 7 Fiber- glass	Iding Ta Privy ult Privy 7. Final C Elevation ひろエ Plastic lans.	Fee Expe Apr
Non-Pressurized Distribution 11 Seepage Bed 12 Seepage Trench 13 Seepage Pit 14 System-In-Fill VI. ABSORPTION SY 1. Gallons Per Day 753 VII. TANK INFORMATION Steptic Tank or Holding Tank Inf Pump Tank /Siphon Chambe VIII. RESPONSIBILITY I, the undersigned, ar Plumber's Name: (Print) Steven R C Plumber's Address (Street, City (0807 CTY IX. COUNTY / DEPAR	STEM INFORM 2. Absorp. Area Required (sq. ft. (030) Capacity in gallons New Existin Tanks Tank 	Pressurized Distribut 21 \boxtimes Mound 22 \square In-Ground Present ATION: 3. Absorp. Area Proposed (sq. ft.) 6.50 Total # of Gallons Tanks 2000 / 2000 / 2000 / 2000 / 2000 / Difference Charger Mer's Signature: Charg	30 [ssure 4. Loading Rate (Gals/day/sq. ft.) 1. 2 Manufacturer's Na Meade Meade of the onsite sewage amps) MP/MPF 23 M 23 mKee U	Specify Ty 5. Perc. Ra (Min./inch ame Prefat Concre	te 6. Sy Site Con- structed Down on tl Bus 6. 6. 5. 6. 5. 6. 5. 6. 5. 6. 5. 6. 5. 6. 5. 6. 5. 6. 5. 6. 5. 6. 5. 6. 6. 6. 6. 6. 6. 6. 6. 6. 6	41 42 43 ystem E Steel Steel he atta iness Pho	lev. 7 Freet 6 Fiber- glass	Iding Ta Privy ult Privy 7. Final C Elevation ひろエ Plastic lans.	Fee Fee Apr
Non-Pressurized Distribution 11 \square Seepage Bed 12 \square Seepage Trench 13 \square Seepage Pit 14 \square System-In-Fill VI. ABSORPTION SY I. Gallons Per Day 753 VII. TANK INFORMATION eptic Tank or Holding Tank INFORMATION eptic Tank or Holding Tank INFORMATION I, the undersigned, as Plumber's Name: (Print) 54euen RC Plumber's Address (Street, City (0807 CTY X. COUNTY / DEPAR \square Disap	STEM INFORM 2. Absorp. Area Required (sq. ft. (030) Capacity in gallons New Existin Tanks Tank - 2000 Y STATEMENT ssume responsibi Cos by State/Zip Code): (10) Y RTMENT USE (proved proved r Given Initial rse Determination APPROVAL / R Fr(SPET EY STRUCTO	Pressurized Distribut 21 \boxtimes Mound 22 \square In-Ground Present ATION: 3. Absorp. Area Proposed (sq. ft.) 6.50 Total # of Gallons Tanks 2000 / 2000 / 2000 / 2000 / Distribute: Diose Constant For Distribute: Diose Constant Permit Fee Constant Permit Permit Fee Constant Permit Permit Fee Constant Permit Permit Permit Fee Constant Permit Perm	30 [ssure 4. Loading Rate (Gals/day/sq. ft.) 1. 2 Manufacturer's Na Meade Mead	Specify Ty 5. Perc. Ra (Min./inch ame Prefat Concre \boxed{X} \boxed{x} e system sho 3SW No.: 75^{-} 25^{-} Date Issued $5^{-}7^{-}96$ AVIK AVIX	te 6. Sy Site Con- structed U D Swn on tl Bus G 5.97 Issuing A Rufa	41 42 43 ystem E Steel 9 Steel 10 10 10 10 10 10 10 10 10 10 10 10 10	lev. 7 Freet 6 Fiber- glass	Iding Ta Privy ult Privy 7. Final C Elevation 1032 Plastic Plastic	Fee Expe Apr

PROPERTY OWNER: COUNTY Page 1 of 5 Madigan Refrigeration PROPERTYLOCATION Dane GOVT. LOT NW 1/4 NW 1/4,5 28 T 8 LOT # | BLOCK # | SUBD. NAME OR CSM # N.R 9 E (or)-₩-B¹⁰⁴ 0 CITY VILLAGE FOWN NEAREST ROAD CTY Huy K Westport · 6103 Level Scale 1"= 40" ۵ 2" 80' Ω 20' 40' 0 B102 8101 1 Provide Constant Station 161 Conditionally. B M= 100.0 rear Bottom of LABOR & HUMAN RELATIONS ι_ό 9 OF INDUSTRY, DEP Siding DIVISION OF SAFETY AND BUILDINGS q ۴ unlan * 136 65 nes Shed SEE CORRESPONDENCE Worehouse 414¹7 on slab ¥ 171 = xisting 3 T Prop Orain 2 **596-01195** Switch \succ Volve . ب \mathcal{O} ¥″ 5 C H 40 INSPECT PLUMBER MUST TO VERIFY EHISTING TANKS STRUCTURAL LONDITION, BAFFES, ER 3"Force REPAIR OR REPLACE IF NECESSARY Driveway RECEIVED Do Tu Sta MAY - 6 1996 SAFETY & BLOGS. DIV.




Plan View Of Mound Using A Bed For The Absorption Area



Modigun Refrigeration Existing TANK NW/4 NWS Sec 28 PLIMP CHAMPER CROSS SECTION AND SPECIFICATIONS 1AG1 4 05 5 Westport. -VENT CAP Y'C.T. VENT PIPE APPROVED LOCKING WEATHER PROOF MANHOLE COVEF. JUNCTION BOX ≥ 25' FROM DOOR. 12"MILL WINDOW OR FRESH AIR INTAKE GRADE -4" MIN. 18" MIN. ¥ CONDUIT - 18"MIN. PROVIDE INLET AIRTIGHT SEALT ORCEV APPROVED JOINTS APPROVED JOINT W/C.I. PIPE W/C.I. PIPE EXTENDING 3' ALARM EXTENDING 3' ONTO SOLID SOLL ONTO SOLID SOIL **GEPT. OF INDUSTRY, LABOR & HUMAN RELATIONS DIVISION OF SAFETY AND BUILDINGS** NO V amen ELEV. 91. 3 FT. D OFF SEE CORRESPONDENCE CONCRETE BLOCK-* RISER EXIT PERMITTED ONLY IF TANK MANUFACTURER HAS SUCH APPROVAL SPECIFICATIONS SEPTIC E DOSE 3 ____ PER DAY MANUFACTURER:_ Meade NUMBER OF DOSES: ____ TANKS TANK SIZE: 2000 ____ GALLONS DOSE VOLUME INCLUDING BACKFLOW: 31316 GALLONS MANUFACTURER: 5. J Electro ALARM MODEL NUMBER: 101 CAPACITIES: A = 24 INCHES OR 940 GALLONS SWITCH TYPE: MERCURY R= 4 INCHES OR 156.8 GALLONS Exist C = 8 INCHES OR 313 1 GGALLONS MANUFACTURER: 6001ds PUMP MODEL NUMBER: WPO 3E (COMPARE to WEUSIIL) 15 INCHES OR 589.6 GALLONS SWITCH TYPE: MCCURY NOTE: PUMP AND ALARM ARE TO BE INSTALLED ON SEPARATE CIRCUITS 42.2 MINIMUM DISCHARGE RATE_ GPM $\frac{2.5}{87}$ FEST96-01195 + MINIMUM NETWORK SUPPLY PRESSURE + 150 FEET OF FORCE MAIN X 158 FT 100 FE FRICTION FACTOR. 187 FE (39.2 pallon pa" 15.37 FEET TOTAL DYNAMIC HEAD = INTERNAL DIMENSIONS OF DANK: LENGTH _____; WIDTH ____; LIQUID DEPTH ____ Det LICENSE NUMBER: MPRS 3375 DATE: 5-3-96 U SIGNED:


Performance Curves

Submersible Effluent Pumps



GOULDS PUMPS, INC.

SENECA FALLS NEW YORK BHAB



W, S,

Wisconsin E Labor and H Division of S	Juman Re	lations	•••-	AND SITE in accord with						Page	e_[0)f
Attach com	plete site	e plan on	paper not less that	n 8 1/2 x 11 inch	es in siz	e. Pian mu	st include, but	COUNT	DANC			
			zontal reference p d location and dist			% of slope,	scale or	PARCE	:L1.D.#			
		•	ON-PLEASE PR			ON			NED BY	4-24	DATE	/
PROPERT		- • •	M					0/11 1/4 5	D T D	,N,R 9	7 54	or) K
PROPERT	YOWNER	<u>Madiq</u> i S MAILING	ADDRESS	Refrigera	tion	LOT #	LOT 1/4 1/4 BLOCK # S		<u> </u>	<u>, N, N / / / / / / / / / / / / / / / / /</u>	<u> </u>	
S30 CITY, STA		4. Hu	ZIP CODE	PHONE NUMBER	}				NEARES	T ROAD		
	Naka	WI	53597)estport		Hwy		- /	
[] New (Constructi	on Us		Number of bedro					existing buildi	ng		
K Replac		* ·	Public or con									
Code deriv	ved daily i	flow <u>757</u>	<u>⊃_gpd ±</u> <u>²5</u> bed, ft ² _/50	Reco	ommende	d design loa	iding rate $-\frac{9}{2}$	bed, gpd/i	it ² <u>, 5</u> tre	nch, gpd.	/ft ²	
-Absorption	+área req	uired <u>787</u>	$\frac{75}{2}$ bed, ft ² $\frac{750}{2}$ ace elevation(s) $\frac{9}{2}$	20_trench, ft ² 29, 5 - 99	Maximu 7, 7	m design loa ff	ading rate <u>· Y</u> (as referred to si	bed, gpd/ te plan bench	tte <u>, s</u> tre mark)	nch, gpd	/₶≏	
Additional	design / s	site conside	erations <u>Moc</u>	unds - (m	ay s	א <u>ד</u> דווכ יאד	to 2 cells					
Parent ma	terial	Loess	over Glas	ial Till		Floo	d plain elevation	, if applicable	NA	f	.	
S = Suitab U = Unsui	le for sys	tem		MOUND DAS DU			URE AT-GR/	NDE 図U	SYSTEM IN F		iolding □S	
0 - 011301		Jotein		SOIL DES			PORT		···	l		
Boring #	Horizon	Depth	Dominant Color			Texture	Structure	Consisten	ce Boundary	Roots	GP	
		in.	Munsell	Qu. Sz. Cont	. Color		Gr. Sz. Sh.				Bed	11
10/	1	0-5	104 × 3/2	NONE		sil	Zfgr	mfr	95	Zrf	,5	
Ground	2	5-18	104R 14			sicl	Zmabk	MFE	CS	irt	.4	
elev. 9 <u>9,5</u> ft.	3	18-42	104 × 4/6			sc/	Qmsbk	mfr	95	-	.4	
Depth to	4	42-47	104 R 6/2	None		(067) 51	2fpl	mfr	95	-	NP	
limiting factor	5		104R 6/6	104r 6/2 7154r 5/8 =	Rmd	SI	lfsbk	myfre	-	-	n	/ P
factor $\frac{47''}{}$,				6"		RECEI	ED		
I	Remark	<u> </u>	Standing (beound u	Jarei			A	PR 21	005	!	:
Boring #	nemark	.s				l i					1	
								Healt	h Departr 9 3	nmen Rent		
102	- 1	0-3	104R 3/2	Norre	2	sil	2fyr	mfr	95	21		
Ground	2	3-27	104R 14			sicl	Zmabk	mfr	CS	-	.4	
elev. 9 <u>9, 7</u> ft.	3	27-34	104× 4/6	(sc/	Zmsbk	. mfr	<u>as</u>		.4	1
Depth to	4	34-40	104R 6/6	Non	'C	sl	lfsbt	myfr	cs	-	.4	_
limiting	5	40-41		SAMEB	-107	sl	Ifsok	myfr		-	N	17
factor		· ·										
I	Remark	(s:	Stewding G	Round 4	later	0	40 "					
CST Name:-	-Please	Inina -	even R	Ceosby	M	einholi	E Exca	ne: Dala Tre	608	-831	-8103	3
					l	-	5359	. 1				
Address:	807 1	yy H	WY A I	Dankal	Leo L	e)I	0051	/		CST Nun		


____ SOIL DESCRIPTION REPORT

g #	Horizon	Depth	Dominant Color	Mottles	Texture	Structure Gr. Sz. Sh.	Consistence	Boundary	Roots.	GP	
, 		in.	Munsell	Qu. Sz. Cont. Color		Gr. 52. 511.				Bed	Tren
	· 1	0-6	104R 3/2	NONP	sil	Zfyr	mfr	45	Zuf	دا 1	.6
t I	Z	6-16	104 R 314	, ,	sil	Zfabk	mfr	CS	ixf	s،	<u>م</u> .
ft.	3	16:28	104 R 4/4	none	Sic/	Zmabk	mfi	ĊS	-	.4	د ، ا
to	4	28-32	104× 44	10 4 R WZ 7. Syr 5/8 2md	si'e/	ZCAbk	mfz	cs	-	NT	2
,"	6	32-40	104 R 4/6	10412 612 7.542 5/8 2md	Sc/	Zmsbt	mfr	as	~	NV.	
r <u>-</u>	6	40-44		104R6/7 7.54F5/p Zmd	S(Ifsbk	myfr		-	N	P
	Remark	s:	·								
g #											
	1	0-8	104 x 3/2	NONE	5.1	Zfqr	mfe	as	Zuf	,5	, Ç
	2	8-15	1041R .14		si (Zfabk	mfr	CS	luf	,5	. (
d ft.	3	1530	104R 414	None	sic(Zmabk	mfr	<u>cs</u>	-	.4	, s
to	4	30-41		Same 13:103	Sic/	Zcabt	mfr	CS	-	N	12
g	5	41-54	104e 4/6	45	scl	2msbk	mfr	-		N	P
0″											
•	Remark	s:	· · · · · · · · · · · · · · · · · · ·								
g #											

elev. _____ft.


.

Depth to limiting factor



.

,



ATTACHMENT B

SEPTIC SYSTEM ABANDONMENT INFORMATION

Refer to the following pages for additional information on the project site.



Healthy people and places

Janel Heinrich, MPH, MA, Director

Environmental Health Division 2300 S Park St, Rm 2010 Madison, WI 53713 608 242-6515 Well & Septic 608 243-0330 Lic. Establishments 608 242-6435 fax www.publichealthmdc.com

Dear Septic System Owner

RE: Proper abandonment of your private septic system

Dane County is required to maintain an inventory of private sewage systems in Dane County. If a private sewage system is no longer in operation for any reason, Wisconsin Administrative Code SPS 383.33 requires that the system be permanently abandoned. In order to remove your system from the County inventory and stop the triennial reporting requirement, you must have your sewage system properly abandoned and submit a private sewage system abandonment form (located on the back of this letter) to our office at the address given above.

In order to properly abandon a private sewage system, SPS. 383.33 requires the following:

- 1. Disconnect all piping to the tanks and/or pits,
- 2. Seal all disconnected piping to the tanks and pits as per SPS. 382,
- 3. Pump and dispose of the contents from all tanks and pits by a WI licensed septic pumper, and
- 4. Remove or destroy all the tanks and fill the pits with clean native soil, gravel, or inert solid material. Proper destruction of a tank left in place includes removal of the cover, breaking the bottom and collapsing the side walls of the tank.

These abandonment requirements apply to all systems that are no longer in use, including but not limited to those that serve a structure that has been connected to public sewer, serve a structure that no longer exists on the property, or those that are no longer functional and are replaced by a new private sewage system. A final private septic maintenance fee will be assessed on a property in the year that the system is abandoned. No fee will be assessed in the years following abandonment unless a new septic system is installed as a replacement. If a system is not abandoned, it will be maintained in the County inventory, subject to reporting requirements, and assessed private septic maintenance fees.

Your assistance in this matter is greatly appreciated. If you have any questions, please feel free to contact me at 242-6515.

Sincerely,

John Hausbeck Environmental Health Services Supervisor



PRIVATE SEWAGE SYSTEM ABANDONMENT FORM

To the system owner: It is important for you to verify the legal description, including the parcel number, with your tax records. Please indicate any changes or corrections on this form.

Ow	vner(s):				Office Refe	erence
Ma	ailing Address:				POWTS #:	:
IVIC					DB ID:	
Le	gal Description:	¼ of	1/4 of Section	, in	(M	lunicipality)
Su	bdivision:		Lot:	Parcel No:		
Pro	operty Address					
pro tha	ease note: The person ovide the information at does not include a	n to complete a Il of that inform	all of the statement ation cannot be ac	ts in the certificat		
	e private sewage systematics of the sewage systematics of the sewage systematics of the sewage systematics of the several s			on ———	(Date)	
1)	The septic tank(s) w	oro pumpod by li	iconcod contic numr	Nor:	(Date)	□ No
1)	The septic tank(s) w	ere pumped by n	icensed septic pump	er.		
2)	The septic tank(s) w	 Completely removed Destroyed in place 				
3)	If the septic tank(s) we that the following act	 Tank cover removed Tank bottom broken Tank sidewalls collapsed Remaining pit filled 				
4)	All piping leading to	and from the sep	otic(s) was disconne	cted and sealed:	□ Yes	□ No
Co	mments:					
Lic	ensed Septic Pumper	: Printed Name		Signature		License #
Se	ptic Pumper Business			-		LICENSE #
PC	WTS Abandoner:					
		Printed Name		Signature		License #
PC	WTS Abandoner Bus	iness Name:				

Return this form to Public Health Madison & Dane County, 2300 S Park St, Rm 2010, Madison WI 53713 or email to <u>privatewellseptic@publichealthmdc.com</u>. Please call (608) 242-6515 if you have questions.

Page Intentionally Left Blank

ATTACHMENT C

EROSION CONTROL PLAN INFORMATION

Refer to the following pages for additional information on the project site.

Building Demolition County Hwy K & M Town of Westport

Project Narrative:

Dane County is seeking bids for demolition of the structures at the intersection of County Road M and County Road K in the Town of Westport. This project is being performed in advance of intersection reconstruction by the County Highway Department. The Public Works Division is seeking an Erosion Control Permit in advance of bid opening to facilitate the project

A majority of the site is currently asphalt, gravel or buildings with less than $\frac{1}{2}$ acre of existing vegetation to be disturbed.

Upon completion of building demolition the foundations will be backfilled with stone and existing asphalt removed. Any disturbed soil areas will be restored with a temporary cover and mulched.

Prior to the start of demolition activities 12" diameter silt sock will be installed along the perimeter of existing asphalt adjacent to existing vegetation to further limit sediment loss.

Stone tracking pads will be installed at points of egress, though little exposed soil is anticipated and potential tracking is expected to be minimal.

We anticipate the project to be complete within 2 months from start.



Building Demolition Hwys. K & M - Westport, Sec.28 Site Map

450


300

0 75 150






Building Demolition Hwys. K & M - Westport Limits of Disturbance 125,000 sq. ft.







Zone AE 1 (EL 853) 828 808080

and I

North Shore Bay Dr

Zone AE

Feet

ZongAE

Bridge

STUDY



Building Demolition Hwys. K & M - Westport, Sec.28 Parcels & WDNR Wetlands





Building Demolition Hwys. K & M - Westport, Sec.28 Contours

0 20 40


80

120





Building Demolition Hwys. K & M - Westport, Sec.28 Drainage Area - 4.75ac.







Building Demolition Hwys. K & M - Westport, Sec.28 Drainage Area - 4.75ac. Project Area - 2.8ac. Existing Impervious - 2.5ac Disturbed Soil - 0.3 ac





Existing Buildings & Asphalt To Be Removed. Gravel as Final Cover




Pg.7



Building Demolition Hwys. K & M - Westport, Sec.28 Erosion Control Measures

180' - Silt Sock - 12" dia.



Existing Vegetation to Remain Undisturbed

Existing Buildings & Asphalt To Be Removed. Gravel as Final Cover

170'

Tracking Pad

760'-Silt Sock - 12" dia.

Temporary Seeding

Fracting Pad

Pg.8



Building Demolition Hwys. K & M - Westport, Sec.28 USLE Flow Path







YEAR 1

Soil Loss & Sediment Discharge Calculation Tool

for use on Construction Sites in the State of Wisconsin



WDNR Version 2.0 (06-29-2017)

Developer:	Dane Coun	ity														
Project:	Building D	emolition -	Hwys K 8	k M												
Date:	06/28/22															
County:	Dane	-												Version 1.0		
Activity (1)	Begin Date (2)	End Date (3)		Annual R Factor (5)		Soil Erodibility K Factor (7)	Slope (%) (8)	Slope Length (ft) (9)	LS Factor (10)	Land Cover C Factor (11)	Soil loss A (tons/acre) (12)	SDF (13)	Sediment Control Practice (14)	Sediment Discharge (t/ac) (15)		
Bare Ground	09/02/22	11/15/22	17.5%	150	Sandy Loam 💂	0.28	2.2%	90	0.21	1.00	1.5	0.953	Vegetative Buffer -	0.9		
Land Control of Contro																
Seed with Mulch or Er	11/15/22	05/15/23	16.0%	150	Sandy Loam	0.28	2.2%	90	0.21	0.10	0.1	0.953	-	0.1		
End 🚽	05/15/23						2.2%	90	0.21			0.000		0.0		
-							2.2%	90	0.21			0.000	-	0.0		
-							2.2%	0				0.000	-	0.0		
]															
-							0.0%	0				0.000		0.0		
													i			

Notes:

See Help Page for further descriptions of variables and items in drop-down boxes.

The last land disturbing activity on each sheet must be 'End'. This is either 12 months from the start of construction or final stabilization.

For periods of construction that exceed 12 months, please demonstrate that 5 tons/acre/year is not exceeded in any given 12 month period.

Recommended Permanent Seeding Dates:

4/1-5/15 and Thaw-6/30 8/7-8/29 Turf, introduced grasses and legumes Native Grasses, forbs, and legumes NOTE: THIS TOOL ONLY ADDRESSED SOIL EROSION DUE TO SHEET FLOW. MEASURES TO CONTROL CHANNEL EROSION MAY ALSO BE REQUIRED TO MEET SEDIMENT DISCHARGE REQUIREMENTS.

TOTAL

% Reduction

Required


1.0

NONE

TOTAL

1.7

Designed By:	R. Shore
Date	6/28/2022



Y PUBLIC WORKS	322012				
RING DIVISION	DR'N BY: N/A	C'KD BY: SC			

SCALE:

N/A

COUNTY PROPERTY - JUNCTION OF COUNTY HIGHWAYS K & M TOWN OF WESTPORT, WISCONSIN

FIGURE 1 SITE PLAN