



DANE COUNTY DEPARTMENT of PUBLIC WORKS, HIGHWAY and TRANSPORTATION

County Executive
Kathleen M. Falk

1919 Alliant Energy Center Way ♦ Madison, Wisconsin 53713
Phone: (608) 266-4018 ♦ Fax: (608) 267-1533

Commissioner / Director
Gerald J. Mandli

April 10, 2008

ATTENTION ALL REQUEST FOR BID (RFB) HOLDERS

RFB NO. 108055 - ADDENDUM NO. 1

LANDFILL GAS MANAGEMENT SYSTEM REPAIRS

BIDS DUE: Monday, April 14, 2008, 2:00 PM. DUE DATE AND TIME ARE NOT CHANGED BY THIS ADDENDUM.

This Addendum is issued to modify, explain or clarify the original Request for Bid (RFB) and is hereby made a part of the RFB. It is bidder's responsibility to make this Addendum available to all subcontractors before bids are due.

Acknowledge receipt of this Addendum on the Bid Form.

PLEASE MAKE THE FOLLOWING CHANGES:

1. General information

- A. The quantities stated in the Construction Documents are approximations. The purpose of listing these quantities is to provide fair bidding for all contractors. If actual Work performed exceeds the quantities stated in the Construction Documents, change orders would be issued. Change orders will have to be approved by RMT before the contractor may proceed with the additional Work.
- B. This job is not a white sheet job, as it does not meet Davis-Bacon wage rate thresholds.
- C. Areas that are disturbed as a result of this Work must have erosion mats installed and must be re-seeded. Owner will provide seed.
- D. RMT will coordinate all Work with Mark Schwarting, facility manager of the Bridges Golf Course; Mark's mobile number is 249-9212.
- E. There are irrigation lines within the golf course limits. Contact Mark before digging, and he will mark these lines. It is solely the Contractor's liability for any damage that occurs during excavation and filling.
- F. During excavation, pile waste, topsoil, clay, and other individual substrates into separate stockpiles. If excavation is taking place within the golf course limits, stockpiles must be outside golf course limits. When filling excavated areas, replace materials in the layers that they were excavated, and compact clay to existing conditions (refer to Scope of Services and Specifications). RMT will perform compaction tests. Contractor is

- responsible for additional work and compaction tests due to failures on initial compaction tests.
- G. When adjusting wellheads and vault boxes, contractor may reuse materials, subject to approval by RMT. It is also acceptable to raise vault boxes instead of lowering well heads. The covers of the vault boxes must be flush with the ground so that mowers and other golf course equipment can drive over them without causing damage. To accomplish this, contractor may fill in areas around the wellheads with topsoil as long as resulting surface water drainage is approved by RMT.
 - H. The Owner is supplying the flare shroud, and John Gwinn of Vulcan Flare & Mechanical Services is fabricating it for the County.

If any additional information about this Addendum is needed, please call John Welch, 608/516-4154.

Enclosures:
N/A