RFB NO. 315022



CONSTRUCTION DOCUMENTS PROJECT MANUAL

DANE COUNTY DEPARTMENT OF PUBLIC WORKS, HIGHWAY AND TRANSPORTATION

PUBLIC WORKS ENGINEERING DIVISION 1919 ALLIANT ENERGY CENTER WAY MADISON, WISCONSIN 53713

REQUEST FOR BIDS NO. 315022 BADGER PRAIRIE HEALTH CARE CENTER - REGRADING AND PRAIRIE RESTORATION BADGER PRAIRIE HEALTH CARE CENTER 1100 EAST VERONA AVE. VERONA, WISCONSIN

Due Date / Time: THURSDAY, MARCH 26, 2015 / 2:00 P.M.

Location: PUBLIC WORKS OFFICE

Performance / Payment Bond: 100% OF CONTRACT AMOUNT

Bid Deposit: 5% OF BID AMOUNT

FOR INFORMATION ON THIS REQUEST FOR BIDS, PLEASE CONTACT:

J. ERIC URTES, AIA - PROJECT MANAGER TELEPHONE NO.: 608/266-4798 FAX NO.: 608/267-1533 E-MAIL: <u>urtes.eric@countyofdane.com</u>

DOCUMENT INDEX FOR RFB NO. 315022

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

Cover Page Documents Index Advertisement for Bids (Legal Notice) Instructions to Bidders Bid Form Fair Labor Practices Certification Best Value Contracting Application Sample Public Works Contract Sample Bid Bond Sample Performance Bond Sample Performance Bond Sample Payment Bond Equal Benefits Compliance Payment Certification General Conditions of Contract Supplementary Conditions

DIVISION 01 - GENERAL REQUIREMENTS

01 00 00 - Basic Requirements

DIVISION 31 - EARTHWORK

31 05 13 - Earthwork 31 25 13 - Erosion Control

DIVISION 32 – PRAIRIE RESTORATION

32 90 10 - Restoration

32 90 20 - Native Vegetated Mat (NVM)

32 90 30 - Prairie Seeding

DRAWINGS

Plot sheets on 42" x 30" (ARCH E1), paper for correct scale or size.

Sheet 1 - Existing Conditions

Sheet 2 - Grading and Erosion Control Plan

Sheet 3 - Grading/Drainage Improvement Areas

Sheet 4 - Prairie Restoration Plan

Sheet 5 - Details

LEGAL NOTICE

INVITATION TO BID

Dane County Public Works, Highway & Transportation Dept., 1919 Alliant Energy Center Way, Madison, WI 53713, will receive sealed Bids until:

2:00 P.M., THURSDAY, MARCH 26, 2015

REQUEST FOR BIDS NO. 315022 BADGER PRAIRIE HEALTH CARE CENTER - REGRADING AND PRAIRIE RESTORATION

BADGER PRAIRIE HEALTH CARE CENTER 1100 EAST VERONA AVE. CITY OF VERONA, WISCONSIN

Dane County is inviting Bids for soil regrading of existing swales / detention ponds and prairie restoration work at the Badger Prairie Health Care Center in Verona. Only firms with capabilities, experience & expertise with similar projects should obtain this packet & submit Bids.

Request for Bids package may be obtained after **2:00 p.m. on Friday, March 6, 2015** by downloading it from <u>countyofdane.com/pwbids</u>. Please call Eric Urtes, Project Manager, at 608/266-4798, or our office at 608/266-4018, for any questions or additional information.

All Bidders must be a registered vendor with Dane County & pay an annual registration fee & must be pre-qualified as a Best Value Contractor before award of Contract. Complete Vendor Registration Form at <u>danepurchasing.com/registration</u> or obtain one by calling 608/266-4131.Complete Pre-qualification Application for Contractors at countyofdane.com/pwht/BVC Application.aspx or obtain one by calling 608/266-4018.

A site tour for Bidders will be held Monday, March 16, 2015 at 10:00 a.m. at Badger Prairie Health Care Center; Bidders are strongly encouraged to attend this tour.

PUBLISH: MARCH 5 & MARCH 12, 2015 - WISCONSIN STATE JOURNAL MARCH 5 & MARCH 12, 2015 - THE DAILY REPORTER

INSTRUCTIONS TO BIDDERS

TABLE OF CONTENTS

1. GENERAL
2. DRAWINGS AND SPECIFICATIONS
3. INTERPRETATION
4. QUALIFICATIONS OF BIDDER (CONTRACTOR AND SUBCONTRACTOR) 2
5. BID GUARANTEE
6. WITHDRAWAL OF BIDS
7. CONTRACT FORM
8. CONTRACT INTERESTS BY COUNTY PUBLIC OFFICIALS
9. EMERGING SMALL BUSINESS PROVISIONS
10. METHOD OF AWARD - RESERVATIONS
11. SECURITY FOR PERFORMANCE AND PAYMENTS
12. TAXES
13. SUBMISSION OF BIDS
14. SUBCONTRACTOR LISTING
15. ALTERNATE BIDS
16. INFORMATIONAL BIDS
17. UNIT PRICES
18. COMMENCEMENT AND COMPLETION
19. SPECIAL HAZARDS COVERAGE
FORM A
FORM B
FORM C
FORM D

1. GENERAL

- A. Before submitting Bid, bidder shall thoroughly examine all Construction Documents. Successful Bidder shall be required to provide all the Work that is shown on Drawings, set forth in Specifications, or reasonably implied as necessary to complete Contract for this project. Construction Documents may be obtained at <u>www.countyofdane.com/pwbids</u>. Bidder is responsible to check back regularly at the web site for Addenda and shall acknowledge all Addenda on Bid Form.
- B. Bidder shall visit site to become acquainted with adjacent areas, means of approach to site, conditions of actual site and facilities for delivering, storing, placing, and handling of materials and equipment. Only firms with capabilities, experience & expertise with similar projects should obtain the Construction Documents and submit Bids.
- C. A pre-bid Site Tour is scheduled on Monday, March 16, 2015 at 10:00 AM at Badger Prairie Health Care Center, 1100 East Verona Avenue, Verona. Attendance by all bidders is optional, however bidders and subcontractors are strongly encouraged to attend.
- D. Failure to visit site or failure to examine any and all Construction Documents will in no way relieve successful Bidder from necessity of furnishing any necessary materials or equipment, or performing any work, that may be required to complete the Work in accordance with Drawings and Specifications. Neglect of above requirements will not be accepted as reason for delay in the Work or additional compensation.
- E. Written inquires regarding intent of Construction Documents shall be directed to the Public Works Project Manager. Bidders shall bring questions, discrepancies, omissions, conflicts or

doubt as to meaning of any part of Construction Documents to the attention of the Public Works Project Manager at least five (5) days before due date for Bids. Failure to request clarification of interpretation of Construction Documents shall not relieve Bidders of their responsibilities to perform Work.

2. DRAWINGS AND SPECIFICATIONS

- A. Drawings and Specifications that form part of this Contract, as stated in Article 1 of General Conditions of Contact, are enumerated in Document Index of these Construction Documents.
- B. Complete sets of Drawings and Specifications for all trades will be issued to all Bidders, irrespective of category of work to be bid on, in order that all Bidders may be familiar with work of other trades as they affect their bid.

3. INTERPRETATION

- A. No verbal explanation or instructions will be given in regard to meaning of Drawings or Specifications before Bid Due Date. Bidders shall bring inadequacies, omissions or conflicts to Owner or Engineer's attention at least five (5) days before Bid Due Date. Prompt clarification will be available to all bidders by Addendum.
- B. Failure to so request clarification or interpretation of Drawings and Specifications will not relieve successful Bidder of responsibility. Signing of Contract will be considered as implicitly denoting that Contractor has thorough understanding of scope of the Work and comprehension of Construction Documents.
- C. Owner or Engineer will not be responsible for verbal instructions.

4. QUALIFICATIONS OF BIDDER (CONTRACTOR AND SUBCONTRACTOR)

- A. Before award of Contract can be approved, Owner shall be satisfied that Bidder involved meets following requirements:
 - 1. Has completed at least one (1) project of at least fifty percent (50%) of size or value of Division of work being bid and type of work completed is similar to that being bid. If greater magnitude of experience is deemed necessary, other than size or value of work, such requirements will be described in appropriate section of Specifications.
 - 2. Maintains permanent place of business.
 - 3. Can be bonded for terms of proposed Contract.
 - 4. Has record of satisfactorily completing past projects and supplies list of no more than three (3) most recent, similar projects, with architect or engineer's and owner's names, addresses and telephone numbers for each project, submit with Bid. Criteria which will be considered in determining satisfactory completion of projects by bidder will include:
 - a. Completed contracts in accordance with drawings and specifications.
 - b. Diligently pursued execution of work and completed contracts according to established time schedule unless Owner grants extensions.
 - c. Fulfilled guarantee requirements of construction documents.

- d. Is not presently on ineligible list maintained by County's Department of Administration for noncompliance with equal employment opportunities and affirmative action requirements.
- e. Authorized to conduct business in Wisconsin. By submitting Bid, bidder warrants that it has: complied with all necessary requirements to do business in State of Wisconsin; that persons executing contract on its behalf are authorized to do so; and, if corporation, that name and address of bidder's registered agent are as set forth in Contract. Bidder shall notify Owner immediately, in writing, of any change in its registered agent, their address, and bidder's legal status. For partnership, term "registered agent" shall mean general partner.
- B. County's Public Works Project Manager will make such investigations as are deemed necessary to determine ability of bidder to perform the Work, and bidder shall furnish to County's Public Works Project Manager or designee all such information and data for this purpose as County's Public Works Project Manager may request. Owner reserves right to reject Bid if evidence submitted by, or investigation of, bidder fails to satisfy Owner that bidder is responsible and qualified to carry out obligations of Contract and to complete the Work contemplated therein.

5. BID GUARANTEE

- A. Bank certified check, cashier's check or Bid Bond, payable to County in amount not less than five percent (5%) of maximum bid, shall accompany each Bid as guarantee that if Bid is accepted, Bidder will execute and return proposed Contract and Performance and Payment Bonds within ten (10) days after being notified of acceptance of Bid. Company issuing bonds must be licensed to do business in Wisconsin.
- B. Any bid, which is not accompanied by bid guarantee, will be considered "No Bid" and will not be read at Bid Due Date.
- C. If successful Bidder so delivers Contract, Certificate of Insurance, and Performance and Payment Bonds, check will be returned to Bidder. In case Bidder fails to deliver such Contract, insurance, and bond, amount of bid guarantee will be forfeited to County as liquidated damages.
- D. All checks tendered as bid guarantee, except those of three (3) lowest qualified, responsible bidders, will be returned to their makers within three (3) days after Bid Due Date. All such retained checks will be returned immediately upon signing of Contract and Performance and Payment Bonds by successful Bidder.

6. WITHDRAWAL OF BIDS

- A. Bids may be withdrawn by written request received from bidder or authorized representative thereof prior to time fixed for Bid Due Date, without prejudice to right of bidder to file new Bid. Withdrawn Bids will be returned unopened. Negligence on part of bidder in preparing their Bid confers no right for withdrawal of Bid after it has been opened.
- B. No Bid may be withdrawn for period of sixty (60) days after Bid Due Date.
- C. If Bid contains error, omission or mistake, bidder may limit liability to amount of bidder's guarantee by giving written Notice of Intent not to execute Contract to Owner within seventy-two (72) hours of Bid Due Date.

7. CONTRACT FORM

A. Sample copy of contract that successful Bidder will be required to enter into is included in these Construction Documents and bidders are required to familiarize themselves with all conditions contained therein.

8. CONTRACT INTERESTS BY COUNTY PUBLIC OFFICIALS

A. In accordance with Wisconsin Statute 946.13, county official may not bid for or enter into any contract involving receipts or disbursements of more than \$15,000.00 in a year, in which they have private pecuniary interest, direct or indirect if at same time they are authorized to take official action with respect to making of this Contract. Any contract entered into in violation of this Statute is void and County incurs no liability thereon. This subsection does not affect application and enforcement of Wisconsin Statute 946.13 by state prosecutors in criminal courts of this state.

9. EMERGING SMALL BUSINESS PROVISIONS

- A. Emerging Small Business Definition. For purposes of this provision, ESB is defined as:
 - 1. Independent business concern that has been in business minimum of one year;
 - 2. Business located in State of Wisconsin;
 - 3. Business comprised of less than twenty-five (25) employees;
 - 4. Business must not have gross sales in excess of three million dollars (\$3,000,000.00) over past three years; and
 - 5. Business does not have history of failing to complete projects.
- B. Emerging Small Business (ESB) Involvement. Bidder shall make good faith effort to award minimum of ten percent (10%) of the Work to ESBs. Bidder shall submit report to Dane County Contract Compliance Officer within seven (7) days after Bid Due Date demonstrating such efforts. Good faith efforts means significant contact with ESBs for purposes of soliciting bids from them. Failure to make or demonstrate good faith efforts will be grounds for disqualification.
- C. **Emerging Small Business Report.** Emerging Small Business Enterprise Report is to be submitted by Bidder in separate envelope marked "Emerging Small Business Report". This report is due within seven (7) days after Bid Due Date. Bidder who fails to submit Emerging Small Business Report shall be deemed not responsive.
- D. ESB Goal. Goal of this project is ten percent (10%) ESB participation. ESB utilizations are shown as percentage of total Bid. If Bidder meets or exceeds specified goal, Bidder is only required to submit Form A Certification, and Form B Involvement. Goal shall be met if Bidder qualifies as ESB.
- E. **Report Contents.** Following award of Contract, Bidder shall submit copies of executed contracts for all Emerging Small Businesses. Emerging Small Business Report shall consist of these:
 - 1. Form A Certification;

- 2. Form B Involvement;
- 3. Form C Contacts;
- 4. Form D Certification Statement (if appropriate); and
- 5. Supportive documentation (i.e., copies of correspondence, telephone logs, copies of advertisements).
- F. **ESB Listing.** Bidders will solicit bids from ESB listing provided by Dane County.
- G. **ESB Certification.** All contractors, subcontractors and suppliers seeking ESB certification must complete and submit Emerging Small Business Certification Application to Dane County Contract Compliance Program.
- H. **Certification Statement.** If ESB firm has not been certified by County as ESB prior to submittal of this Bid, ESB Report cannot be used to fulfill ESB goal for this project unless firm provides "Form D Certification Statement". Certification statement must be completed and signed by ESB firm.
- I. Questions. Questions concerning Emerging Small Business provisions shall be directed to:

Dane County Contract Compliance Officer City-County Building, Room 421 210 Martin Luther King, Jr. Blvd. Madison, WI 53703 608/266-5623

- J. **Substituting ESBs.** In event of any significant changes in subcontract arrangements or if need arises to substitute ESBs, Bidder shall report such proposed changes to Contract Compliance Officer to making any official changes and request authorization to substitute ESB firm. Bidder further agrees to make every possible effort to replace ESB firm with another qualified ESB firm.
- K. **Good Faith Efforts.** Good faith efforts can be demonstrated by meeting all of these obligations:
 - 1. Selecting portions of the Work to be performed by ESBs in order to increase likelihood of meeting ESB goal including, where appropriate, breaking down Contract into smaller units to facilitate ESB participation.
 - 2. Advertising in general circulation, trade associations and women / minority focus media concerning subcontracting opportunities.
 - 3. Providing written notices to reasonable number of specific ESBs that their interest in Contract was being solicited in sufficient time to allow ESBs to participate effectively.
 - 4. Following up on initial solicitations of interest by contacting ESBs within five (5) working days prior to Bid Due Date to determine with certainty whether ESB were interested, to allow ESBs to prepare bids.
 - 5. Providing interested ESB with adequate information about Drawings, Specifications and requirements of Contract.

- 6. Using services of available minority, women and small business organizations and other organizations that provide assistance in recruitment of MBEs / WBEs / ESBs.
- 7. Negotiating in good faith with interested ESBs, not rejecting ESBs as unqualified without sound reason based on thorough investigation of their capabilities.
- 8. Submitting required project reports and accompanying documents to County's Contract Compliance Officer within twenty-four (24) hours after Bid Due Date.
- L. **Appeals Disqualification of Bid.** Bidder who is disqualified may appeal to Public Works & Transportation Committee and Equal Opportunity Commission.

10. METHOD OF AWARD - RESERVATIONS

- A. Following will be basis of award of Contract, providing cost does not exceed amount of funds then estimated by County as available to finance Contract(s):
 - 1. Lowest dollar amount submitted by qualified responsible bidder on Base Bid for all work comprising project, combined with such additive Owner accepted alternates.
 - 2. Owner reserves right to reject all bids or any bid, to waive any informality in any bid, and to accept any bid that will best serve interests of County.
 - 3. Unit Prices and Informational Bids will not be considered in establishing low bidder.

11. SECURITY FOR PERFORMANCE AND PAYMENTS

- A. Simultaneous with delivery of signed Contract, Bidder shall be required to furnish Performance and Payment Bonds as specified in Article 29 of General Conditions of Contract, "Contract Security". Surety Company shall be licensed to do business in Wisconsin. Performance and Payment Bonds must be dated same date or subsequent to date of Contract. Performance and Payment Bonds must emulate information in Sample Performance and Payment Bonds in Construction Documents.
- B. Provide certified copy of power of attorney from Surety Company showing that agent who signs Bond has power of attorney to sign for Surety Company. Secretary or Assistant Secretary of company must sign this certification, not attorney-in-fact. Certification must bear same or later date as Bond. Power of Attorney must emulate model power of attorney information detailed in Sample Performance and Payment Bonds.
- C. If Bidder is partnership or joint venture, State certified list, providing names of individuals constituting partnership or joint venture must be furnished. Contract itself may be signed by one partner of partnership, or one partner of each firm comprising joint venture, but Performance and Payment Bonds must be signed by all partners.
- D. If Bidder is a corporation, it is necessary that current certified copy of resolution or other official act of directors of corporation be submitted showing that person who signs Contract is authorized to sign contracts for corporation. It is also necessary that corporate seal be affixed to resolution, contract, and performance and payment bonds. If your corporation has no seal, it is required that above documents include statement or notation to effect that corporation has no seal.

12. TAXES

- A. Bidder shall include in Bid, all Sales, Consumer, Use and other similar taxes required by law.
- B. In accordance with Wisconsin Statute 71.80(16)(a),successful nonresident bidder, whether incorporated or not, and not otherwise regularly engaged in business in this state, shall file surety bond with State of Wisconsin Department of Revenue payable to Department of Revenue, to guarantee payment of income taxes, required unemployment compensation contributions, sales and use taxes and income taxes withheld from wages of employees, together with any penalties and interest thereon. Amount of bond shall be three percent (3%) of Contract or subcontract price on all contracts of \$50,000 or more.

13. SUBMISSION OF BIDS

- A. All Bids shall be submitted on standard Bid Form bound herein and only Bids that are made on this Bid Form will be considered. Entire Bid Form and other supporting documents, if any, shall be removed or copied from Construction Documents, filled out, and submitted in manner specified hereinafter. Submit completed Bid Bond with Bid as well.
- B. No bids for any subdivision or any sub-classification of this Work, except as indicated, will be accepted. Any conditional Bid, amendment to Bid Form or appended item thereto, or inclusion of any correspondence, written or printed matter, or details of any nature other than that specifically called for, which would alter any essential provision of Construction Documents, or require consideration of unsolicited material or data in determining award of Contract, will disqualify Bid. Telecommunication alterations to Bid will not be accepted.
- C. Bidders must submit single Bid for all the Work.
- D. Bid amounts shall be inserted in words and in figures in spaces provided on Bid Form; in case of conflict, written word amounts will govern.
- E. Addenda issued after Bid Letting shall become part of Construction Documents. Bidders shall acknowledge receipt of such addenda in appropriate space provided on Bid Form. Bid may be rejected if receipt of any particular addendum applicable to award of Contract has not been acknowledged on Bid Form.
- F. Bids shall be signed, placed in envelope, sealed and delivered before due time to place designated in Invitation to Bid, and identified with project name, bid number, location, category of work being bid upon, Bid Due Date, name and address of bidder.
- G. Bidder shall be responsible for sealed Bid being delivered to place designated for Bid Due Date on or before date and time specified. Bids received after time of closing will be rejected and returned to bidder unopened.
- H. Bid will be considered invalid and will be rejected if bidder has not signed it.
- I. Faxed Bids will not be accepted.
- J. Bidder's organization shall submit completed with Bid, Fair Labor Practices Certification form, included in these Construction Documents.

14. SUBCONTRACTOR LISTING

A. Bidders shall be required to submit list of major subcontractors for General Construction, Plumbing, HVAC, and Electrical work proposed for this project to include committed prices for each subcontractor. List shall be placed in separate sealed envelope that must be clearly identified as "Major Subcontractor List", for named project and name of Bidder submitting it. County must receive envelope no later than date by which successful Bidder is required to submit his or her signed Contract, as established in Construction Documents.

15. ALTERNATE BIDS

- A. Bidder shall carefully read requests for Alternate Bids, and thoroughly examine Drawings and Specifications to determine extent various changes and conditions will affect Bid.
- B. Space is provided in Bid Form for requested Alternate Bids. Failure to submit bid for any requested Alternate Bids may result in rejection of entire Bid.
- C. Bidder shall state amount to be added / subtracted to Base Bid for providing alternates, including all incidentals, omissions, additions, and adjustments as may be necessary or required by such changes. If there is no difference in price, Bidder shall state, "No Change".
- D. Descriptions of requested Alternate Bids are as set forth in Construction Documents.

16. INFORMATIONAL BIDS

- A. Bidder shall state amount that is included in Base Bid for all equipment, materials and labor required to complete the Work described. Informational bids are amounts requested for accounting purposes and for allocation of funds only. It is not intended to omit any of the Work described or related items from this project.
- B. Description of requested Informational Bids, if any, is as set forth in Construction Documents.

17. UNIT PRICES

- A. Provide unit prices where requested on Bid Form. Unit prices will include all costs for materials, labor, insurance, taxes, overhead and profit necessary to perform specified work. Estimated quantities are approximate only. Payment will be based upon actual quantities placed, provided or installed. Failure to provide requested unit prices may result in rejection of entire Bid.
- B. Owner reserves right to accept or reject any unit prices as given in Bid.
- C. Bidder shall refer to Bid Form and applicable specification section to determine basis of unit measure and detailed information related to each unit price item requested.

18. COMMENCEMENT AND COMPLETION

A. Successful Bidder shall commence work when schedule and weather permit, but no later than stated in Bid Form. Contractor shall pursue the Work regularly and continuously at reasonable rate to insure completion of the Work within time stated in Bid.

B. Should it be found impossible to complete the Work on or before time specified for completion, written request may be submitted for extension of time setting forth reasons believed to justify granting of such request. Refer to Article 20 of General Conditions of Contract, titled "Time for Completion".

19. SPECIAL HAZARDS COVERAGE

A. Not Applicable.

FORM A

DANE COUNTY EMERGING SMALL BUSINESS REPORT - CERTIFICATION

In accordance with General Conditions of Contract, submit this Emerging Small Business Report within seven (7) days after Bid Due Date.

PROJECT NAME:	
BID NO.:	BID DUE DATE:
BIDDER INFORMATION	
COMPANY NAME:	
ADDRESS:	
TELEPHONE NO.:	
CONTACT PERSON:	

FORM B

DANE COUNTY EMERGING SMALL BUSINESS REPORT - INVOLVEMENT	(Copy this Form as necessa	Page of ary to provide complete information)
COMPANY NAME:		
PROJECT NAME:	BID NO.:	
ESB NAME:	CONTACT PERSON:	
ADDRESS:	PHONE NO.:	
CITY:	STATE:	ZIP:
Indicate percentage of financial commitment to this ESB:	<u>%</u> Amount: <u>\$</u>	
ESB NAME:	CONTACT PERSON:	
ADDRESS:	PHONE NO.:	
CITY:	STATE:	ZIP:
Indicate percentage of financial commitment to this ESB:	<u>%</u> Amount: <u>\$</u>	
ESB NAME:	CONTACT PERSON:	
ADDRESS:	PHONE NO.:	
CITY:	STATE:	ZIP:
Indicate percentage of financial commitment to this ESB:	<u>%</u> Amount: \$	

FORM C

DANE COUNTY EMERGING SMALL BUSINESS REPORT - CONTACTS		Page of (Copy this Form as necessary to provide complete information)			
COMPANY NAME:					
PROJECT NAME:			BID	0 NO.:	
ESB FIRM NAME CONTACTED	DATE	PERSON CONTACTED	DID ESB BID?	DID YOU ACCEPT BID?	REASON FOR REJECTION
1)					
2)					
3)					
4)					
5)					
6)					
7)					

FORM D

DANE COUNTY EMERGING SMALL BUSINESS REPORT - CERTIFICATION STATEMENT

I,	, <u> </u>	of
ivane	The	
		_ certify to best of my knowledge and
Company		
belief that this business meets Emerging Small Bus	siness det	finition as indicated in Article 9 and
that information contained in this Emerging Small	Business	Report is true and correct.

Bidder's Signature

Date

BID FORM

BID NO. 315022 PROJECT: BADGER PRAIRIE HEALTH CARE CENTER – REGRADING AND PRAIRIE RESTORATION

BADGER PRAIRIE HEALTH CARE CENTER 1100 EAST VERONA AVE. CITY OF VERONA, WISCONSIN

TO: DANE COUNTY DEPARTMENT OF PUBLIC WORKS, HIGHWAY & TRANSPORTATION PROJECT MANAGER 1919 ALLIANT ENERGY CENTER WAY MADISON, WISCONSIN 53713

BASE BID - LUMP SUM:

Dane County is inviting Bids for soil regrading of existing swales / detention ponds and prairie restoration work including a three year management plan at the Badger Prairie Health Care Center in Verona. Only firms with capabilities, experience & expertise with similar projects should obtain this packet & submit Bids.

The undersigned, having examined the site where the Work is to be executed and having become familiar with local conditions affecting the cost of the Work and having carefully examined the Drawings and Specifications, all other Construction Documents and Addenda thereto prepared by Dane County Department of Public Works, Highway & Transportation hereby agrees to provide all labor, materials, equipment, prairie restoration (including a 3-year prairie management program to promote establishment of the prairie vegetation) and services necessary for the complete and satisfactory execution of the entire Work, as specified in the Construction Documents, for the Base Bid stipulated sum of:

and	/100	Dollars	

Written Price

\$

Numeric Price

LUMP SUM ALLOWANCE FOR:

Interpretive Signage for Prairie Restoration along roadway. Include a lump sum allowance in the Base Bid of four thousand dollars (\$4000). The allowance will be used for interpretive signs for public education of prairie restoration practices (including prairie burns) and information about volunteering for prairie seed harvesting with the Dane County Parks Department.

Four Thousand	an	nd <u>00</u> /100) Dollars
Written Price			
\$4,000			

Numeric Price

UNIT PRICE 1: REMOVAL & REPLACEMENT OF UNSUITABLE SOIL

Add price for the removal of unsuitable soil (quantity and necessity to be confirmed by Engineer) encountered during grading or restoration that is determined not to be capable of sustaining prairie plantings. Removed soil is to be replaced by soil with a chemistry capable of establishing prairie. Unsuitable Soil Removal & Replacement with soil (approved by Project Manager).

@_\$	/cu. yd.
and	/100 Dollars
@	/cu. yd.
and	/100 Dollars
	and @ <u>\$</u>

UNIT PRICE 2: ADDITIONAL TYPE B NATIVE VEGETATED MAT

Add price for additional Type B Native Vegetated Mat required beyond the 0.35 acres to be included in Base Bid.

@	\$ <u>/sq</u> .	yd.
	-	-

and /100 Dollars

Written Price

Receipt of the following addenda and inclusion of their provisions in this Bid is hereby acknowledged:

Addendum No(s). _____ through _____

Dated _____

Dane County, Badger Prairie Health Care Center must have this project completed by June 22, 2015. Assuming this Work can be started by April 27, 2015 (and the County can authorize the purchase of Native Vegetated Mat and seed by April 17) what dates can you commence and complete this job?

::

_____ Completion Date: ______ (final, not substantial) I hereby certify that all statements herein are made on behalf of:

(Name of Corporation, Partnership or Person submitting Bid)		
Select one of the following: 1. A corporation organized and existing under the laws of the State of		, or
2. A partnership consisting of		, or
3. A person conducting business as		?
Of the City, Village, or Town of	of the State of	

I have examined and carefully prepared this Bid from the associated Construction Documents and have checked the same in detail before submitting this Bid; that I have full authority to make such statements and submit this Bid in (its) (their) (my) behalf; and that the said statements are true and correct. In signing this Bid, we also certify that we have not, either directly or indirectly, entered into any agreement or participated in any collusion or otherwise taken any action in restraint of free competition; that no attempt has been made to induce any other person or firm to submit or not to submit a Bid; that this Bid has been independently arrived at without collusion with any other bidder, competitor, or potential competitor; that this Bid has not been knowingly disclosed prior to the Bids Due Date to another bidder or competitor; that the above statement is accurate under penalty of perjury.

The undersigned further agrees to honor the Base Bid and the Alternate Bid(s) for 60 days from date of Award of Contract.

SIGNATURE: (Bid is invalid without signature)	
Print Name: D	Date:
Title:	
Address:	
Telephone No.: Fax No.:	
Email Address:	
Contact Person:	

THIS PAGE IS FOR BIDDERS' REFERENCE AND NEED NOT BE SUBMITTED WITH BID FORM.

BID CHECK LIST: These items must be included with Bid: □ Bid Form □ Bid Bond □ Project Experience / Reference Summary

□ Fair Labor Practices Certification

BIDDERS SHOULD BE AWARE OF THE FOLLOWING:

DANE COUNTY VENDOR REGISTRATION PROGRAM

Any person bidding on any County contract must be registered with the Dane County Purchasing Division & pay an annual registration fee. A contract will not be awarded to an unregistered vendor. Obtain a *Vendor Registration Form* by calling 608/266-4131 or complete a new form or renewal online at:

www.danepurchasing.com/registration

DANE COUNTY BEST VALUE CONTRACTING PRE-QUALIFICATION

Contractors must be pre-qualified as a Best Value Contractor with the Dane County Public Works Engineering Division before the award of contract. Obtain a *Best Value Contracting Application* by calling 608/266-4018 or complete one online at: www.countyofdane.com/pwht/BVC_Application.aspx

EQUAL BENEFITS REQUIREMENT

By submitting a Bid, the contractor acknowledges that a condition of this contract is to provide equal benefits as required by Dane County Code of Ordinances Chapter 25.016. Contractor shall provide equal benefits as required by that Ordinance to all required employees during the term of the contract. Equal Benefits Compliance Payment Certification shall be submitted with final pay request. For more information: www.danepurchasing.com/partner_benefit.aspx



DANE COUNTY DEPARTMENT of PUBLIC WORKS, HIGHWAY and TRANSPORTATION

County Executive Joseph T. Parisi 1919 Alliant Energy Center Way • Madison, Wisconsin 53713 Phone: (608) 266-4018 • FAX: (608) 267-1533 Commissioner / Director Gerald J. Mandli

BEST VALUE CONTRACTING APPLICATION

CONTRACTORS / LICENSURE APPLICANTS

The Dane County Department of Public Works requires all contractors to be pre-qualified as a best value contractor with the County prior to being awarded a contract. In addition, the County pre-qualifies potential contractors and sub-contractors who wish to work on County contracts. Subcontractors must become pre-qualified ten (10) days prior to commencing work under any Dane County Public Works Contract. Potential subcontractors are urged to become pre-qualified as early as possible. This document shall be completed, properly executed, along with the necessary attachments and additional information that the County requires for the protection and welfare of the public in the performance of a County contract.

Contractors or subcontractors of any tier who attain pre-qualification status will retain that status for a period of two (2) years from the date of qualification. Contractors shall notify the Dane County Department of Public Works, Highway & Transportation within fifteen (15) days of any changes to its business or operations that are relevant to the pre-qualification application. Failure to do so could result in suspension, revocation of the contractor's pre-qualification, debarment from County contracts for up to three (3) years and / or other sanctions available under the law.

No contracts will be awarded for construction work performed on Dane County projects unless the contractor is currently approved as a Wisconsin Trade Trainer or has applied for approval as an Apprenticeship Trade Trainer to the Wisconsin Department of Workforce Development and agrees to an acceptable apprenticeship program. If you are not currently approved as a Wisconsin Trade Trainer, or have not applied for approval as an Apprenticeship Trade Trainer, please contact the Department of Workforce Development - Bureau of Apprenticeship Standards at 608/266-3133 or visit their web site at: <u>dwd.wisconsin.gov/apprenticeship/</u>.

EXEMPTIONS

- Contractors who employ less than five (5) apprenticeable trade workers are not required to pre-qualify.
- Contractors performing work that does not apply to an apprenticeable trade, as outlined in Appendix A.
- The contractor / subcontractor provides sufficient documentation to demonstrate one or more of the following:
 - o apprentices are not available in a specific geographic area;
 - the applicable apprenticeship program is unsuitable or unavailable; or
 - there is a documented depression of the local construction market which prevents compliance.

SEC.	PROOF OF RESPONSIBILITY	CHECK IF APPLICABLE
1	Does your firm possesses all technical qualifications and resources,	Yes: No:
	including equipment, personnel and financial resources, necessary to	
	perform the work required for any project or obtain the same through	
	the use of responsible, pre-qualified subcontractors?	
2	Will your firm possess all valid, effective licenses, registrations or	Yes: No:
	certificates required by federal, state, county, or local law, which are	
	necessary for the type of work to be performed including, but not	
	limited to, those for any type of trade work or specialty work?	
3	Will your firm meet all bonding requirements as required by applicable	Yes: No:
	law or contract specifications?	
4	Will your firm meet all insurance requirements as required by	Yes: No:
	applicable law or specifications, including general liability insurance,	
	workers compensation insurance and unemployment insurance	
	requirements?	
5	Will your firm maintain a substance abuse policy for employees hired	Yes: No:
	for public works contracts that comply with Wis. Stats. Sec. 103.503?	
6	Does your firm acknowledge that it must pay all craft employees on	Yes: No:
	public works projects the wage rates and benefits required under	
	Section 66.0903 of the Wisconsin Statutes?	
7	Will your firm fully abide by the equal opportunity and affirmative	Yes: No:
	action requirements of all applicable laws, including County	
	ordinances?	
8	In the past three (3) years, has your firm had control or has another	Yes: No:
	corporation, partnership or other business entity operating in the	If Yes, attach details.
	construction industry controlled it? If so, please attach a statement	
	explaining the nature of the firm relationship?	
9	In the past three (3) years, has your firm had any type of business,	Yes: No:
-	contracting or trade license, certification or registration revoked or	If Yes, attach details.
	suspended?	
10	In the past three (3) years, has your firm been debarred by any federal,	Yes: No:
	state or local government agency?	If Yes, attach details.
11	In the past three (3) years, has your firm defaulted or failed to complete	Yes: No:
	any contract?	If Yes, attach details.
12	In the past three (3) years, has your firm committed a willful violation	Yes: No:
	of federal, state or local government safety laws as determined by a	If Yes, attach details.
	final decision of a court or government agency authority.	
13	In the past three (3) years, has your firm been in violation of any law	Yes: No:
	relating to your contracting business where the penalty for such	If Yes, attach details.
	violation resulted in the imposition of a penalty greater than \$10,000?	
14	Is your firm Executive Order 108 precertified with the State of	Yes: No:
	Wisconsin?	
15	Is your firm an active Wisconsin Trade Trainer as determined by the	Yes: No:
	Wisconsin Bureau of Apprenticeship Standards?	
16	Is your firm exempt from being pre-qualified with Dane County?	Yes: No:
10	y min enempt from being pro quantos with Dune county?	If Yes, attach reason for exemption.
17	Does your firm acknowledge that in doing work under any County	Yes: No:
	Public Works Contract, it will be required to use as subcontractors only	
	those contractors that are also pre-qualified with the County or become	
	so ten days prior to commencing work?	
18	Contractor has been in business less than one year?	Yes: No:
19	Is your firm a first time Contractor requesting a one time exemption,	Yes: No:
-/	but, intend to comply on all future contracts and are taking steps	
	typical of a "good faith" effort?	
20	Not applicable. My firm does not intend to work on Best Value	Yes: No:
20	Contracts. Note: Best Value Contracting is required to bid on most	
	Public Works Contracts (if unclear, please call Jan Neitzel Knox 608-	
	266-4029).	
	200 -1 029).	

SIGNATURE SECTION

Your firm's Officer, or the individual who would sign a bid and / or contract documents must sign this document.

I do hereby certify that all statements herein contained are true and correct to the best of my knowledge:

Signature

Date

Printed or Typed Name and Title

NAME AND ADDRESS OF CONTRACTOR			
Name of Firm:			
Address:			
City, State, Zip:			
Telephone Number:			
Fax Number:			
E-mail Address:			

REMEMBER!

Return all to forms and attachments, or questions to:

JAN NEITZEL KNOX EMAIL: NEITZEL-KNOX@COUNTYOFDANE.COM OFFICE: (608)266-4029, FAX: (608)267-1533

DANE COUNTY DEPARTMENT OF PUBLIC WORKS, HGHWAY & TRANSPORTATION 1919 ALLIANT ENERGY CENTER WAY MADISON, WI 53713

APPENDIX A

APPRENTICEABLE TRADES

Bricklayer Carpenter Cement Mason (Concrete Finisher) Cement Mason (Heavy Highway) Construction Craft Laborer Data Communications Installer Electrician Elevator Mechanic / Technician Environmental Systems Technician / HVAC Service Technician / HVAC Install & Service Glazier Heavy Equipment Operator / Operating Engineer Insulation Worker (Heat & Frost) Iron Worker (Assembler, Metal Buildings) Painter / Decorator Plasterer Plumber Roofer / Waterproofer Sheet Metal Worker Sprinkler Fitter Steamfitter (Service & Refrigeration) Taper & Finisher Telecommunications (Voice, Data & Video) Installer / Technician Tile Setter

COUNTY OF DANE

PUBLIC WORKS CONSTRUCTION CONTRACT

Contract No. _____ Bid No. _315022

Authority: 2014 RES -_____

WITNESSETH:

WHEREAS, COUNTY, whose address is c/o Assistant Public Works Director, 1919 Alliant Energy Center Way, Madison, WI 53713, desires to have CONTRACTOR provide soil regrading of existing swales / detention ponds and prairie restoration work including three year management plan at the Badger Prairie Health Care Center at 1100 East Verona Avenue, Verona, WI ("the Project"); and

WHEREAS,	CONTRACT	COR, whose address is	
			is able and willing to construct the Project,
. / .	\ /. A.		

in accordance with the Construction Documents;

NOW, THEREFORE, in consideration of the above premises and the mutual covenants of the parties hereinafter set forth, the receipt and sufficiency of which is acknowledged by each party for itself, COUNTY and CONTRACTOR do agree as follows:

2. COUNTY agrees to pay the CONTRACTOR in current funds for the performance of the Contract subject to additions and deductions, as provided in the General Conditions of Contract and to make payments on account thereof as provided in Article entitled, "Payments to Contractor" of the General Conditions of Contract.

3. During the term of this Contract, CONTRACTOR agrees to take affirmative action to ensure equal employment opportunities. The CONTRACTOR agrees in accordance with Wisconsin Statute 111.321 and Chapter 19 of the Dane County Code of Ordinances not to discriminate on the basis of age, race, ethnicity, religion, color, gender, disability, marital status, sexual orientation, national origin, cultural differences, ancestry, physical appearance, arrest record or conviction record, military participation or membership in the national guard, state defense force or any other reserve component of the military forces of the United States, or political beliefs.

Such equal opportunity shall include, but not be limited to, the following: employment, upgrading, demotion, transfer, recruitment, advertising, layoff, termination, training, rates of pay, and any other form of compensation. CONTRACTOR agrees to post in conspicuous places, available to all employees and applicants for employment, notices setting forth the provisions of this paragraph.

4. CONTRACTOR shall file an Affirmative Action Plan with the Dane County Contract Compliance Officer in accord with Chapter 19 of the Dane County Code of Ordinances. CONTRACTOR must file such plan within fifteen (15) days of the effective date of this Contract. During the term of this Contract CONTRACTOR shall also provide copies of all announcements of employment opportunities to COUNTY'S Contract Compliance Office, and shall report annually the number of persons, by race, ethnicity, gender, and disability status, which apply for employment and, similarly classified, the number hired and number rejected.

5. During the term of this Contract, all solicitations for employment placed on CONTRACTOR'S behalf shall include a statement to the effect that CONTRACTOR is an "Equal Opportunity Employer."

6. CONTRACTOR agrees to comply with provisions of Chapter 25.016 of the Dane County Code of Ordinances, which pertains to domestic partnership benefits.

7. CONTRACTOR agrees to furnish all information and reports required by COUNTY'S Contract Compliance Officer as the same relate to affirmative action and nondiscrimination, which may include any books, records, or accounts deemed appropriate to determine compliance with Chapter 19, Dane County Code of Ordinances, and the provisions of this Contract.

8. CONTRACTOR agrees that all persons/employed by CONTRACTOR or any subcontractor shall be paid no less than the minimum wage established under Chapter 40, Subchapter II, Dane County Code of Ordinances. CONTRACTOR agrees to abide by and comply with the provisions of Chapter 40, Subchapter II of the Dane County Code of Ordinances, and said Subchapter is fully incorporated herein by reference.

9. This Contract is intended to be a Contract solely between the parties hereto and for their benefit only. No part of this Contract shall be construed to add to, supplement, amend, abridge or repeal existing rights, benefits or privileges of any third party or parties including, but not limited to, employees of either of the parties.

10. The entire agreement of the parties is contained herein and this Contract supersedes any and all oral agreements and negotiations between the parties relating to the subject matter hereof. The parties expressly agree that the express terms of this Contract shall not be amended in any fashion except in writing, executed by both parties.

11. CONTRACTOR must be pre-qualified as a Best Value Contractor with Dane County Public Works Engineering Division before award of Contract. Subcontractors must be pre-qualified ten (10) days prior to commencing Work under this Contract.

IN WITNESS WHEREOF, COUNTY and CONTRACTOR, by their respective authorized agents, have caused this Contract and its Schedules to be executed, effective as of the date by which all parties hereto have affixed their respective signatures, as indicated below.

* * * * * * *

FOR CONTRACTOR:

Signature	Date
Printed or Typed Name and Title	
Signature	Date
Printed or Typed Name and Title NOTE: If CONTRACTOR is a corporation, Secretary should atte Regulations, unincorporated entities are required to provide either Employer Number in order to receive payment for services render This Contract is not valid or effectual for any purpose until appro- designated below, and no work is authorized until the CONTRAC proceed by COUNTY'S Assistant Public Works Director.	ved by the appropriate authority
FOR COUNTY:	
Joseph T. Parisi, County Executive	Date

Scott McDonell, County Clerk

Date

THE AMERICAN INSTITUTE OF ARCHITECTS



AIA Document A310

Bid Bond

Bond No.

KNOW ALL MEN BY THESE PRESENTS, that we

(Here insert full name and address or legal title of Contractor)

as Principal, hereinafter called the Principal, and

(Here insert full name and address or legal title of Surety)

a corporation duly organized under the laws of the State of WI as Surety, hereinafter called the Surety, are held and firmly bound unto

(Here insert full name and address or legal title of Owner)

as Obligee, hereinafter called Obligee, in the sum of () Percent of total amount bid Dollars (\$ Percent of attached bid). For the payment of which sum well and truly to be made, the said Principal and the said Surety, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the Principal has submitted a bid for Project No.: (Here insert full name, address, and description of project)

NOW, THEREFORE, if the Obligee shall accept the bid of the Principal and the Principal shall enter into a Contract with the Obligee in accordance with the terms of such bid, and give such bond or bonds as may be specified in the bidding or Contract Documents with good and sufficient surety for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof, or in the event of the failure of the Principal to enter such Contract and give such bond or bonds, if the Principal shall pay to the Obligee the difference not to exceed the penalty hereof between the amount specified in said bid and such larger amount for which the Obligee may in good faith contract with another party to perform the Work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect.

Signed and sealed this	day of	, 20 .
	(P	Principal) (Seal)
(Witness)	T	Title)
	(S	Surety) (Seal)
(Witness)		ATTORNEY-IN-FACT

AIA DOCUMENT A310 *BID BOND * AIA * Feb. 1970 ED. * THE AMERICAN INSTITUTE OF ARCHITECTS 1735 N.Y. AVE, N.W., WASHINGTON, D.C. 20006

THE AMERICAN INSTITUTE OF ARCHITECTS



Bond No.

AIA Document A312

Performance Bond

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

CONTRACTOR (Name and Address):

SURETY (Name and Principal Place of Business):

OWNER (Name and Address):				
CONSTRUCTION CONTRACT Date: Amount: \$ Description (Name and Location):				
BOND Date (Not earlier than Construction Contract Date): Amount: \$ Modifications to this Bond:	[]None	[] See Page 3		
CONTRACTOR AS PRINCIPAL COMPANY: (Corporate Seal)	SURETY COMPANY:	(Corporate Seal)		
Signature: Name and Title:	Signature: Name and Title:	Attorney-in-Fact		
(Any additional signatures appear on page 3)				
FOR INFORMATION ONLY-Name, Address and Telepho AGENT OR BROKER:	ne OWNER'S REPRESENTAT Engineer or other party):	TIVE (Architect,		

1. The Contractor and the Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors, and assigns to the Owner for the performance of the Construction Contract, which is incorporated herein by reference.

2. If the Contractor performs the Construction Contract, the Surety and the Contractor shall have no obligation under this Bond, except to participate in conferences as provided in Subparagraph 3.1.

3. If there is no Owner Default, the Surety's obligation under this Bond shall arise after:

3.1 The Owner has notified the Contractor and the Surety at its address described in Paragraph 10 below that the Owner is considering declaring a Contractor Default and has requested and attempted to arrange a conference with the Contractor and the Surety to be held not later than fifteen days after receipt of such notice to discuss methods of performing the Construction Contract. If the Owner, the Contractor and the Surety agree, the Contractor shall be allowed a reasonable time to perform the Construction Contract, but such an agreement shall not waive the Owner's right, if any, subsequently to declare a Contractor Default; and

3.2 The Owner has declared a Contractor Default and formally terminated the Contractor's right to complete the contract. Such Contractor Default shall not be declared earlier than twenty days after the Contractor and the Surety have received notice as provided in Subparagraph 3.1; and

3.3 The Owner has agreed to pay the Balance of the Contract Price to the Surety in accordance with the terms of the Construction Contract or to a contractor selected to perform the Construction Contract in accordance with the terms of the contract with the Owner.

4. When the Owner has satisfied the conditions of Paragraph 3, the Surety shall promptly and at the Surety's expense take one of the following actions:

4.1 Arrange for the Contractor, with consent of the Owner, to perform and complete the Construction Contract; or

4.2 Undertake to perform and complete the Construction Contract itself, through its agents or through independent contractors; or

4.3 Obtain bids or negotiated proposals from qualified contractors acceptable to the Owner for a contract for performance and completion of the Construction Contract, arrange for a contract to be prepared for execution by the Owner and the contractor selected with the Owner's concurrence, to be secured with performance and payment bonds executed by a qualified surety equivalent to the bonds issued on the Construction Contract, and pay to the Owner the amount of damages as described in Paragraph 6 in excess of the Balance of the Contract Price incurred by the Owner resulting from the Contractor's default; or

4.4 Waive its rights to perform and complete, arrange for completion, or obtain a new contractor and with reasonable promptness under the circumstances: **1.** After investigation, determine the amount for

which it may be liable to the Owner and, as soon as practicable after the amount is determined, tender payment therefor to the Owner; or **2.** Deny liability in whole or in part and notify the Owner citing reasons therefor.

5. If the Surety does not proceed as provided in Paragraph 4 with reasonable promptness, the Surety shall be deemed to be in default on this Bond fifteen days after receipt of an additional written notice from the Owner to the Surety demanding that the Surety perform its obligations under this Bond, and the Owner shall be entitled to enforce any remedy available to the Owner. If the Surety proceeds as provided in Subparagraph 4.4, and the Owner refuses the payment tendered or the Surety has denied liability, in whole or in part, without further notice the Owner shall be entitled to enforce any remedy available to the Owner.

6. After the Owner has terminated the Contractor's right to complete the Construction Contract, and if the Surety elects to act under Subparagraph 4.1, 4.2, or 4.3 above, then the responsibilities of the Surety to the Owner shall not be greater than those of the Contractor under the Construction Contract, and the responsibilities of the Owner to the Surety shall not be greater than those of the Owner under the Construction Contract. To the limit of the amount of this Bond, but subject to commitment by the Owner of the Balance of the Contract Price to mitigation of costs and damages on the Construction for:

6.1 The responsibilities of the Contractor for correction of defective work and completion of the Construction Contract;

6.2 Additional legal, design professional and delay costs resulting from the Contractor's Default, and resulting from the actions or failure to act of the Surety under Paragraph 4; and

6.3 Liquidated damages, or if no liquidated damages are specified in the Construction Contract, actual damages caused by delayed performance or non-performance of the Contractor.

7. The Surety shall not be liable to the Owner or others for obligations of the Contractor that are unrelated to the Construction Contract, and the Balance of the Contract Price shall not be reduced or set off on account of any such unrelated obligations. No right of action shall accrue on this Bond to any person or entity other than the Owner or its heirs, executors, administrators, or successors.

8. The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.

9. Any proceeding, legal or equitable, under this Bond may be instituted in any court of competent jurisdiction in the location in which the work or part of the work is located and shall be instituted within two years after Contractor Default or within two years after the Contractor ceased working or within two years after the Surety refuses or fails to perform its obligations under this Bond, whichever occurs first. If the provisions of this Paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.

10. Notice to the Surety, the Owner or the Contractor shall be mailed or delivered to the address shown on the signature page.

11. When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted here from and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. The intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

12 DEFINITIONS

12.1 Balance of the Contract Price: The total amount payable by the Owner to the Contractor under the Construction Contract after all proper adjustments have been made, including allowance to the Contractor of any amounts received or to be received by the Owner in settlement of insurance or other


claims for damages to which the Contractor is entitled, reduced by all valid and proper payments made to or on behalf of the Contractor under the Construction Contract.

12.2 Construction Contract: The agreement between the Owner and the Contractor identified on the signature page, including all Contract Documents and changes thereto.

12.3 Contractor Default: Failure of the Contractor, which has neither been remedied nor waived, to perform or otherwise to comply with the terms of the Construction Contract.

12.4 Owner Default: Failure of the Owner, which has neither been remedied nor waived, to pay the Contractor as required by the Construction Contract or to perform and complete or comply with the other terms thereof.

MODIFICATIONS TO THIS BOND ARE AS FOLLOWS:



(Space is provided below for additional signatures of added parties, other than those appearing on the cover page.)

CONTRACTOR AS PRINCIPAL Company: (Corporate Seal) SURETY Company:

(Corporate Seal)

Signature: <u>Name and Title:</u> Address: Signature: _____ Name and Title: Address:

THE AMERICAN INSTITUTE OF ARCHITECTS



Bond No.

AIA Document A312

Payment Bond

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

CONTRACTOR (Name and Address):

SURETY (Name and Principal Place of Business):

OWNER (Name and Address):				
CONSTRUCTION CONTRACT Date: Amount: \$ Description (Name and Location):				
BOND Date (Not earlier than Construction Contract Date): Amount: \$ Modifications to this Bond:	[]None	[] See Page 6		
CONTRACTOR AS PRINCIPAL COMPANY: (Corporate Seal)	SURETY COMPANY:	(Corporate Seal)		
Signature: Name and Title:	Signature: Name and Title:	Attorney-in-Fact		
(Any additional signatures appear on page 6)				
FOR INFORMATION ONLY-Name, Address and Telepho AGENT OR BROKER:	ne OWNER'S REPRESENTAT Engineer or other party):	ΠVE (Architect,		

1. The Contractor and the Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors, and assigns to the Owner to pay for labor, materials and equipment furnished for use in the performance of the Construction Contract, which is incorporated herein by reference.

2. With respect to the Owner, this obligation shall be null and void if the Contractor:

2.1 Promptly makes payment, directly, or indirectly, for all sums due Claimants, and

2.2 Defends, indemnifies and holds harmless the Owner from claims, demands, liens or suits by any person or entity whose claim, demand, lien or suit is for the payment for labor, materials, or equipment furnished for use in the performance of the Construction Contract, provided the Owner has promptly notified the Contractor and the Surety (at the address described in Paragraph 12) of any claims, demands, liens, or suits and tendered defense of such claims, demands, liens or suits to the Contractor and the Surety, and provided there is no Owner Default.

3. With respect to Claimants, this obligation shall be null and void if the Contractor promptly makes payment, directly or indirectly, for all sums due.

4. The Surety shall have no obligation to Claimants under this Bond until:

4.1 Claimants who are employed by or have a direct contract with the Contractor have given notice to the Surety (at the address described in Paragraph 12) and sent a copy, or notice thereof, to the Owner, stating that a claim is being made under this Bond and, with substantial accuracy, the amount of the claim.

4.2 Claimants who do not have a direct contract with the Contractor:

 Have furnished written notice to the Contractor and sent a copy, or notice thereof, to the Owner, within 90 days after having last performed labor or last furnished materials or equipment included in the claim stating, with substantial accuracy, the amount of the claim and the name of the party to whom the materials were furnished or supplied or for whom the labor was done or performed; and
 Have either received a rejection in whole or in part from the Contractor, or not received within 30 days of furnishing the above notice any communication from the Contractor by which the Contractor has indicated the claim will be paid directly or indirectly; and

3. Not having been paid within the above 30 days, have sent a written notice to the Surety (at the address described in Paragraph 12) and sent a copy, or notice thereof, to the Owner, stating that a claim is being made under this Bond and enclosing a copy of the previous written notice furnished to the Contractor.

5. If a notice required by Paragraph 4 is given by the Owner to the Contractor or to the Surety, that is sufficient compliance.

6. When the Claimant has satisfied the conditions of Paragraph 4, the Surety shall promptly and at the Surety's expense take the following actions:

6.1 Send an answer to the Claimant, with a copy to the Owner, within 45 days after receipt of the claim, stating the amounts that are undisputed and the basis for challenging any amounts that are disputed.

6.2 Pay or arrange for payment of any undisputed amounts.

7. The Surety's total obligation shall not exceed the amount of this Bond, and the amount of this Bond shall be credited for any payments made in good faith by the Surety.

8. Amounts owed by the Owner to the Contractor under the Construction Contract shall be used for the performance of the Construction Contract and to satisfy claims, if any, under any Construction Performance Bond. By the Contractor furnishing and the Owner accepting this Bond, they agree that all funds earned by the Contractor in the performance of the Construction Contract are dedicated to satisfy obligations of the Contractor and the Surety under this Bond, subject to the Owner's priority to use the funds for the completion of the work.

9. The Surety shall not be liable to the Owner, Claimants or others for obligations of the Contractor that are unrelated to the Construction Contract. The Owner shall not be liable for payment of any costs or expenses of any Claimant under this Bond, and shall have under this Bond no obligations to make payments to, give notices on behalf of, or otherwise have obligations to Claimants under this Bond.

10. The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.

11. No suit or action shall be commenced by a Claimant under this Bond other than in a court of competent jurisdiction in the location in which the work or part of the work is located or after the expiration of one year from the date (1) on which the Claimant gave the notice required by Subparagraph 4.1 or Clause 4.2.3, or (2) on which the last labor or service was performed by anyone or the last materials or equipment were furnished by anyone under the Construction Contract, whichever of (1) or (2) first occurs. If the provisions of this Paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.

12. Notice to the Surety, the Owner or the Contractor shall be mailed or delivered to the address shown on the signature page. Actual receipt of notice by Surety, the Owner or the Contractor, however accomplished, shall be sufficient compliance as of the date received at the address shown on the signature page.

13. When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. The intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

14. Upon request by any person or entity appearing to be a potential beneficiary of this Bond, the Contractor

shall promptly furnish a copy of this Bond or shall permit a copy to be made.

15. DEFINITIONS

15.1 Claimant: An individual or entity having a direct contract with the Contractor or with a subcontractor of the Contractor to furnish labor, materials or equipment for use in the performance of the Contract. The intent of this Bond shall be to include without limitation in the terms "labor, materials or equipment" that part of water, gas, power, light, heat, oil, gasoline, telephone service or rental equipment used in the Construction Contract, architectural and engineering services required for performance of the work of the Contractor and the Contractor's

MODIFICATIONS TO THIS BOND ARE AS FOLLOWS:

subcontractors, and all other items for which a mechanic's lien may be asserted in the jurisdiction where the labor, materials or equipment were furnished.

15.2 Construction Contract: The agreement between the Owner and the Contractor identified on the signature page, including all Contract Documents and changes thereto.

15.3 Owner Default: Failure of the Owner, which has neither been remedied nor waived, to pay the Contractor as required by the Construction Contract or to perform and complete or comply with the other terms thereof.

(Space is provided below for additional signatures of added parties, other than those appearing on the cover page.)

CONTRACTOR AS PRINCIPAL Company: (Corporate Seal) SURETY Company:

(Corporate Seal)

Signature:

Name and Title: Address: Signature:

Name and Title: Address:

EQUAL BENEFITS COMPLIANCE PAYMENT CERTIFICATION

PURPOSE

25.016(8) of the Dane County Ordinance requires that each contractor receiving payment for contracted services must certify that he or she has complied fully with the requirements of Chapter 25.016 "Equal Benefits Requirement" of the Dane County Ordinances. Such certification must be submitted prior to the final payment on the contract.

This form should be included with a copy of the final contract invoice forwarded to your contract representative at Dane County.

CERTIFICATION

I, ___

Printed or Typed Name and Title

_____ certify that

Printed or Typed Name of Contractor

has complied fully with the requirements of Chapter 25.016 of the Dane County Ordinances "Equal Benefits Requirements".

Signed			
•			

Date _____

For questions on this form, please contact Chuck Hicklin at 608-266-4109 or your contract representative at Dane County.

GENERAL CONDITIONS OF CONTRACT

TABLE OF CONTENTS

GEI	NERAL CONDITIONS OF CONTRACT	1
1. (CONSTRUCTION DOCUMENTS	2
2. I	DEFINITIONS	2
3. <i>I</i>	ADDITIONAL INSTRUCTIONS AND DRAWINGS	2
	SHOP DRAWINGS, PRODUCT DATA AND SAMPLES	
	CUTTING AND PATCHING	
	CLEANING UP	
	JSE OF SITE	
8 1	MATERIALS AND WORKMANSHIP	
	CONTRACTOR'S TITLE TO MATERIALS	
	"OR EQUAL" CLAUSE	
	PATENTS AND ROYALTIES	
	SURVEYS, PERMITS, REGULATIONS AND TAXES	
	CONTRACTOR'S OBLIGATIONS AND SUPERINTENDENCE	
	WEATHER CONDITIONS	
	PROTECTION OF WORK AND PROPERTY	
	INSPECTION AND TESTING OF MATERIALS	
	REPORTS, RECORDS AND DATA	
	CHANGES IN THE WORK	
	EXTRAS	
	TIME FOR COMPLETION	
	CORRECTION OF WORK	
21.	SUBSURFACE CONDITIONS FOUND DIFFERENT	10
	RIGHT OF DEPARTMENT TO TERMINATE CONTRACT	
	CONSTRUCTION SCHEDULE AND PERIODIC ESTIMATES PAYMENTS TO CONTRACTOR	
	WITHHOLDING OF PAYMENTS	
	ACCEPTANCE OF FINAL PAYMENT AS RELEASE	
	PAYMENTS BY CONTRACTOR CONTRACT SECURITY	
	ASSIGNMENTS	
	MUTUAL RESPONSIBILITY OF CONTRACTORS	
	SEPARATE CONTRACTS	
	SUBCONTRACTS PUBLIC WORKS PROJECT MANAGER'S AUTHORITY	
	ENGINEER'S AUTHORITY	
	STATED ALLOWANCES ESTIMATES OF QUANTITIES	
	LANDS AND RIGHTS-OF-WAY	
38. 20	GENERAL GUARANTEE	17
	CONFLICTING CONDITIONS	
	NOTICE AND SERVICE THEREOF	
41.	PROTECTION OF LIVES AND HEALTH	1/
		10
	AFFIRMATIVE ACTION PROVISION AND MINORITY / WOMEN /	10
	DISADVANTAGED BUSINESS ENTERPRISES COMPLIANCE WITH FAIR LABOR STANDARDS	
	DOMESTIC PARTNERSHIP BENEFITS USE AND OCCUPANCY PRIOR TO ACCEPTANCE	
	MINIMUM WAGES	
	CLAIMS	
	ANTITRUST AGREEMENT	
	INSURANCE	
	WISCONSIN LAW CONTROLLING	
51.		23

1. CONSTRUCTION DOCUMENTS

- A. Construction Documents, listed in Table of Contents of this Specification volume shall form part of this Contract and provisions of Construction Documents shall be as binding upon parties as if they were fully set forth in Contract itself.
- B. These shall also be considered as part of Construction Documents: Addenda, including additions and modifications incorporated in such addenda before execution of Contract; requests for information; construction bulletins; change orders; and written interpretations by Engineer or Public Works Project Manager that are made after execution of Contract.
- C. Construction Documents are complementary, and what is required by one shall be as binding as if required by all. Intent of Construction Documents is to include all labor, materials and equipment necessary for proper execution of the Work.

2. DEFINITIONS

- A. These terms as used in this Contract are respectively defined as follows:
 - 1. All uses of term "County" in Construction Documents shall mean Dane County.
 - 2. All uses of term "Department" in Construction Documents shall mean Department of Public Works, Highway & Transportation, which is a unit of Dane County government. Department is County agency overseeing Contract with Contractor.
 - 3. Public Works Project Manager is appointed by and responsible to Department. Public Works Project Manager has authority to act on behalf of Department and will sign change orders, payment requests and other administrative matters related to projects.
 - 4. Public Works Project Manager is responsible for supervision, administration and management of field operations involved in construction phase of this Work.
 - 5. Term "Work" includes all labor, equipment and materials necessary to produce project required by Construction Documents.
 - 6. Term "Substantial Completion" is date when project or specified area of project is certified by Engineer that construction is sufficiently completed, in accordance with Construction Documents, and as modified by any subsequent changes agreed to by parties, so that County may occupy project or specified area of project for use for which it was intended subject to permit approval for occupancy.
 - 7. Contractor is person, firm, or corporation with whom County makes Contract. Though multiple contracts may be involved, Construction Documents treat them throughout as if each were of singular number.

3. ADDITIONAL INSTRUCTIONS AND DRAWINGS

A. Contractor may be furnished additional instructions and detail drawings as necessary to carry out the Work included in Contract. Additional drawings and instructions thus supplied to Contractor will coordinate with Construction Documents and will be so prepared that they can be reasonably interpreted as part thereof. Contractor shall carry out the Work in accordance with additional detail drawings and instructions.

4. SHOP DRAWINGS, PRODUCT DATA AND SAMPLES

A. Unless otherwise specified, Contractor shall submit three (3) copies of all Shop Drawings for each submission, until receiving final approval. After final approval, provide five (5) additional copies for distribution and such other copies as may be required.

- B. Contractor shall submit, on an on-going basis and as directed, Product Data such as brochures that shall contain catalog cuts and specifications of all furnished mechanical and electrical equipment. After Engineer's approval, one (1) copy shall remain in Engineer's file, one (1) kept at Department's office and one (1) kept at job site by Contractor for reference purposes.
- C. Samples shall consist of physical examples furnished by Contractor in sufficient size and quantity to illustrate materials, equipment or workmanship, and to establish standards to compare the Work.
 - 1. Submit Samples in sufficient quantity (minimum of two (2)) to permit Engineer to make all necessary tests and of adequate size showing quality, type, color range, finish, and texture. Label each Sample stating material, type, color, thickness, size, project name, and Contractor's name.
 - 2. Submit transmittal letter requesting approval, and prepay transportation charges to Engineer's office on samples forwarded.
 - 3. Materials installed shall match approved Samples.
- D. Contractor shall review Shop Drawings and place their dated stamp thereon to evidence their review and approval and shall submit with reasonable promptness and in orderly sequence to cause no delay in the Work or in work of any other contractor. At time of submission, Contractor shall inform Engineer in writing of any deviation in Shop Drawings or Samples from requirements of Construction Documents. Engineer will not consider partial lists.
- E. Engineer will review and approve or reject Shop Drawings with reasonable promptness to cause no delay. Engineer's approval shall not relieve Contractor from responsibility for errors or omissions in Shop Drawings.
- F. Contractor shall not commence any work requiring Shop Drawing, Product Data or Sample submission until Engineer has approved submission. All such work shall be in accordance with approved Shop Drawings, Product Data and Samples.
- G. Contractor shall keep on site of the Work, approved or conformed copy of Shop Drawings and shall at all time give Department access thereto.
- H. By stamping and submitting Shop Drawings, Product Data and Samples, Contractor thereby represents that he or she has or will determine and verify all field measurements, field construction criteria, materials, catalog numbers, and similar data and that he or she has checked and coordinated each Shop Drawing, Product Data and Sample with requirements of the Work and of Construction Documents. Engineer shall return without examination, Shop Drawings, Product Data and Samples not so noted.
- I. All Shop Drawings from any one Contractor should be numbered consecutively and on cover sheet shall bear name and location of project, name of Contractor, date of submittal and date of each correction or revision and associated Specification section and page number.

5. CUTTING AND PATCHING

A. Not Used.

6. CLEANING UP

- A. Contractor shall keep premises and surrounding area free from accumulation of waste materials or rubbish caused by operations under Contract. Contractor shall remove from and about the Work waste materials, rubbish, Contractor's tools, construction equipment, machinery, and surplus materials at completion of the Work. Contractor shall maintain streets and sidewalks around the Work site in clean condition. Contractor shall remove all spillage and prevent tracking of spillage arising from performance of the Work, into, out of, and within the Work site. Contractor shall establish regular maintenance program of sweeping, vacuuming and / or hosing to minimize accumulation of dirt and dust upon such areas.
- B. If Contractor fails to clean up as directed in Construction Documents, County may do so and shall charge Contractor cost thereof.

7. USE OF SITE

- A. Contractor shall provide County and Engineer access to the Work under all circumstances.
- B. Contractor shall confine operations at site to areas permitted by County, law, ordinance, permits and Construction Documents and shall not unreasonably encumber site with materials or equipment. Contractor shall assure free, convenient, unencumbered, direct and safe access to all properties adjacent to the Work for County, its employees, invitees and guests.

8. MATERIALS AND WORKMANSHIP

- A. Contractor shall perform all work and furnish all supplies and materials, machinery, equipment, facilities and means, necessary to complete the Work required by this Contract, within time specified, in accordance with provisions of Construction Documents.
- B. All equipment and materials incorporated in the Work covered by this Contract are to be new; use recycled and / or recovered materials to extent that such use is technically and economically feasible. Recovered materials are products recovered from solid waste in form identical to original form for use that is same as, or similar to original use. Recycled materials are products manufactured from solid waste.
- C. If requested, Contractor shall furnish satisfactory evidence as to kind and quality of construction materials proposed or used. Contractor shall furnish to Engineer, for approval, manufacturer name and model, performance capacities and other pertinent information of machinery, mechanical, electrical or other types of equipment, which Contractor plans to install.
- D. If not otherwise provided, materials and labor called for in this Contract shall be provided and performed in accordance with established practice and standards recognized by Engineers, Department, and construction industry.
- E. Reference to "Standard" specifications of any association or manufacturer, or codes of County authorities, intends most recent printed edition or catalog in effect on date that corresponds with date of Construction Documents.

F. Whenever reference is made in Specifications that work shall be "performed", "applied", in accordance with "manufacturer's directions or instructions", Contractor to whom those instructions are directed shall furnish three (3) printed copies of such instructions to Engineer before execution of the Work.

9. CONTRACTOR'S TITLE TO MATERIALS

A. Contractor or any subcontractor shall not purchase materials or supplies for the Work subject to any chattel mortgage or under conditional sale contract or other agreement by which seller retains interest. Contractor warrants that all materials and supplies used in the Work are free from all liens, claims or encumbrances and Contractor has good title to them.

10. "OR EQUAL" CLAUSE

- A. Whenever equipment or materials are identified on Drawings or in Specifications by reference to manufacturer's or vendor's name, trade name, catalog number, and other identifying information, it is intended to establish standards; and any equipment or material of other manufacturers and vendors which will perform adequately duties imposed by general design will be considered equally accepted provided equipment or material so proposed is, in opinion of Engineer, of equal substance and function. Engineer and Department shall provide written approval before Contractor may purchase or install it.
- B. Equipment or materials of manufacturers, other than those named, may be used only upon following conditions:
 - 1. That, in opinion of Engineer and Department, proposed material or equipment item is fully equal or superior (in design, materials, construction, workmanship, performance, finish, etc.) to named item. No compromise in quality level, however small, is acceptable.
 - 2. That, in substituting materials or equipment, Contractor assumes responsibility for any changes in system or for modifications required in adjacent or related work to accommodate such substitution despite Engineer's and Department's approval, and all costs growing out of approval of "or equal" items shall be responsibility of Contractor. No extra costs resulting from such approval shall become responsibility of Department, Engineer or any other separate Contractor.
 - 3. It shall be understood that use of materials or equipment other than those specified, or approved equal by Engineer and Department, shall constitute violation of Contract, and that Engineer and Department shall have right to require removal of such materials or equipment and their replacement with specified materials or equipment at Contractor's expense.
 - 4. Product and manufacturer named first in Specifications or on information shown on Drawings is basis of selection of manufactured items and equipment, particularly mechanical equipment. In using other than first named products or manufacturers, including those specified as additionally approved or acceptable, Contractor assumes responsibility for any changes in system and for modifications in any work required to accommodate them. Engineer's approval of such additionally acceptable products or manufacturers, either in Specifications or in Addendum, does not relieve Contractor from obligation to coordinate such optional products with other Contractors, whose work may be affected by them, and to pay all additional costs resulting from their inclusion into the Work. Contractor's liability shall include payment of Engineer's fees for any additional services made necessary by or directly connected to such product changes. No extra

costs resulting from such changes shall become responsibility of Department, Engineer or any other separate Contractor.

C. No request for approval of "or equal" materials will be entertained except from Contractor. Identify any request for substitution as substitution on Contractor's letter of transmittal and give reasons for substitution. Department may in its sole discretion allow substitutions of materials.

11. PATENTS AND ROYALTIES

- A. If Contractor uses any design, device or material covered by letters, patent or copyright, it is mutually agreed and understood, that, without exception, contract prices shall include all royalties or costs arising from use of such design, device or materials, in any way involved in the Work.
- B. Contractor shall indemnify and save harmless County from any and all claims for infringement by reason of use of such patent or copyright in connection with the Work agreed to be performed under this Contract, and shall indemnify County for any cost, expense or damage which it may be obliged to pay by reason of such infringement at any time during prosecution of the Work or after completion of the Work.

12. SURVEYS, PERMITS, REGULATIONS AND TAXES

- A. Department will furnish to Contractor all site, topography and property surveys necessary for execution of the Work. All staking for the Work shall be the responsibility of the Contractor.
- B. Contractor shall procure all permits, licenses and approvals necessary for execution of this Contract.
- C. Contractor shall give all notices and comply with all State of Wisconsin, Federal and local laws, codes, rules and regulations relating to performance of the Work, protection of adjacent property, and maintenance of passageways, guard fences or other protective facilities.
- D. Contractor shall pay all Sales, Consumer, Use and other similar taxes required by law.
- E. Contractor shall promptly notify Engineer of any variances of Drawings or Specifications with that of any State of Wisconsin, federal or local law, code, rule or regulation. Upon such notification, Engineer will require correction of variance to comply with applicable law, code, rule or regulation at no additional cost to Contractor.
- F. Work under this Contract shall comply with all applicable State of Wisconsin, Federal and local laws, codes and regulations.

13. CONTRACTOR'S OBLIGATIONS AND SUPERINTENDENCE

A. Contractor shall provide and pay for all materials, labor, tools, equipment, transportation and superintendence necessary to execute, complete and deliver the Work within specified time. Contractor agrees to secure at their own expense all personnel necessary to carry out the Work. Such personnel shall not be deemed County employees nor shall they have or be deemed to have any direct contractual relationship with County.

- B. Performance of any work necessary after regular working hours, on Sundays or Legal Holidays shall be without additional expense to County. Performance of any work at site at other than normal working hours must be coordinated with Public Works Project Manager.
- C. Contractor shall furnish, erect, maintain and remove such temporary works as may be required.
- D. Contractor shall observe, comply with, and be subject to all terms, conditions, requirements and limitations of Construction Documents.
- E. At the Work site, Contractor shall give personal superintendence to the Work or shall employ construction superintendent or foreman, experienced in character of work covered by Contract, who shall have full authority to act for Contractor. Understand that such superintendent or foreman shall be acceptable to Engineer and Department.
- F. Remove from project or take other corrective action upon notice from Engineer or Department for Contractor's employees whose work is considered by Engineer or Department to be unsatisfactory, careless, incompetent, unskilled or otherwise objectionable.
- G. Contractor and subcontractors shall be required to conform to Labor Laws of State of Wisconsin and various acts amendatory and supplementary thereto and to other laws, ordinances and legal requirements applicable to the Work.
- H. Presence and observation of the Work by Engineer or Public Works Project Manager shall not relieve Contractor of any obligations.

14. WEATHER CONDITIONS

A. In event of temporary suspension of work, or during inclement weather, or whenever Engineer shall direct, Contractor shall, and shall cause subcontractors to protect carefully all work and materials against damage or injury from weather. If, in opinion of Engineer or Department, any work or materials that have been damaged or injured due to failure on part of Contractor or any subcontractors so to protect the Work, such materials shall be removed and replaced at expense of Contractor.

15. PROTECTION OF WORK AND PROPERTY

- A. Contractor shall at all times safely guard County's property from injury or loss in connection with this Contract. Contractor shall at all times safely guard and protect the Work, and adjacent property, from damage. Contractor shall replace or make good any such damage, loss or injury unless such is caused directly by errors contained in Contract, or by County, or County's duly authorized representative.
- B. Contractor may act diligently, without previous instructions from Engineer and / or Department, in emergency that threatens loss or injury of property, or safety of life. Contractor shall notify Engineer and / or Department immediately thereafter. Promptly submit any claim for compensation by Contractor due to such extra work to Engineer and / or Department for approval as provided for in Article 18 herein.

16. INSPECTION AND TESTING OF MATERIALS

- A. Authorized representatives and agents of County government shall have access at all times to the Work wherever it is in preparation or progress and Contractor shall provide facilities for such access and for inspection.
- B. Should it be considered necessary or advisable at any time before final acceptance of the Work to make examination of work already completed, by removing or tearing out same, Contractor shall upon request, promptly furnish all necessary facilities, labor and materials. If such work is found to be defective in any aspect, due to fault of Contractor or subcontractors thereof, Contractor shall assume all expenses of such examination and of satisfactory reconstruction. Contractor will be reimbursed for such examination and replacement in accordance with Article 18 A.3., of these General Conditions of Contract if such work is found to meet requirements of Contract.
- C. If Specifications, Engineer's, or Public Works Project Manager's instructions require any work to be specially tested or approved, Contractor shall give Engineer and Public Works Project Manager timely notice of its readiness for testing or inspection. Test all materials and equipment requiring testing in accordance with accepted or specified standards, as applicable. Engineer shall recommend laboratory or inspection agency and Department will select and pay for all initial laboratory inspection services. Should retesting be required, due to failure of initial testing, cost of such retesting shall be borne by Contractor.
- D. Cost of any testing performed by manufacturers or Contractor for substantiating acceptability of proposed substitution of materials and equipment, or necessary conformance testing in conjunction with manufacturing processes or factory assemblage, shall be borne by Contractor or manufacturer responsible.

17. REPORTS, RECORDS AND DATA

A. Contractor shall submit to Engineer and Public Works Project Manager such schedule of quantities and costs, progress schedules, payrolls, reports, estimates, invoices, records and other data as either may request concerning work performed or to be performed under this Contract.

18. CHANGES IN THE WORK

- A. Make no changes, except in cases of emergency, in the Work covered by approved Construction Documents without having prior written approval of Department. Charges or credits for the Work covered by approved change shall be determined by one of these methods:
 - 1. Unit bid prices previously approved.
 - 2. Agreed lump sum based on actual cost of:
 - a) Labor, including foremen, and all fringe benefits that are associated with their wages.
 - b) Materials entering permanently into the Work.
 - c) Ownership or rental cost of construction tools and equipment during time of use on extra work.
 - d) Power and consumable supplies for operation of power equipment.
 - e) Workmen's Compensation Insurance, Contractor's Public Liability and Property Damage Insurance, and Comprehensive Automobile Liability Insurance.

- f) Social Security and old age and unemployment contributions.
- g) Add to cost under (2), fixed fee to be agreed upon, but not to exceed fifteen percent (15%) of actual cost of work performed with their own labor force. Fee shall be compensation to cover cost of supervision, overhead, bond, profit and any other general expense.
- h) On that portion of the Work under (2) done under subcontract, Contractor may include not over seven and one-half percent (7½%) for supervision, overhead, bond, profit and any other general expense.
- i) Department may require correct amount of costs with supporting vouchers; Contractor shall keep and present in such form as directed.
- 3. Cost-plus work, with not-to-exceed dollar limit, based on actual cost of:
 - a) Labor, including foremen, and all fringe benefits that are associated with their wages.
 - b) Materials entering permanently into the Work.
 - c) Ownership or rental cost of construction tools and equipment during time of use on extra work. Rental cost cannot exceed fifty percent (50%) replacement value of rented equipment.
 - d) Power and consumable supplies for operation of power equipment.
 - e) Workmen's Compensation Insurance, Contractor's Public Liability and Property Damage Insurance, and Comprehensive Automobile Liability Insurance.
 - f) Social Security and old age and unemployment contributions.
 - g) To cost under (3), there shall be added fixed fee to be agreed upon but not to exceed fifteen percent (15%) of actual cost of work performed with their own labor force. Fee shall be compensation to cover cost of supervision, overhead, bond, profit, and any other general expense.
 - h) On that portion of the Work under (3) done under subcontract, Contractor may include not over seven and one-half percent (7½%) for supervision, overhead, bond, profit, and any other general expense.
 - i) Contractor shall keep and present, in such form as directed, correct amount of cost together with such supporting vouchers as may be required by Department.
- B. If Contractor claims that by any instructions given by Engineer, Department, by drawings or otherwise, regarding performance of the Work or furnishing of material under Contract, involves extra cost, Contractor shall give Department written notice of cost thereof within two (2) weeks after receipt of such instructions and in any event before proceeding to execute work, unless delay in executing work would endanger life or property.
- C. No claim for extra work or cost shall be allowed unless it was done in pursuance of written Change Order from Engineer and approved by Department, as previously mentioned, and claim presented with payment request submitted after changed or extra work is completed.
- D. Negotiation of cost for change in the Work shall not be cause for Contractor to delay prosecution of the Work if Contractor has been authorized in writing by Public Works Project Manager to proceed.

19. EXTRAS

A. Without invalidating Contract, Department may order extra work or make changes by altering, adding to or deducting from the Work, contract sum being adjusted in accordance with Article 18 herein.

20. TIME FOR COMPLETION

A. Contractor agrees that the Work shall be prosecuted regularly and diligently and complete the Work as stated in Construction Documents.

21. CORRECTION OF WORK

- A. All work, all materials whether incorporated in the Work or not, and all processes of manufacture shall at all times and places be subject to inspection of Engineer and Public Works Project Manager who shall be judge of quality and suitability of the Work, materials, and processes of manufacture for purposes for which they are used. Should they fail to meet Engineer's and Public Works Project Manager's approval they shall be reconstructed, made good, replaced or corrected, by Contractor at Contractor's expense. Immediately remove all rejected material from site.
- B. If Contractor defaults or neglects to carry out the Work in accordance with Construction Documents or fails to perform any provision of Contract, Department may, after ten (10) days' written notice to Contractor and without prejudice to any other remedy County may have, make good such deficiencies. In such case, appropriate Change Order shall be issued deducting from Contractor's payments then or thereafter, cost of correcting such deficiencies, including cost of Engineer's additional services made necessary by such default, neglect or failure.

22. SUBSURFACE CONDITIONS FOUND DIFFERENT

A. If Contractor encounters subsurface or latent conditions at site materially differing from those shown on Drawings or indicated in Specifications, Contractor shall immediately give notice to Engineer and Public Works Project Manager of such conditions before they are disturbed. Engineer will thereupon promptly investigate conditions, and if Engineer finds that they materially differ from those shown on Drawings or indicated in Specifications, Engineer will at once make such changes as necessary, any increase or decrease of cost resulting from such changes to be adjusted in manner provided in above Article 18 entitled "Changes in the Work".

23. RIGHT OF DEPARTMENT TO TERMINATE CONTRACT

- A. In event that any provisions of this Contract are violated by Contractor or by any subcontractors, County may serve written notice upon Contractor and Surety of its intention to terminate Contract, such notice to contain reasons for such intention to terminate Contract, and unless within ten (10) days after serving of such notice upon Contractor, such violation or delay shall cease and satisfactory arrangement or correction be made, Contract shall, upon expiration of said ten (10) days, cease and terminate.
- B. In event of any such termination, County shall immediately serve notice thereof upon Surety and Contractor, and Surety shall have right to take over and perform Contract subject to County's approval; provided, however, that if Surety does not commence performance thereof within ten (10) days from date of mailing to such Surety of notice of termination, County may take over the Work and prosecute same to completion by contract, or by force account, at expense of Contractor; Contractor and Surety shall be liable to County for any excess cost occasioned County thereby, and in such event County may take possession of and

utilize in completing the Work, such materials and equipment as may be on the Work site and therefore necessary.

24. CONSTRUCTION SCHEDULE AND PERIODIC ESTIMATES

- A. Contractor shall be responsible for Construction Schedule and coordination. Immediately after execution and delivery of Contract and before making first payment, Contractor shall notify all subcontractors to furnish all required information to develop Construction Schedule. Contractor and all subcontractors associated with the Work shall furnish following information from each Division of Specifications:
 - 1. List of construction activities;
 - 2. Start, finish and time required for completion of each activity;
 - 3. Sequential relationships between activities;
 - 4. Identify all long lead-time items, key events, meetings or activities such as required submittals, fabrication and delivery, procurement of materials, installation and testing;
 - 5. Weekly definition of extent of work and areas of activity for each trade or Subcontract; and
 - 6. Other information as determined by Public Works Project Manager.
- B. In addition to above requested items, Contractor shall request delivery dates for all Countyfurnished equipment, materials or labor. This shall include any work handled by Department under separate contracts such as asbestos abatement, air and water balancing, etc. Indicate on Construction Schedule these associated delivery and installation dates.
- C. Progress Reporting:
 - 1. Contractor shall update and publish Construction Schedule on monthly basis. Revisions to Schedule shall be by Contractor and made in same detail as original Schedule and accompanied by explanation of reasons for revision; and shall be subject to approval by Department.
 - 2. Failure of Contractor to keep Schedule in updated format shall result in County hiring firm specializing in construction schedule development and deducting those costs associated with updating process from payments due Contractor.
 - 3. Contractor shall submit show actual percentage of each activity completed, estimated future progress, and anticipated completion time.
- D. Responsibility for timely completion requires:
 - 1. Contractor and subcontractors understand that performance of each is interdependent upon performance of others.
 - 2. Whenever it becomes apparent from current schedule, that phasing or progress completion dates will not be met, Contractor must take some or all following actions at no additional cost to County:
 - a) Increase construction labor in such quantities and crafts as will eliminate backlog of work.
 - b) Increase number of working hours per shift, shifts per working day, working days per week, amount of construction equipment, or any combination of foregoing to eliminate backlog of work.
 - c) Reschedule work (yet remain in conformance with Drawings and Specifications).
 - 3. Prior to proceeding with any of above actions, Contractor shall notify Public Works Project Manager.

E. Maintain current Construction Schedule at all times. Revise Construction Schedule in same detail as original and accompany with explanation of reasons for revision. Schedule shall be subject to approval by Engineer and Public Works Project Manager.

25. PAYMENTS TO CONTRACTOR

- A. Contractor shall provide:
 - 1. Detailed estimate giving complete breakdown of contract price by Specification Division; and
 - 2. Periodic itemized estimates of work done for purpose of making partial payments thereon.

Submit these estimates for approval first to Engineer, then to Public Works Project Manager. Costs employed in making up any of these schedules are for determining basis of partial payments and not considered as fixing basis for additions to or deductions from Contract price.

- B. County will make partial payments to Contractor for value, proportionate to amount of Contract, of all labor and material incorporated in the Work during preceding calendar month upon receipt of Application and Certificate for Payment form from Engineer and approval of Department.
- C. Contractor shall submit for approval first to Engineer, and then to Public Works Project Manager all Application and Certificate for Payment forms. If requested, Application and Certificate for Payment shall be supported by such additional evidence as may be required, showing Contractor's right to payment claimed.
- D. Application and Certificate for Payment for preparatory work and materials delivered and suitably stored at site to be incorporated into the Work at some future period, will be given due consideration. Requesting payment for materials stored off site, may be rejected, however, if deemed essential for reasons of job progress, protection, or other sufficient cause, requests will be considered, conditional upon submission by Contractor of bills of sale, photographs and such other procedures as will adequately protect County's interest such as storage in bonded warehouse with adequate coverage. If there is any error in payment, Contractor is obligated to notify Department immediately, but no longer than ten (10) days from receipt of payment.
- E. Payments by County will be due within forty-five (45) days after receipt by Department of Application and Certificate for Payment.
- F. County will retain five percent (5%) of each Application and Certificate for Payment until final completion and acceptance of all the Work covered by Contract. However, anytime after fifty percent (50%) of the Work has been furnished and installed at site, County will make remaining payments in full if Engineer and Public Works Project Manager find that progress of the Work corresponds with Construction Schedule. If Engineer and Public Works Project Manager find that progress of the Work does not correspond with Construction Schedule, County may retain up to ten percent (10%) of each Application and Certificate for Payment for the Work completed.
- G. All material and work covered by partial payments made shall become sole property of County, but this provision shall not be construed as relieving Contractor from sole responsibility for care and protection of materials and work upon which payments have been

made, or restoration of any damaged work, or as waiver of right of County to require fulfillment of all of terms of Contract.

- H. County will make final payment within sixty (60) days after final completion of the Work, and will constitute acceptance thereof. Submit Equal Benefits Compliance Payment Certification with final pay request. Payment may be denied if Certification is not included.
- I. County may make payment in full, including retained percentages and less authorized deductions, upon completion and acceptance of each Division where price is stated separately in Contract.
- J. Every contractor engaged in performance of any contract for Department of Public Works, Highway & Transportation shall submit to this Department, as requested and with final application for payment for work under said contract, affidavit(s) as required to prove that all debts and claims against this Work are paid in full or otherwise satisfied, and give final evidence of release of all liens against the Work and County. If Wisconsin Prevailing Wage Rate Determination is required for this Work, use "Prime Contractor Affidavit of Compliance with Prevailing Wage Rate Determination" and "Agent or Subcontractor Affidavit of Compliance with Prevailing Wage Rate Determination" (if applicable). If Wisconsin Prevailing Wage Rate Determination is not required for this Work, use "Dane County, Wisconsin_Contractor Wage Affidavit". Forms of such affidavits are included in Supplementary Conditions.

26. WITHHOLDING OF PAYMENTS

- A. County, after having served written notice on said Contractor, may either pay directly any unpaid bills of which Department has written notice, or withhold from Contractor's unpaid compensation sum of money deemed reasonably sufficient to pay any and all such lawful claims until satisfactory evidence is furnished that all liabilities have been fully discharged; whereupon, payment to Contractor shall be resumed in accordance with terms of this Contract, but in no event shall these provisions be construed to impose any obligations upon County to either Contractor or Contractor's Surety.
- B. In paying any unpaid bills of Contractor, County shall be deemed agent of Contractor, and any payment so made by County, shall be considered as payment made under Contract by County to Contractor and County shall not be liable to Contractor for any such payment made in good faith.
- C. Contractor shall indemnify, hold harmless and defend Dane County, its boards, commissions, agencies, officers, employees and representatives from all claims growing out of lawful demands of subcontractors, laborers, workers, mechanics, material men, and furnishers of machinery and parts thereof, equipment, power tools, and all supplies, including commissary, incurred in performance of this Contract.
- D. At Department's request, Contractor shall furnish satisfactory evidence that all obligations of nature designated above have been paid, discharged or waived.

27. ACCEPTANCE OF FINAL PAYMENT AS RELEASE

A. Making of final payment shall constitute waiver of all claims by County except those arising from:

- 1. Unsettled lien;
- 2. Faulty or defective work appearing after substantial completion;
- 3. Failure of the Work to comply with requirements of Construction Documents; or
- 4. Terms of any special guarantees required by Construction Documents.
- B. Acceptance of final payment shall constitute waiver of all claims by Contractor.

28. PAYMENTS BY CONTRACTOR

- A. Contractor shall pay following not later than fifth (5^{th}) day following each payment received from County:
 - 1. All transportation and utility services rendered;
 - 2. All materials, tools, and other expendable equipment that have been delivered at site of the Work to extent of ninety percent (90%) of cost thereof, and balance of cost thereof when said balance is paid to Contractor; and
 - 3. Each subcontractor, respective amount allowed Contractor because of work performed by subcontractor to extent of subcontractor's interest therein.

29. CONTRACT SECURITY

- A. Contractor shall furnish Performance and Payment Bonds in amount at least equal to one hundred percent (100%) of Contract price as security for faithful performance of this Contract and payment of all persons performing labor on project under this Contract and furnishing materials in connection with this Contract.
- B. Sample Performance and Payment Bonds that Contractor will be required to execute is bound into these Construction Documents. Before construction Contract is consummated, completed Performance and Payment Bonds must be approved by Department.

30. ASSIGNMENTS

A. Contractor shall not assign whole or any part of this Contract or any moneys due or to become due hereunder without written consent of Department. In case Contractor assigns all or any part of any moneys due or to become due under this Contract, instrument of assignment shall contain clause substantially to effect that it is agreed that right of assignee in and to any moneys due or to become due to Contractor shall be subject to prior claims of all persons, firms and corporations for services rendered or materials supplied for performance of the Work called for in this Contract.

31. MUTUAL RESPONSIBILITY OF CONTRACTORS

A. If, through acts of neglect on part of Contractor or any subcontractor shall suffer loss or damage on the Work, Contractor agrees to settle with such subcontractor by agreement or arbitration if such other subcontractor will so settle. If such subcontractor shall assert any claim against County on account of any damage alleged to have been sustained, Department shall notify Contractor, who shall indemnify, hold harmless and defend Dane County, its boards, commissions, agencies, officers, employees and representatives against any such claim.

32. SEPARATE CONTRACTS

- A. Department may award other contracts for the Work and all Contractors shall fully cooperate with each other and carefully adjust their work to that provided under other contracts as may be directed by Department. No Contractor shall commit or permit any act that will interfere with performance of the Work by any other Contractor.
- B. Contractor shall coordinate the Work with those of other Contractors. Cooperation will be required in arrangement for storage of materials and in detailed execution of the Work. Contractor, including subcontractors, shall keep informed of progress and detail work of others and shall notify Engineer or Department immediately of lack of progress or defective workmanship on part of others. Failure of Contractor to keep informed of the Work progressing on site and failure to give notice of lack of progress or defective workmanship by others shall be construed as acceptance by Contractor of status of the Work as being satisfactory for proper coordination with Contractor's own work.

33. SUBCONTRACTS

- A. Contractor may use services of specialty subcontractors on those parts of the Work that, under normal contracting practices, are performed by specialty subcontractors.
- B. Contractor shall not award any work to any subcontractor without prior approval of Department. Qualifications of subcontractors shall be same as qualifications of Contractor. Request for subcontractor approval shall be submitted to Department fifteen (15) days before start of subcontractor's work. If subcontractors are changed or added, Contractor shall notify Department in writing.
- C. Contractor shall be as fully responsible to County for acts and omissions of subcontractors, and of persons either directly or indirectly employed by them, as Contractor is for acts and omissions of persons directly employed by Contractor.
- D. Contractor shall cause appropriate provisions to be inserted in all subcontracts relative to the Work to bind subcontractors to Contractor by terms of General Conditions of Contract and other Construction Documents insofar as applicable to work of subcontractors and to give Contractor same power as regards terminating any subcontract that Department may exercise over Contractor under any provision of Construction Documents.
- E. Nothing contained in this Contract shall create any contractual relation between any subcontractor and County.
- F. Contractor shall insert in all subcontracts, Articles 26, 33, 43 and 45, respectively entitled: "Withholding of Payments", "Subcontracts", "Affirmative Action Provision and Minority / Women / Disadvantaged Business Enterprises", and "Minimum Wages", and shall further require all subcontractors to incorporate physically these same Articles in all subcontracts.

34. PUBLIC WORKS PROJECT MANAGER'S AUTHORITY

- A. Public Works Project Manager shall:
 - 1. Administer and ensure compliance with Construction Documents;

- 2. Provide responsible on-site observations of construction and have authority to request work and to stop work whenever necessary to insure proper enforcement of Construction Documents;
- 3. Convene and chair project meetings and foreman's coordination meetings when necessary to coordinate resolution of conflicts between Contractors, Engineers, Consultants, and Department; and
- 4. Check and inspect material, equipment and installation procedures of all trades for proper workmanship and for compliance with Drawings, Specifications and Shop Drawings, permit no material on project site that is not satisfactory and reject work not in compliance with Construction Documents.

35. ENGINEER'S AUTHORITY

- A. Engineer is retained by, and is responsible to Department acting for County.
- B. Engineer shall determine amount, quality, acceptability, and fitness of several kinds of work and materials that are provided under this Contract and shall decide all questions that may arise in relation to said work and construction thereof.
- C. Engineer shall decide meaning and intent of any portion of Specifications and of any Drawings where they may be found obscure or be in dispute.
- D. Engineer shall provide responsible observation of construction. Engineer has authority to stop the Work whenever such stoppage may be necessary to insure proper execution of Construction Documents.
- E. Engineer shall be interpreter of conditions of Construction Documents and judge of its performance.
- F. Within reasonable time, Engineer shall make decisions on all matters relating to progress of the Work or interpretation of Construction Documents.
- G. Engineer's decisions are subject to review by Public Works Project Manager.

36. STATED ALLOWANCES

A. Not Used.

37. ESTIMATES OF QUANTITIES

A. Whenever estimated quantities of work to be done and materials to be furnished under this Contract are shown in any of Construction Documents, they are given for use in comparing bids and right is especially reserved to increase or diminish them as they may be deemed reasonably necessary or desirable by Department to complete the Work included in this Contract, and cost for such increase or diminution shall be adjusted in manner provided for in General Conditions of Contract Article 18 entitled "Changes in the Work".

38. LANDS AND RIGHTS-OF-WAY

A. Prior to start of construction, County shall furnish all land and rights-of-way necessary for carrying out and completion of the Work to be performed under this Contract.

39. GENERAL GUARANTEE

- A. Neither final certificate of payment nor any provision in Construction Documents nor partial or entire occupancy of premises by County shall constitute acceptance of work not done in accordance with Construction Documents or relieve Contractor of liability in respect to any expressed warranties or responsibility for faulty materials or workmanship.
 - 1. In no event shall making of any payment required by Contract constitute or be construed as waiver by County of any breach of covenants of Contract or waiver of any default of Contractor and making of any such payment by County while any such default or breach shall exist shall in no way impair or prejudice right of County with respect to recovery of damages or other remedy as result of such breach or default.
- B. Contractor shall remedy and make good all defective workmanship and materials and pay for any damage to other work resulting there from, which appear within period of one (1) year from date of substantial completion, providing such defects are not clearly due to abuse or misuse by County. Department will give notice of observed defects with reasonable promptness.
- C. Guarantee on work executed after certified date of substantial completion will begin on date when such work is inspected and approved by Engineer and Public Works Project Manager.
- D. Where guarantees or warrantees are required in sections of Specifications for periods in excess of one (1) year, such longer terms shall apply; however, Contractor's Performance and Payment Bonds shall not apply to any guarantee or warranty period in excess of one (1) year.

40. CONFLICTING CONDITIONS

- A. Any provision in any of Construction Documents which may be in conflict or inconsistent with any Articles in these General Conditions of Contract or Supplementary Conditions shall be void to extent of such conflict or inconsistency.
- B. In case of ambiguity or conflict between Drawings and Specifications, Specifications shall govern.
- C. Printed dimensions shall be followed in preference to measurements by scale. Large-scale drawings take precedence over small-scale drawings. Dimensions on Drawings and details are subject to field measurements of adjacent work.

41. NOTICE AND SERVICE THEREOF

A. Any notice to Contractor from Department relative to any part of this Contract shall be in writing and considered delivered and service thereof completed, when said notice is posted, by certified or registered mail, to Contractor at Contractor's last given address, or delivered in person to said Contractor, or Contractor's authorized representative on the Work.

42. PROTECTION OF LIVES AND HEALTH

- A. In order to protect lives and health of Contractor's employees under Contract, Contractor shall comply with all pertinent provisions of Wisconsin Administrative Code, Rules of Department of Commerce, relating to Safety and Health.
- B. Contractor alone shall be responsible for safety, efficiency and adequacy of Contractor's tools, equipment and methods, and for any damage that may result from their failure or their improper construction, maintenance or operation.

43. AFFIRMATIVE ACTION PROVISION AND MINORITY / WOMEN / DISADVANTAGED BUSINESS ENTERPRISES

A. Affirmative Action Provisions.

- 1. During term of their Contract, Contractor agrees not to discriminate on basis of race, religion, color, sex, handicap, age, sexual preference, marital status, physical appearance, or national origin against any person, whether recipient of services (actual or potential), employee, or applicant for employment. Such equal opportunity shall include but not be limited to following: employment, upgrading, demotion, transfer, recruitment, advertising, layoff, termination, training, rates of pay, and any other form of compensation or level of service(s). Contractor agrees to post in conspicuous places, these affirmative action standards so as to be visible to all employees, service recipients and applicants for this paragraph. Listing of prohibited bases for discrimination shall no be construed to amend in any fashion state or federal law setting forth additional bases and exceptions shall be permitted only to extent allowable in state or federal law.
- 2. Contractor is subject to this Article only if Contractor has ten (10) or more employees and receives \$10,000.00 or more in annual aggregate contracts with County. Contractor shall file and Affirmative Action Plan with Dane County Contract Compliance Officer in accord with Chapter 19 of Dane County Code of Ordinances. Such plan must be filed within fifteen (15) days of effective date of this Contract and failure to do so by said date shall constitute ground for immediate termination of Contract by County. Contractor shall also, during term of this Contract, provide copies of all announcements of employment opportunities to County's Contract Compliance Office, and shall report annually number of persons, by race, sex and handicap status, who apply for employment, and, similarly classified, number hired and number rejected.
- Contact Dane County Contract Compliance Officer at Dane County Contract Compliance Office, 210 Martin Luther King, Jr. Blvd., Room 421, Madison, WI 53703, 608/266-4114.
- 4. In all solicitations for employment placed on Contractor's behalf during term of this Contract, Contractor shall include statement to affect Contractor is "Equal Opportunity Employer". Contractor agrees to furnish all information and reports required by County's Contract Compliance Officer as same relate to affirmative action and nondiscrimination, which may include any books, records, or accounts deemed appropriate to determine compliance with Chapter 19, Dane County Code of Ordinances, and provision of this Contract.
- B. Minority / Women / Disadvantaged / Emerging Small Business Enterprises.
 - Chapter 19.508 of Dane County Code of Ordinances is official policy of Dane County regarding utilization of, to fullest extent of, Minority Business Enterprises (MBEs), Women Business Enterprises (WBEs) Disadvantage Business Enterprises (DBEs) and Emerging Small Business Enterprises (ESBEs).

2. Contractor may utilize MBEs / WBEs / DBEs / ESBEs as subcontractors or suppliers. List of subcontractors will be required of low bidder as stated in this Contract. List shall indicate which are MBEs / WBEs / DBEs / ESBEs and percentage of subcontract awarded, shown as percentage of total dollar amount of bid.

44. COMPLIANCE WITH FAIR LABOR STANDARDS

- A. During term of this Contract, Contractor shall report to County Contract Compliance Officer, within ten (10) days, any allegations to, or findings by National Labor Relations Board (NLRB) or Wisconsin Employment Relations Commission (WERC) that Contractor has violated statute or regulation regarding labor standards or relations. If investigation by Contract Compliance Officer results in final determination that matter adversely affects Contractor's responsibilities under this Contract, and which recommends termination, suspension or cancellation of this Contract, County may take such action.
- B. Contractor may appeal any adverse finding by Contract Compliance Officer as set forth in Dane County Ordinance 25.015(11)(c) through (e).
- C. Contractor shall post this statement in prominent place visible to employees: "As condition of receiving and maintaining contract with Dane County, this employer shall comply with federal, state and all other applicable laws prohibiting retaliation or union organizing."

45. DOMESTIC PARTNERSHIP BENEFITS

A. Contractor agrees to provide same economic benefits to all of its employees with domestic partners as it does to employees with spouses, or cash equivalent if such benefit cannot reasonably be provided. Contractor agrees to make available for County inspection Contractor's payroll records relating to employees providing services on or under this Contract or subcontract. If any payroll records of Contractor contain any false, misleading or fraudulent information, or if Contract or fails to comply with provisions of Chapter 25.016, Dane County Ordinances, contract compliance officer may withhold payments on Contract; terminate, cancel or suspend Contract in whole or in part; or, after due process hearing, deny Contractor right to participate in bidding on future County contracts for period of one year after first violation is found and for period of three years after second or subsequent violation is found.

46. USE AND OCCUPANCY PRIOR TO ACCEPTANCE

- A. Contractor agrees to use and occupancy of portion or unit of the Work before formal acceptance by Department, provided Department:
 - 1. Secures written consent of Contractor; except when in opinion of Public Works Project Manager, Contractor is chargeable with unwarranted delay in final cleanup of punch list items or other Contract requirements.
 - 2. Secures endorsement from insurance carrier and consent of Surety permitting occupancy of building or use of the Work during remaining period of construction, or, secures consent of Surety.
 - 3. Assumes all costs and maintenance of heat, electricity and water.
 - 4. Accepts all work completed within that portion or unit of the Work to be occupied, at time of occupancy.

47. MINIMUM WAGES

- A. Contractor shall post, at appropriate conspicuous point on site of project, schedule showing all determined minimum wage rates for various classes of laborers and mechanics to be engaged in the Work under this Contract and all deductions, if any, required by law to be made from unpaid wages actually earned by laborers and mechanics so engaged.
- B. Supplementary Conditions section in Construction Documents lists wage determinations required by State Law.
- C. If, after award of Contract, it becomes necessary to employ any person in trade or occupation not classified in wage determinations, such person shall be paid at not less than such rate as shall be determined by Wisconsin Department of Workforce Development. Such approved minimum rate shall be retroactive to time of initial employment of such person in such trade or occupation. Contractor shall notify Department of Contractor's intention to employ persons in trades or occupations not so classified in sufficient time for Department to obtain approved rates for such trades or occupations.
- D. Specified wage rates are minimum rates only, and Department will not consider any claims for additional compensation made by Contractor because of payment by Contractor of any wage rate in excess of applicable rate contained in this Contract. Contractor shall adjust any disputes in regard to payment of wages in excess of those specified in this Contract.
- E. Submit required affidavit(s) to Department of Public Works, Highway & Transportation, as requested and with final application for payment for work under said contract. Affidavit(s) shall clearly indicate name, trade or occupation, and paid wages of every laborer, worker or mechanic employed by Contractor and all subcontractors during billing period including accurate record of number of hours worked by each employee and actual wages paid as stipulated in Wisconsin Statue 66.0903. If Wisconsin Prevailing Wage Rate Determination is required for this Work, use "Prime Contractor Affidavit of Compliance with Prevailing Wage Rate Determination" and "Agent or Subcontractor Affidavit of Compliance with Prevailing Wage Rate Determination" (if applicable). If Wisconsin Prevailing Wage Rate Determination is not required for this Work, use "Dane County, Wisconsin Contractor Wage Affidavit". Forms of such affidavits are included in Supplementary Conditions.

48. CLAIMS

A. No claim may be made until Department's Assistant Public Works Director has reviewed Engineer's decision as provided for in Article 35 of General Conditions of Contract. If any claim remains unresolved after such review by Department's Assistant Public Works Director the claim may be filed under Wisconsin Statute 893.80. Work shall progress during period of any dispute or claim. Unless specifically agreed between parties, venue will be in Dane County, Wisconsin.

49. ANTITRUST AGREEMENT

A. Contractor and County recognize that in actual economic practice, overcharges resulting from antitrust violations are in fact usually borne by County. Therefore, Contractor hereby assigns to County any and all claims for such overcharges as to goods and materials purchased in connection with this Contract, except as to overcharges which result from

antitrust violations commencing after price is established under this Contract and any change order thereto.

50. INSURANCE

- A. Contractor Carried Insurance:
 - Contractor shall not commence work under this Contract until Contractor has obtained all insurance required under this Article and has provided evidence of such insurance to Risk Manager, 425 City-County Building, 210 Martin Luther King Jr. Blvd., Madison, WI 53703. Contractor shall not allow any subcontractor to commence work until insurance required of subcontractor has been so obtained and approved. Company providing insurance must be licensed to do business in Wisconsin.
 - 2. Worker's Compensation Insurance:
 - a) Contractor shall procure and shall maintain during life of this Contract, Worker's Compensation Insurance as required by statute for all of Contractor's employees engaged in work at site of project under this Contract and, in case of any such work sublet, Contractor shall require subcontractor similarly to provide Worker's Compensation Insurance for all of latter's employees to be engaged in such work unless such employees are covered by protection afforded by Contractor's Worker's Compensation Insurance.
 - b) If any claim of employees engaged in hazardous work on project under this Contract is not protected under Worker's Compensation Statute, Contractor shall provide and shall cause each subcontractor to provide adequate Employer's Liability Insurance for protection of such of Contractor's employees as are not otherwise protected.
 - 3. Contractor's Public Liability and Property Damage Insurance:
 - a) Contractor shall procure and maintain during life of this Contract, Contractor's Public Liability Insurance and Contractor's Property Damage Insurance in amount not less than \$1,000,000 bodily injury, including accidental death, to any one person, and subject to same limit for each person, in amount not less than \$1,000,000 on account of one accident, and Contractor's Property Damage Insurance in amount not less then \$1,000,000 or combined single limit of at least \$1,000,000 with excess coverage over and above general liability in amount not less than \$5,000,000. Contractor shall add "Dane County" as additional insured for each project.
 - b) Contractor's Public Liability and Property Damage Insurance shall include Products, Completed Operation, and Contractual Liability under Insurance Contract. "Contractor shall in all instances save, defend, indemnify and hold harmless County and Engineer against all claims, demands, liabilities, damages or any other costs which may accrue in prosecution of the Work and that Contractor will save, defend, indemnify and hold harmless County and Engineer from all damages caused by or as result of Contractor's operations" and each shall be listed as additional insured on Contractor's and sub-contractors' insurance policies.
 - c) Obligations of Contractor under Article 48.A.2)b) shall not extend to liability of Engineer, agents or employees thereof, arising out of:
 - 1) Preparation or approval of maps, drawings, opinions, reports, surveys, change orders, designs or specifications; or
 - 2) giving of or failure to give directions or instructions by Engineer, agents or employees thereof provided such giving or failure to give is primary cause of injury or damage.
 - d) Contractor shall procure and shall maintain during life of this Contract, Comprehensive Automobile Liability Insurance covering owned, non-owned and hired automobiles for limits of not less than \$1,000,000 each accident single limit,

bodily injury and property damage combined with excess coverage over and above general liability in amount not less than \$5,000,000.

- e) Contractor shall either:
 - Require each subcontractor to procure and to maintain during life of subcontract, subcontractor's Public Liability Property Damage Insurance, and Comprehensive Automobile Liability Insurance of type and in same amount specified in preceding paragraphs; or
 - 2) Insure activities of subcontractors in Contractor's own policy.
- 4. Scope of Insurance and Special Hazards: Insurance required under Article 48.A.2 hereof shall provide adequate protection for Contractor and subcontractors, respectively, against damage claims which may arise from operations under this Contract, whether such operation be by insured or by anyone directly or indirectly employed by insured and also against any of special hazards which may be encountered in performance of this Contract as enumerated in Supplementary Conditions.
- 5. Proof of Carriage of Insurance: Contractor shall furnish Risk Manager with certificates showing type, amount, class of operations covered, effective dates, dates of expiration of policies and "Dane County" listed as additional insured. Such certificates shall also contain (substantially) following statement: "Insurance covered by this certificate will not be canceled or materially altered, except after ten (10) days written notice has been received by Risk Manager."
- B. Builder's Risk:
 - 1. County shall provide Builder's Risk policy. Terms of this policy will be made available by County's Risk Manager, upon Contractor's request. By executing this Contract, Contractor warrants it is familiar with terms of said policy.
- C. Indemnification / Hold Harmless:
 - 1. Contractor shall indemnify, hold harmless and defend Dane County, its boards, commissions, agencies, officers, employees and representatives from and against all claims, damages, losses and expenses including attorneys' fees arising out of or resulting from performance of the Work, provided that any such claim, damage, loss or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself) including loss of use resulting therefrom, and is caused in whole or in part by any act or omission of Contractor, any subcontractor, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, regardless of whether or not it is caused in part by part indemnified hereunder.
 - 2. In any and all claims against Dane County, its boards, commissions, agencies, officers, employees and representatives or by any employee of Contractor, any subcontractor, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, indemnification obligation under this Contract shall not be limited in any way by any limitation on amount or type of damages, compensation or benefits payable by or for Contractor or any subcontractor under worker's compensation acts, disability benefits or other employee benefit acts.
 - 3. Obligations of Contractor under this Contract shall not extend to liability of Engineer, its agents or employees arising out of:
 - a) Preparation or approval of maps, drawings, opinion, reports, surveys, change orders, designs or specifications; or
 - b) Giving of or failure to give directions or instruction by Engineer, its agents or employees provided such giving or failure to give is primary cause of injury or damage.

4. Dane County shall not be liable to Contractor for damages or delays resulting from work by third parties or by injunctions or other restraining orders obtained by third parties.

51. WISCONSIN LAW CONTROLLING


A. It is expressly understood and agreed to by parties hereto that in event of any disagreement or controversy between parties, Wisconsin law shall be controlling.

SUPPLEMENTARY CONDITIONS

1. APPLICATION & CERTIFICATE FOR PAYMENT

A. Every contractor engaged in performance of any contract for Department of Public Works, Highway & Transportation shall submit partial and final Application & Certificate for Payment for work under said contract. Form shall provide similar information as shown on AIA G702TM and G703TM forms (samples shown below). Forms shall be submitted to Public Works Project Manager for approval.

PROM CONTRACTOR: VA ARCHTECT: PRODO TO: CONTRACT FOR: ARC CONTRACT OR: VA ARCHTECT: PROJECT NOS: // /	n accord for World
PROM CONTRACTOR: VA ARONTECT: CONTRACT DATE PROJECT NOS: CONTRACT DATE PROJECT NOS CONTR	FIELD OTHER inform a score
CONTRACTOR'S APPLICATION FOR PAYMENT Apploation is made for provines, as down bloors, is consistion with the Contract Contract state Adv provines, as down bloors, is consistion with the Contract Contract state Adv provines (200), is analyde 1.0HGMAN, CONTRACT SUM 2. Not change thy Change Orders 3. Contract state 1 ± 2	FIELD OTHER inform in accord for Wor
CONTRACTOR'S APPLICATION FOR PAYMENT Apple data in its made for progress, in shows below, in connection with the Contract. The undersigned Contract is profile with the formation is made for progress. Contract Sum Contract Sum 5 2. Not change by Change Orders 5 3. Contract Sum To DATE (Line 1 & 2) 5 4. Strated Sum Do Date (Line 1 & 2) 5 5. Strated Sum Do Date (Line 1 & 2) 5 6. Strated Sum Do Date (Line 1 & 2) 5 7. Strated Sum Do Date (Line 1 & 2) 5 8. Contract Sum To Date (Line 1 & 2) 5 9. Strated Sum Do Date (Line 1 & 2) 5 9. Strated Sum Do Date (Line 1 & 2) 5 9. Strate Sum To Date (Line 1 & 2) 5 9. Strate Sum Do Date (Line 1 & 2) 5 9. Strate Sum Do Date (Line 1 & 2) 5 9. Strate Sum Do Date (Date 1 & 2) 5 9. Strate Sum Do Date (Date 1 & 2) 5 9. Strate Sum Do Date (Date 1 & 2) 5 9. Strate Sum Do Date (Date 1 & 2) 5 9. Strate Sum Do Date (Date 1 & 2) 5 9. Strate Sum Do Date (Date 2 Sum Do Date 2 Sum D	OTHER inform for World
Applements in an analy for provinces, in strandord. Construction is much for provinces, and shown below, in construction with the Construct. Construction State, AEA Document G700, is analyded. S. Act change by Change Orders S. Act change by Change Orders S. Construct State 1 ± 2 S. Construct State 1 ± 2 S. Construct State 1 ± 2 S. Construction State 1 ± 2 S. Const	inform naccord for Wor
Application is made for progress, is shown below, in connection with the Contract. Continuous Store, ADA Document G700, is analyded. Contract Stare (Document G700, is analyded. Contract Stare (Docum	inform naccord for Wor
A TOTAL CARNED LESS RETAXAGE S ARCHITEC''S CERTIFICATE FOR PAYMENT Obset Less Retax December and the less december december and the less december december december	Work month
(Line X law Line 6) 5	
CULINGE OF DEPARTMENT ADDITIONS DEDUCTIONS ARCHITECT:	
Total changes approved in previous months by Owner 5 5 8y	
Total approval (b): Month 5 5 5 Total approval (b): Month 6 5 5 This Contificate is not negotiable. The AMOUNT CERTIFIED is periable only to th	
TOTALS 5 This Control of the AMALAST CONTROL of the Provide only of the	



2. PREVAILING WAGE RATE DETERMINATION

- B. These supplements shall modify, delete, and / or add to General Conditions of Contract. Where any article, paragraph, or subparagraph in General Conditions of Contract is supplemented by one of these paragraphs, provisions of such article, paragraph, or subparagraph shall remain in effect and supplementary provisions shall be considered as added thereto. Where any article, paragraph, or subparagraph in General Conditions of Contract is amended, voided, or superseded by any of these paragraphs, provisions of such article, paragraph, or subparagraph not so amended, voided, or superseded shall remain in effect.
 - 1. General Conditions of Contract Article 47, "Minimum Wages", paragraph B. Following Prevailing Wage Rate Determination No. 201500870 is added to General Conditions of Contract.
- C. These State of Wisconsin forms, hereinafter set forth in this section, shall be filled out and submitted to Department of Public Works, Highway & Transportation:
 - 1. Disclosure of Ownership (ERD-7777)
 - 2. Prime Contractor Affidavit of Compliance With Prevailing Wage Rate Determination (ERD-5724)
 - 3. List of Agents and Subcontractors (Page 2 ERD-5724)
 - 4. Agent or Subcontractor Affidavit of Compliance With Prevailing Wage Rate Determination (ERD-10584)
 - 5. List of Agents and Subcontractors (Page 2 ERD-10584)
 - 6. Request To Employ Subjourneyperson (ERD-10880)
- D. At a minimum, these wage rates must be displayed in a place where all workers can access them, but not inside the job trailer. If this isn't easily done based on job conditions, the State requires they be displayed at a library or other public building.

ISSUE DATE: 3/5/2015 PROJECT: BADGER PRAIRIE HEALTH CARE CENTER - REGRADING AND PRAIRIE RESTORATION VERONA CITY, DANE COUNTY, WI Determination No. 201500870 [Owner Project No. 315022] **PROJECT OWNER: REQUESTER:** ERIC URTES, PROJECT MANAGER ERIC URTES, PROJECT MANAGER DANE COUNTY PUBLIC WORKS DANE COUNTY PUBLIC WORKS 1919 ALLIANT ENERGY CENTER WAY 1919 ALLIANT ENERGY CENTER WAY MADISON, WI 53713 MADISON, WI 53713 **ADDITIONAL CONTACT: NOTE:** The Requester must provide a copy of this Project Determination and enclosures to the Project Owner and Additional Contact.

The department received an application for prevailing wage rate determination for the above-captioned project. The department conducted a survey to determine the prevailing wage rate for the trade(s) or occupation(s) needed to complete the project. The survey's findings appear in the attached project determination.

If you believe that the wage rate for any trade or occupation does not accurately reflect the prevailing wage rate in the city, village or town where the project is located, you may ask the department to conduct an administrative review of such wage rate. You must submit this request in writing within 30 days from the date indicated above. Additionally, your request must include wage rate information from at least three similar projects in the city, village or town where the proposed project is located and on which some work has been performed by the contested trade(s) during the current survey period and was previously considered by the department in issuing the attached determination. See DWD 290.10 of the Wisconsin Administrative Code and either s. 66.0903(3)(br), Stats., or s. 103.49(3)(c), Stats., for a complete explanation of the administrative review process.

Enclosures

It is hereby ordered that the prevailing wage rates set forth in the attached project determination shall only be applicable to the above referenced project. This order is a **FINAL ORDER** of the department unless a timely request for an administrative review is filed with the department.

ISSUED BY:

Equal Rights Division Labor Standards Bureau Construction Wage Standards Section P.O. Box 8928, Madison, WI 53708-8928 (608)266-6861

Web Site: http://dwd.wisconsin.gov/er/

PREVAILING WAGE RATE DETERMINATION Issued by the State of Wisconsin Department of Workforce Development Pursuant to s. 66.0903, Wis. Stats.

Pursuant to s. 66.0903, Wis. Stats Issued On: 3/5/2015

201500870 **DETERMINATION NUMBER:** Prime Contracts MUST Be Awarded or Negotiated On Or Before EXPIRATION DATE: 12/31/2015. If NOT, You MUST Reapply. BADGER PRAIRIE HEALTH CARE CENTER - REGRADING AND PRAIRIE **PROJECT NAME:** RESTORATION PROJECT NO: 315022 **PROJECT LOCATION:** VERONA CITY, DANE COUNTY, WI CONTRACTING AGENCY: DANE COUNTY PUBLIC WORKS Contractors are responsible for correctly classifying their workers. Either call the Department of CLASSIFICATION: Workforce Development (DWD) with trade or classification guestions or consult DWD's Dictionary of Occupational Classifications & Work Descriptions on the DWD website at: dwd.wisconsin.gov/er/prevailing wage rate/Dictionary/dictionary main.htm. Time and one-half must be paid for all hours worked: **OVERTIME:** - over 10 hours per day on prevailing wage projects - over 40 hours per calendar week - Saturday and Sunday - on all of the following holidays: January 1: the last Monday in May: July 4: the 1st Monday in September; the 4th Thursday in November; December 25: - The day before if January 1, July 4 or December 25 falls on a Saturday; - The day following if January 1, July 4 or December 25 falls on a Sunday. Apply the time and one-half overtime calculation to whichever is higher between the Hourly Basic Rate listed on this project determination or the employee's regular hourly rate of pay. Add any applicable Premium or DOT Premium to the Hourly Basic Rate before calculating overtime. A DOT Premium (discussed below) may supersede this time and one-half requirement. FUTURE INCREASE: When a specific trade or occupation requires a future increase, you MUST add the full hourly increase to the "TOTAL" on the effective date(s) indicated for the specific trade or occupation. If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the PREMIUM PAY: "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whevenever such pay is applicable. DOT PREMIUM: This premium only applies to highway and bridge projects owned by the Wisconsin Department of Transportation and to the project type heading "Airport Pavement or State Highway Construction." DO NOT apply the premium calculation under any other project type on this determination. APPRENTICES: Pay apprentices a percentage of the applicable journeyperson's hourly basic rate of pay and hourly fringe benefit contributions specified in this determination. Obtain the appropriate percentage from each apprentice's contract or indenture. Subjourney wage rates may be available for some of the trades or occupations indicated below with SUBJOURNEY: the exception of laborers, truck drivers and heavy equipment operators. Any employer interested in using a subjourney classification on this project MUST complete Form ERD-10880 and request the applicable wage rate from the Department of Workforce Development PRIOR to using the subjourney worker on this project.

This document **MUST BE POSTED** by the **CONTRACTING AGENCY** in at least one conspicuous and easily accessible place **on the site of the project**. A local governmental unit may post this document at the place normally used to post public notices if there is no common site on the project. This document **MUST** remain posted during the entire time any worker is employed on the project and **MUST** be physically incorporated into the specifications and all contracts and subcontracts. If you have any questions, please write to the Equal Rights Division, Labor Standards Bureau, P.O. Box 8928, Madison, Wisconsin 53708 or call (608) 266-6861.

The following statutory provisions apply to local governmental unit projects of public works and are set forth below pursuant to the requirements of s. 66.0903(8), Stats.

s. 66.0903 (1) (f) & s. 103.49 (1) (c) "PREVAILING HOURS OF LABOR" for any trade or occupation in any area means 10 hours per day and 40 hours per week and may not include any hours worked on a Saturday or Sunday or on any of the following holidays:

- 1. January 1.
- 2. The last Monday in May.
- 3. July 4.
- 4. The first Monday in September.
- 5. The 4th Thursday in November.
- 6. December 25.
- 7. The day before if January 1, July 4 or December 25 falls on a Saturday.
- 8. The day following if January 1, July 4 or December 25 falls on a Sunday.

s. 66.0903 (10) RECORDS; INSPECTION; ENFORCEMENT.

(a) Each contractor, subcontractor, or contractor's or subcontractor's agent performing work on a project of public works that is subject to this section shall keep full and accurate records clearly indicating the name and trade or occupation of every person performing the work described in sub. (4) and an accurate record of the number of hours worked by each of those persons and the actual wages paid for the hours worked.

s. 66.0903 (11) LIABILITY AND PENALTIES.

(a) 1. Any contractor, subcontractor, or contractor's or subcontractor's agent who fails to pay the prevailing wage rate determined by the department under sub. (3) or who pays less than 1.5 times the hourly basic rate of pay for all hours worked in excess of the prevailing hours of labor is liable to any affected employee in the amount of his or her unpaid wages or his or her unpaid overtime compensation and in an additional amount as liquidated damages as provided under subd. 2., 3., whichever is applicable.

2. If the department determines upon inspection under sub. (10) (b) or (c) that a contractor, subcontractor, or contractor's or subcontractor's agent has failed to pay the prevailing wage rate determined by the department under sub. (3) or has paid less than 1.5 times the hourly basic rate of pay for all hours worked in excess of the prevailing hours of labor, the department shall order the contractor to pay to any affected employee the amount of his or her unpaid wages or his or her unpaid overtime compensation and an additional amount equal to 100 percent of the amount of those unpaid wages or that unpaid overtime compensation as liquidated damages within a period specified by the department in the order.

3. In addition to or in lieu of recovering the liability specified in subd. 1. as provided in subd. 2., any employee for and in behalf of that employee and other employees similarly situated may commence an action to recover that liability in any court of competent jurisdiction. If the court finds that a contractor, subcontractor, or contractor's or subcontractor's agent has failed to pay the prevailing wage rate determined by the department under sub. (3) or has paid less than 1.5 times the hourly basic rate of pay for all hours worked in excess of the prevailing hours of labor, the court shall order the contractor, subcontractor, or agent to pay to any affected employee the amount of his or her unpaid wages or his or her unpaid overtime compensation and an additional amount equal to 100 percent of the amount of those unpaid wages or that unpaid overtime compensation as liquidated damages. 5. No employee may be a party plaintiff to an action under subd. 3. unless the employee consents in writing to become a party and the consent is filed in the court in which the action is brought. Notwithstanding s. 814.04 (1), the court shall, in addition to any judgment awarded to the plaintiff, allow reasonable attorney fees and costs to be paid by the defendant.

BUILDING OR HEAVY CONSTRUCTION

Includes sheltered enclosures with walk-in access for the purpose of housing persons, employees, machinery, equipment or supplies and non-sheltered work such as canals, dams, dikes, reservoirs, storage tanks, etc. A sheltered enclosure need not be "habitable" in order to be considered a building. The installation of machinery and/or equipment, both above and below grade level, does not change a project's character as a building. On-site grading, utility work and landscaping are included within this definition. Residential buildings of four (4) stories or less, agricultural buildings, parking lots and driveways are NOT included within this definition.

SKILLED TRADES

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
101	Acoustic Ceiling Tile Installer Future Increase(s): Add \$1.42/hr on 6/1/2015; Add \$1.42/hr on 6/1/2016.	32.72	16.00	48.72
102	Boilermaker Future Increase(s): Add \$1.50/hr. on 01/01/2016	33.35	28.24	61.59
103	Bricklayer, Blocklayer or Stonemason Future Increase(s): Add \$1.40 on 06/01/2015; Add \$1.45 on 06/06/2016 Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	32.82	18.66	51.48
104	Cabinet Installer Future Increase(s): Add \$1.42/hr on 6/1/2015; Add \$1.42/hr on 6/1/2016.	32.72	16.00	48.72
105	Carpenter Future Increase(s): Add \$1.42/hr on 6/1/2015; Add \$1.42/hr on 6/1/2016. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	32.72	16.00	48.72
106	Carpet Layer or Soft Floor Coverer Future Increase(s): Add \$1.42/hr on 6/1/2015; Add \$1.42/hr on 6/1/2016.	32.72	16.00	48.72
107	Cement Finisher	31.98	12.04	44.02
108	Drywall Taper or Finisher	26.05	18.23	44.28
109	Electrician Future Increase(s): Add \$1.20/hr on 6/1/15; Add \$1.25/hr on 6/1/16. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	34.82	19.67	54.49
110	Elevator Constructor	43.84	27.09	70.93

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
111	Fence Erector	18.00	6.09	24.09
112	Fire Sprinkler Fitter	36.79	18.81	55.60
113	Glazier Future Increase(s): Add \$.75/hr eff. 06/01/2015; Add \$.90/hr eff. 06/01/2016	37.07	14.42	51.49
114	Heat or Frost Insulator	33.43	25.81	59.24
115	Insulator (Batt or Blown) Future Increase(s): Add \$1.42/hr on 6/1/2015; Add \$1.42/hr on 6/1/2016.	32.72	16.00	48.72
116	Ironworker	31.50	20.01	51.51
117	Lather	31.40	15.90	47.30
118	Line Constructor (Electrical)	39.50	17.73	57.23
119	Marble Finisher	16.25	2.32	18.57
120	Marble Mason	32.09	18.04	50.13
121	Metal Building Erector	19.05	8.08	27.13
122	Millwright Future Increase(s): Add \$1.47/hr on 6/1/2015; Add \$1.47/hr on 6/1/2016.	34.44	16.07	50.51
123	Overhead Door Installer	27.46	1.98	29.44
124	Painter	25.75	16.60	42.35
125	Pavement Marking Operator	30.10	17.34	47.44
126	Piledriver Future Increase(s): Add \$1.50/hr on 6/1/2015; Add \$1.60/hr on 6/1/2016. Premium Increase(s): Add \$.65/hr for Piledriver Loftsman; Add \$.75/hr for Sheet Piling Loftsman. DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	30.11	26.51	56.62
127	Pipeline Fuser or Welder (Gas or Utility)	30.83	20.89	51.72
129	Plasterer Future Increase(s): Add \$1.56 on 06/01/2015; Add \$1.61 on 06/01/2016; Add\$1.66 on 06/01/2017	32.65	19.36	52.01
130	Plumber Future Increase(s): Add \$1.80 on 6/1/15	37.57	17.47	55.04

Add \$1.80 on 6/1/15

203

Three or More Axle

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
132	Refrigeration Mechanic Future Increase(s): Add \$1.80 on 6/1/15	44.20	18.26	62.46
133	Roofer or Waterproofer	29.40	11.31	40.71
134	Sheet Metal Worker	34.45	22.54	56.99
135	Steamfitter Future Increase(s): Add \$1.80/hr on 6/1/15.	44.20	18.26	62.46
137	Teledata Technician or Installer Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	22.50	12.74	35.24
138	Temperature Control Installer	42.95	15.04	57.99
139	Terrazzo Finisher	16.25	2.32	18.57
140	Terrazzo Mechanic	31.18	17.35	48.53
141	Tile Finisher	23.85	17.18	41.03
142	Tile Setter	29.81	17.18	46.99
143	Tuckpointer, Caulker or Cleaner	23.60	7.10	30.70
144	Underwater Diver (Except on Great Lakes)	35.40	15.90	51.30
146	Well Driller or Pump Installer	25.32	15.65	40.97
147	Siding Installer	36.17	19.44	55.61
150	Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	30.16	15.11	45.27
151	Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	31.60	26.76	58.36
152	Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	27.65	14.49	42.14
153	Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	27.83	15.01	42.84
154	Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.90	9.83	31.73
	TRUCK DRIVERS			
<u>CODE</u>	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
201	Single Axle or Two Axle	32.89	18.96	51.85

18.00

21.99

39.99

Fringe Benefits Must Be Paid O	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY	HOURLY FRINGE <u>BENEFITS</u> \$		
<u>CODE</u>	TRADE OR OCCUPATION	BASIC RATE <u>OF PAY</u> \$		<u>TOTAL</u> \$	
204	Articulated, Euclid, Dumptor, Off Road Material Hauler Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016.	33.69	19.78	53.47	
205	Pavement Marking Vehicle	20.85	11.02	31.87	
207	Truck Mechanic	18.00	21.99	39.99	

LABORERS

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
301	General Laborer Future Increase(s): Add \$1.35/hr eff. 06/01/2015; Add \$1.25/hr eff. 06/06/2016 Premium Increase(s): Add \$1.00/hr for certified welder; Add \$.25/hr for mason tender	24.97	15.12	40.09
302	Asbestos Abatement Worker	18.00	9.58	27.58
303	Landscaper	18.75	10.26	29.01
310	Gas or Utility Pipeline Laborer (Other Than Sewer and Water)	21.55	14.14	35.69
311	Fiber Optic Laborer (Outside, Other Than Concrete Encased) Premium Increase(s): DOT PREMIUMS: Pay two times the hourly basic rate on New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	18.82	14.16	32.98
314	Railroad Track Laborer	14.50	5.29	19.79
315	Final Construction Clean-Up Worker Future Increase(s): Add \$1.35/hr eff. 06/01/2015; Add \$1.25/hr eff. 06/06/2016	24.97	15.12	40.09

HEAVY EQUIPMENT OPERATORS SITE PREPARATION, UTILITY OR LANDSCAPING WORK ONLY

<u>CODE</u>	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u>	HOURLY FRINGE <u>BENEFITS</u>	<u>TOTAL</u>
501	Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Milling Machine; Boring Machine (Directional, Horizontal or Vertical); Backhoe (Track Type) Having a Mfgr's Rated Capacity of 130,000 Lbs. or Over; Backhoe (Track Type) Having a Mfgr's Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bulldozer or Endloader (Over 40 hp); Compactor (Self-Propelled 85 Ft Total Drum Width & Over, or Tractor Mounted, Towed & Light Equipment); Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Crane, Shovel, Dragline, Clamshells; Forklift (Machinery Moving or Steel Erection, 25 Ft & Over); Gradall (Cruz-Aire Type); Grader or Motor Patrol; Master Mechanic; Mechanic or Welder; Robotic Tool Carrier (With or Without Attachments); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Tractor or Truck Mounted Hydraulic Backhoe; Tractor or Truck Mounted Hydraulic Crane (10 Tons or Under); Tractor (Scraper, Dozer, Pusher, Loader); Trencher (Wheel Type or Chain Type Having Over 8 Inch Bucket). Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016.		\$	\$ 53.47
502	Backfiller; Broom or Sweeper; Bulldozer or Endloader (Under 40 hp); Environmental Burner; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Jeep Digger; Screed (Milling Machine); Skid Rig; Straddle Carrier or Travel Lift; Stump Chipper; Trencher (Wheel Type or Chain Type Having 8 Inch Bucket & Under). Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016.	33.69	19.78	53.47
503	Air Compressor (&/or 400 CFM or Over); Augers (Vertical & Horizontal); Compactor (Self-Propelled 84 Ft Total Drum Width & Under, or Tractor Mounted, Towed & Light Equipment); Crusher, Screening or Wash Plant; Farm or Industrial Type Tractor; Forklift; Generator (&/or 150 KW or Over); Greaser; High Pressure Utility Locating Machine (Daylighting Machine); Mulcher; Oiler; Post Hole Digger or Driver; Pump (3 Inch or Over) or Well Points; Refrigeration Plant or Freeze Machine; Rock, Stone Breaker; Skid Steer Loader (With or Without Attachments); Vibratory Hammer or Extractor, Power Pack. Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016.	31.62	19.78	51.40
504	Work Performed on the Great Lakes Including Diver; Wet Tender or Hydraulic Dredge Engineer.	41.65	21.71	63.36
505	Work Performed on the Great Lakes Including Crane or Backhoe Operator; Assistant Hydraulic Dredge Engineer; Hydraulic Dredge Leverman or Diver's Tender; Mechanic or Welder; 70 Ton & Over Tug Operator. Premium Increase(s): Add \$.50/hr for Friction Crane, Lattice Boom or Crane Certification (CCO).	41.65	21.71	63.36

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY BASIC RATE	HOURLY FRINGE		
<u>CODE</u>	TRADE OR OCCUPATION	OF PAY \$	<u>BENEFITS</u> \$	<u>TOTAL</u> \$	
506	Work Performed on the Great Lakes Including Deck Equipment Operator or Machineryman (Maintains Cranes Over 50 Tons or Backhoes 115,000 Lbs. or More); Tug, Launch or Loader, Dozer or Like Equipment When Operated on a Barge, Breakwater Wall, Slip, Dock or Scow, Deck Machinery.	35.72	17.85	53.57	
507	Work Performed on the Great Lakes Including Deck Equipment Operator, Machineryman or Fireman (Operates 4 Units or More or Maintains Cranes 50 Tons or Under or Backhoes 115,000 Lbs. or Under); Deck Hand, Deck Engineer or Assistant Tug Operator; Off Road Trucks - Great Lakes ONLY.	6	20.40	55.86	

HEAVY EQUIPMENT OPERATORS EXCLUDING SITE PREPARATION, UTILITY, PAVING LANDSCAPING WORK

<u>CODE</u>	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
508	Boring Machine (Directional); Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity of Over 4,000 Lbs., Crane With Boom Dollies; Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Master Mechanic. Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016. Premium Increase(s): Add \$.50/hr for >200 Ton; Add \$1/hr at 300 Ton; Add \$1.50/hr at 400 Ton; Add \$2/hr at 500 Ton & Over.	36.67	19.78	56.45
509	Backhoe (Track Type) Having a Mfgr's Rated Capacity of 130,000 Lbs. or Over; Boring Machine (Horizontal or Vertical); Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With A Lifting Capacity Of 4,000 Lbs. & Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Pile Driver; Versi Lifts, Tri-Lifts & Gantrys (20,000 Lbs. & Over). Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016. Premium Increase(s): Add \$.25/hr for all >45 Ton lifting capacity cranes.		19.78	55.20
510	Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump (Over 46 Meter), Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine Concrete Spreader & Distributor; Dredge (NOT Performing Work on the Great Lakes); Forklift (Machinery Moving or Steel Erection, 25 Ft & Over); Gradall (Cruz-Aire Type); Hydro-Blaster (10,000 PSI or Over); Milling Machine; Skid Rig; Traveling Crane (Bridge Type). Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016.		19.78	54.00

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY BASIC RATE	HOURLY FRINGE	
<u>CODE</u>	TRADE OR OCCUPATION	OF PAY \$	BENEFITS	<u>TOTAL</u> \$
511	Air, Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Bulldozer or Endloader (Over 40 hp); Compactor (Self-Propelled 85 Ft Total Drum Width & Over, or Tractor Mounted, Towed & Light Equipment); Concrete Pump (46 Meter & Under), Concrete Conveyor (Rotec or Bidwell Type); Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Environmental Burner; Gantrys (Under 20,000 Lbs.); Grader or Motor Patrol; High Pressure Utility Locating Machine (Daylighting Machine); Manhoist; Material or Stack Hoist; Mechanic or Welder; Railroad Track Rail Leveling Machine, Tie Placer, Extractor, Tamper, Stone Leveler or Rehabilitation Equipment; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yd or More Capacity; Screed (Milling Machine); Sideboom; Straddle Carrier or Travel Lift; Tining or Curing Machine; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Tractor or Truck Mounted Hydraulic Crane (10 Tons or Under); Trencher (Wheel Type or Chain Type Having Over 8-Inch Bucket). Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016.	33.69	19.78	53.47
512	Backfiller; Broom or Sweeper; Bulldozer or Endloader (Under 40 hp); Compactor (Self-Propelled 84 Ft Total Drum Width & Under, or Tractor Mounted, Towed & Light Equipment); Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Conveyor System; Concrete Finishing Machine (Road Type); Fireman (Pile Driver & Derrick NOT Performing Work on the Great Lakes); Grout Pump; Hoist (Tugger, Automatic); Industrial Locomotives; Jeep Digger; Lift Slab Machine; Mulcher; Roller (Rubber Tire, 5 Ton or Under); Screw or Gypsum Pumps; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Stump Chipper; Trencher (Wheel Type or Chain Type Having 8-Inch Bucket & Under); Winches & A-Frames. Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016.	31.62	19.78	51.40
513	Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Boatmen (NOT Performing Work on the Great Lakes); Boiler (Temporary Heat); Crusher, Screening or Wash Plant; Elevator; Farm or Industrial Type Tractor; Fireman (Asphalt Plant NOT Performing Work on the Great Lakes); Forklift; Generator (&/or 150 KW or Over); Greaser; Heaters (Mechanical); Loading Machine (Conveyor); Oiler; Post Hole Digger or Driver; Prestress Machine; Pump (3 Inch or Over) or Well Points; Refrigeration Plant or Freeze Machine; Robotic Tool Carrier (With or Without Attachments); Rock, Stone Breaker; Skid Steer Loader (With or Without Attachments); Vibratory Hammer or Extractor, Power Pack. Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016.	30.99	19.78	50.77
514	Gas or Utility Pipeline, Except Sewer & Water (Primary Equipment). Future Increase(s): Add \$1/hr on 6/1/2015; Add \$1/hr on 5/30/2016.	36.34	22.14	58.48
515	Gas or Utility Pipeline, Except Sewer & Water (Secondary Equipment). Future Increase(s): Add \$1.65/hr on 6/1/2015.	33.12	19.35	52.47
516	Fiber Optic Cable Equipment	28.89	17.95	46.84

SEWER, WATER OR TUNNEL CONSTRUCTION

Includes those projects that primarily involve public sewer or water distribution, transmission or collection systems and related tunnel work (excluding buildings).

SKILLED TRADES

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
103	Bricklayer, Blocklayer or Stonemason	32.09	18.04	50.13
105	Carpenter Future Increase(s): Add \$1.50/hr on 6/1/2015; Add \$1.65/hr on 6/1/2016. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	34.13	20.61	54.74
107	Cement Finisher Future Increase(s): Add \$1.87 on 6/1/15; Add \$1.75 on 6/1/16. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.40/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.	35.18	16.78	51.96
109	Electrician Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	33.93	22.77	56.70
111	Fence Erector	18.00	6.09	24.09
116	Ironworker	31.50	20.01	51.51
118	Line Constructor (Electrical)	39.50	17.73	57.23
125	Pavement Marking Operator	30.10	17.34	47.44
126	Piledriver	29.56	25.71	55.27
130	Plumber	21.50	0.00	21.50
135	Steamfitter	42.95	17.81	60.76
137	Teledata Technician or Installer	22.25	12.24	34.49
143	Tuckpointer, Caulker or Cleaner	23.60	7.10	30.70
144	Underwater Diver (Except on Great Lakes)	35.40	15.90	51.30

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY BASIC RATE	HOURLY FRINGE		
<u>CODE</u>	TRADE OR OCCUPATION	OF PAY \$	BENEFITS	<u>TOTAL</u> \$	
146	Well Driller or Pump Installer	25.32	15.65	40.97	
150	Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	35.55	15.57	51.12	
151	Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	31.60	15.19	46.79	
152	Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	27.65	13.44	41.09	
153	Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	25.68	13.28	38.96	
154	Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.75	12.97	34.72	

TRUCK DRIVERS

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked		HOURLY	
<u>CODE</u>	TRADE OR OCCUPATION	BASIC RATE <u>OF PAY</u> \$	FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
201	Single Axle or Two Axle Future Increase(s): Add \$1.15/hr on 6/1/2015. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	25.18	18.31	43.49
203	Three or More Axle	19.50	4.97	24.47
204	Articulated, Euclid, Dumptor, Off Road Material Hauler	32.89	18.96	51.85
205	Pavement Marking Vehicle	20.85	11.02	31.87
207	Truck Mechanic	19.50	4.97	24.47

LABORERS

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked		CRATE FRINGE <u>Y BENEFITS T</u>	
<u>CODE</u>	TRADE OR OCCUPATION	OF PAY \$		<u>TOTAL</u> \$
301	General Laborer Future Increase(s): Add \$1.35/hr eff. 06/01/2015; Add \$1.25/hr eff. 06/06/2016 Premium Increase(s): Add \$.20 for blaster, bracer, manhole builder, caulker, bottomman and power tool; Add \$.55 for pipelayer; Add \$1.00 for tunnel work 0-15 lbs. compressed air; Add \$2.00 for over 15-30 lbs. compressed air; Add \$3.00 for over 30 lbs. compressed air.	26.34	15.13	41.47
303	Landscaper	39.43	0.00	39.43

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
304	Flagperson or Traffic Control Person	31.95	0.00	31.95
311	Fiber Optic Laborer (Outside, Other Than Concrete Encased)	18.33	13.65	31.98
314	Railroad Track Laborer	14.50	5.29	19.79

HEAVY EQUIPMENT OPERATORS SEWER, WATER OR TUNNEL WORK

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
521	Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Master Mechanic; Pile Driver. Future Increase(s): Add \$1.55/hr on 6/1/2015. Premium Increase(s): Add \$.25/hr for operating tower crane.	37.24	20.10	57.34
522	Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Boring Machine (Directional); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump (Over 46 Meter), Concrete Conveyor (Rotec or Bidwell Type); Concrete Spreader & Distributor; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With a Lifting Capacity of 4,000 Lbs. & Under; Dredge (NOT Performing Work on the Great Lakes); Milling Machine; Skic Rig; Telehandler; Traveling Crane (Bridge Type). Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016.		19.78	54.00
523	Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Boring Machine (Horizontal or Vertical); Bulldozer or Endloader (Over 40 hp); Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Concrete Pump (46 Meter & Under), Concrete Conveyor (Roted or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Hydro-Blaster (10,000 PSI or Over); Manhoist; Material or Stack Hoist; Mechanic or Welder; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yd or More Capacity; Screed (Milling Machine); Sideboom; Straddle Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Tractor or Truck Mounted Hydraulic Crane (10 Tons or Under); Trencher (Wheel Type or Chain Type Having Over 8-Inch Bucket). Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016.		19.78	53.47

				~go o
<u>CODE</u>	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
524	Backfiller; Broom or Sweeper; Bulldozer or Endloader (Under 40 hp); Compactor (Self-Propelled 85 Ft Total Drum Width & Over, or Tractor Mounted, Towed & Light Equipment); Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Conveyor System; Concrete Finishing Machine (Road Type); Environmental Burner; Fireman (Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Hoist (Tugger, Automatic); Grout Pump; Jeep Digger; Lift Slab Machine; Mulcher; Power Subgrader; Pump (3 Inch or Over) or Well Points; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Screw or Gypsum Pumps; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Stump Chipper; Tining or Curing Machine; Trencher (Wheel Type or Chair Type Having 8-Inch Bucket & Under); Winches & A-Frames.		18.96	49.78
525	Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Compactor (Self-Propelled 84 Ft Total Drum Width & Under, or Tractor Mounted, Towed & Light Equipment); Crusher, Screening or Wash Plant; Farm or Industrial Type Tractor; Fireman (Asphalt Plant NOT Performing Work on the Great Lakes); Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Loading Machine (Conveyor); Post Hole Digger or Driver; Refrigeration Plant or Freeze Machine; Rock, Stone Breaker; Skid Steer Loader (With or Without Attachments); Vibratory Hammer or Extractor, Power Pack.	30.69	18.46	49.15
526	Boiler (Temporary Heat); Forklift; Greaser; Oiler.	30.19	18.96	49.15
527	Work Performed on the Great Lakes Including Diver; Wet Tender or Hydraulic Dredge Engineer.	41.65	21.71	63.36
528	Work Performed on the Great Lakes Including 70 Ton & Over Tug Operator; Assistant Hydraulic Dredge Engineer; Crane or Backhoe Operator; Hydraulic Dredge Leverman or Diver's Tender; Mechanic or Welder.	41.65	21.71	63.36
529	Work Performed on the Great Lakes Including Deck Equipment Operator or Machineryman (Maintains Cranes Over 50 Tons or Backhoes 115,000 Lbs. or More); Tug, Launch or Loader, Dozer or Like Equipment When Operated on a Barge, Breakwater Wall, Slip, Dock or Scow, Deck Machinery.	35.72	17.85	53.57
530	Work Performed on the Great Lakes Including Deck Equipment Operator; Machineryman or Fireman (Operates 4 Units or More or Maintains Cranes 50 Tons or Under or Backhoes 115,000 Lbs. or Under), Deck Hand, Deck Engineer or Assistant Tug Operator; Off Road Trucks - Great Lakes ONLY.		20.40	55.86

Page 15 of 21

LOCAL STREET OR MISCELLANEOUS PAVING CONSTRUCTION

Includes roads, streets, alleys, trails, bridges, paths, racetracks, parking lots and driveways (except residential or agricultural), public sidewalks or other similar projects (excluding projects awarded by the Wisconsin Department of Transportation).

	SKILLED TRADES				
<u>CODE</u>	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$	
103	Bricklayer, Blocklayer or Stonemason	32.09	18.04	50.13	
105	Carpenter Future Increase(s): Add \$1.42/hr on 6/1/2015; Add \$1.42/hr on 6/1/2016. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	32.72	16.00	48.72	
107	Cement Finisher Future Increase(s): Add \$1.87 on 6/1/15; Add \$1.75 on 6/1/16. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.40/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.	35.18	16.78	51.96	
109	Electrician	35.72	19.17	54.89	
111	Fence Erector	18.00	6.09	24.09	
116	Ironworker	31.50	20.01	51.51	
118	Line Constructor (Electrical)	39.50	17.73	57.23	
124	Painter	25.75	16.60	42.35	
125	Pavement Marking Operator	30.10	17.34	47.44	
126	Piledriver	29.56	25.71	55.27	
133	Roofer or Waterproofer	29.40	11.31	40.71	
137	Teledata Technician or Installer	22.25	12.24	34.49	
143	Tuckpointer, Caulker or Cleaner	23.60	7.10	30.70	
144	Underwater Diver (Except on Great Lakes)	35.40	15.90	51.30	
150	Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	35.55	15.57	51.12	

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked		HOURLY	
<u>CODE</u>	TRADE OR OCCUPATION	BASIC RATE <u>OF PAY</u> \$	FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
151	Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	31.60	15.19	46.79
152	Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	27.65	13.44	41.09
153	Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	25.68	13.28	38.96
154	Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.75	12.97	34.72

TRUCK DRIVERS

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
201	Single Axle or Two Axle Future Increase(s): Add \$1.15/hr on 6/1/2015. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	25.18	18.31	43.49
203	Three or More Axle	16.00	0.00	16.00
204	Articulated, Euclid, Dumptor, Off Road Material Hauler Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016.	33.69	19.78	53.47
205	Pavement Marking Vehicle	20.85	11.02	31.87
206	Shadow or Pilot Vehicle	24.37	17.77	42.14
207	Truck Mechanic	16.00	0.00	16.00

LABORERS

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY BASIC RATE	HOURLY FRINGE	
<u>CODE</u>	TRADE OR OCCUPATION	OF PAY \$	BENEFITS \$	<u>TOTAL</u> \$
301	General Laborer	29.32	12.44	41.76
303	Landscaper Future Increase(s): Add \$1.05/hr eff. 06/01/2015; Add \$1.00/hr eff.	30.13	15.14	45.27

06/01/2016; Add \$1.00/hr eff. 06/01/2017 Premium Increase(s):

<u>CODE</u>	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u> DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup ofter event firms paring)	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$	
304	after such time period). Flagperson or Traffic Control Person	19.06	14.29	33.35	
304		19.00	14.29		
311	Fiber Optic Laborer (Outside, Other Than Concrete Encased)	18.33	13.65	31.98	
314	Railroad Track Laborer	14.50	5.29	19.79	
HEAVY EQUIPMENT OPERATORS CONCRETE PAVEMENT OR BRIDGE WORK					
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$	

541	Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Master Mechanic. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http://www.dot.wi.gov/busine	37.72	21.15	58.87
	this night work premium at: http://www.dot.wi.gov/busine ss/civilrights/laborwages/pwc.htm.			

<u>CODE</u>	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
542	Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With a Lifting Capacity of 4,000 Lbs. & Under; Crane, Tower Crane Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http://www.dot.wi.gov/busine ss/civilrights/laborwages/pwc.htm.	37.22	21.15	58.37
543	Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Automatic Subgrader (Concrete); Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Boring Machine (Directional, Horizontal or Vertical); Bridge (Bidwell) Paver; Bulldozer or Endloader; Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Manhoist; Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Straddle Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A-Frames.	35.72	17.85	53.57

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
544	 Backfiller; Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Jeep Digger Joint Sawer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler; Tining or Curing Machine. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http://www.dot.wi.gov/busine ss/civilrights/laborwages/pwc.htm. 		21.15	57.61
545	Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack.	35.17	20.40	55.57
546	Fiber Optic Cable Equipment.	28.89	17.95	46.84
547	Work Performed on the Great Lakes Including Diver; Wet Tender or Hydraulic Dredge Engineer.	41.65	21.71	63.36
548	Work Performed on the Great Lakes Including 70 Ton & Over Tug Operator; Assistant Hydraulic Dredge Engineer; Crane or Backhoe Operator; Hydraulic Dredge Leverman or Diver's Tender; Mechanic or Welder.	41.65	21.71	63.36
549	Work Performed on the Great Lakes Including Deck Equipment Operator or Machineryman (Maintains Cranes Over 50 Tons or Backhoes 115,000 Lbs. or more); Tug, Launch or Loader, Dozer or Like Equipment When Operated on a Barge, Breakwater Wall, Slip, Dock or Scow, Deck Machinery.	35.72	17.85	53.57
550	Work Performed on the Great Lakes Including Deck Equipment Operator; Machineryman or Fireman (Operates 4 Units or More or Maintains Cranes 50 Tons or Under or Backhoes 115,000 Lbs. or Under); Deck Hand, Deck Engineer or Assistant Tug Operator; Off Road Trucks - Great Lakes ONLY.	6	20.40	55.86

HEAVY EQUIPMENT OPERATORS ASPHALT PAVEMENT OR OTHER WORK

<u>CODE</u>	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
551	Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self Erecting Tower Crane With a Lifting Capacity of Over 4,000 Lbs., Crane With Boom Dollies; Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads and/or Jib Lengths Measuring 176 Ft or Over; Master Mechanic.	36.72	20.40	57.12
552	Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With a Lifting Capacity Of 4,000 Lbs. & Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http://www.dot.wi.gov/busine ss/civilrights/laborwages/pwc.htm.		21.15	58.37
553	Air, Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boring Machine (Directional, Horizontal or Vertical); Bulldozer or Endloader; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Conveyor System; Concrete Laser/Screed; Concrete Slipform Placer Curb & Gutter Machine; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Manhoist; Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Railroad Track Rail Leveling Machine, Tie Placer, Extractor, Tamper, Stone Leveler or Rehabilitation Equipment; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A-Frames. Future Increase(s): Add \$1.60/hr on 6/2/2015; Add \$1.60/hr on 6/3/2016.		19.78	53.47

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY BASIC RATE	HOURLY	
CODE	TRADE OR OCCUPATION	OF PAY \$	FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
554	Backfiller; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Jeep Digger; Joint Sawer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self-Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017.	36.17	20.80	56.97
555	Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http://www.dot.wi.gov/busine ss/civilrights/laborwages/pwc.htm.	36.17	21.15	57.32
556	Fiber Optic Cable Equipment.	27.89	17.20	45.09

Department of Workforce Development Equal Rights Division P.O. Box 8928 Madison, WI 53708-8928 Telephone: (608) 266-6860 Fax: (608) 267-4592 TTY: (608) 264-8752



Scott Walker, Governor Reginald J. Newson, Secretary

The documents following the Prevailing Wage Rate Determination consist of eighteen pages (including this one) of various forms/documents that will be used throughout the completion of the project. The chart below lists the form number, form/document name, the party who uses the document, and the document's number of pages. If you have any questions regarding these forms please call the Prevailing Wage Office at (608)266-6861.

ERD Form Number	Form Name	Party Who Uses the Form	Pages
	Prevailing Wage - Public Entity Project Owners	Explanation of project owner responsibilities	2
16056	Post the White Sheet	Contracting agency	1
10908	Consolidated List of Debarred Contractors	Any party contracting someone to complete work on a prevailing wage project	3
· · ·	Prevailing Wage – Contractors	Explanation of contractor responsibilities	2
7777	Disclosure of Ownership	Contractors that meet the criteria set out in (3)(A)&(B) of the form	1
5724	Prime Contractor Affidavit of Compliance	Prime contractor files with contracting agency upon completion of the work before receiving final payment	2
10584	Agent or Subcontractor Affidavit of Compliance	Subcontractors file with their awarding contractor upon completion of their work on the project before receiving final payment	2
10880	Request to Employ Subjourneyperson	Contractors wishing to employ a subjourneyperson(s)	1
	Additional General Prevailing Wage Law Information	General information for public entity or any other interested party	3

10/01/2014

 Department of Workforce Development

 Equal Rights Division

 P.O. Box 8928

 Madison, WI

 53708-8928

 Telephone:

 (608) 266-6860

 Fax:

 (608) 267-4592

 TTY:

 (608) 264-8752

STATE OF WISCONSIN

Scott Walker, Governor Reginald J. Newson, Secretary

PREVAILING WAGE – Public Entity Project Owners

Any public works project that has a total estimated project cost that equals or exceeds single-trade or multiple-trade project thresholds requires a prevailing wage rate determination issued by the Department of Workforce Development (DWD). Public works include erecting, constructing, remodeling, repairing, demolishing, alterations, painting and decorating projects for a local governmental unit or state agency. State law excludes minor service or maintenance work, warranty work, or work under a supply-and-installation contract. There is a statutory definition for most of these exclusions. The prevailing wage law that applies to local governmental units is §66.0903, Wis. Stats. The prevailing wage law that applies to state agencies is §103.49, Wis. Stats. The applicable administrative rules for all public entities are DWD 290 and DWD 294, Wis. Adm. Code.

Thresholds

- A "single-trade project of public works" means a project in which a single trade accounts for 85% or more of the total labor cost of the project. The single trade threshold is \$48,000.
- A "multiple-trade project of public works" means a project in which no single trade accounts for 85% or more of the total labor cost of the project.
 - (a) The multiple-trade threshold is \$100,000, unless a municipality falls under the description in (b).
 - (b) The multiple-trade threshold of \$234,000 applies to public works projects erected, constructed, repaired, remodeled, or demolished by a private contractor for •a city or village with a population less than 2500 or •a town.

A local governmental unit or state agency that has a public works project that equals or exceeds the prevailing wage thresholds must do all of the following:

 Request a prevailing wage rate determination for the project from DWD at least 30 days before soliciting bids or negotiating contracts. An Application for Prevailing Wage Rate Determination is available on the DWD website: <u>http://dwd.wisconsin.gov/er/prevailing wage rate/default.htm</u>

To avoid waiting for a project determination use the on-line application system that permits the user to generate a determination immediately and save all documents in PDF form to the user's computer. Use this project determination on line application at the following address:

http://dwd.wisconson.gov/er/prevailing wage rate/pw online determinations.htm

- Tell potential contractors the project is subject to state prevailing wage law when soliciting bids.
- Include the prevailing wage rate determination in the construction contract, or if there is no written contract, provide a copy of the project determination to each prime contractor.
- Award contracts to contractors who do not appear on the "Consolidated List of Debarred Contractors."
- Notify contractors that they are required to have a written substance abuse testing program in place that fulfills the requirements of §103.503, Wis. Stats., before commencing work on the prevailing wage project.
- Post the prevailing wage rate determination on the project site. (This document is often referred to as "the white sheet.")
- Notify project contractors that if DWD finds that a contractor violated the prevailing wage law, DWD will assess liquidated damages of 100% of the wages owed to employees.
- Obtain an Affidavit of Compliance from each prime contractor before making final payment for the project.

If the total estimated cost of the project exceeds the prevailing wage thresholds, a local governmental unit or state agency also must obtain a prevailing wage rate determination under the following circumstances:

- when a completed facility is leased, purchased, lease-purchased or otherwise acquired by or dedicated to a public entity in lieu of the public entity contracting for the project,
- when one public entity does work for another public entity,
- when a *private* entity will construct a road, street, bridge, sanitary sewer or water main project and dedicate it to a local governmental unit or the state for its ownership or maintenance (except for some residential subdivisions).

For more information, visit the prevailing wage website: <u>http://dwd.wisconsin.gov/er/prevailing wage rate/default.htm</u>. For further assistance, call the Equal Rights Division at 608-266-6861 and ask for prevailing wage.

POST THE WHITE SHEET

As the public entity receiving this prevailing wage rate determination, YOU ARE REQUIRED by law to post the prevailing wage rate determination (i.e., white sheet) in at least one conspicuous and easily accessible place on the project site that is available to all construction workers. The white sheet must remain posted from the onset of the project until all construction labor on the project has been completed.

[See, Wis. Admin. Code §DWD 290.12(1)]

Posting the white sheet inside the general contractor's trailer does not meet this requirement. That placement is not available/accessible to all workers and is not a location over which you have control.

If you have questions about posting, please call (608)266-6861 and ask for prevailing wage intake.

lssue No. 63 Page 1 of 3

Consolidated List of Debarred Contractors Prepared and Issued By State of Wisconsin - Department of Workforce Development

November 1, 2014

determined or established for a state or local public works project. No state agency, local governmental unit or owner or developer may knowingly solicit "debarred" from the "effective date" through the "termination date" indicated for that contractor. Questions regarding this list should be addressed to Julie Eckenwalder, Equal Rights Division, P. O. Box 8928, Madison, WI 53708 or call (608) 266-3148. Deaf, hearing or speech-impaired callers may contact This list has been prepared in accordance with the provisions of §§66.0903(12) and 103.49(7), Wis. Stats., and Chapter DWD 294 of the Wisconsin Administrative Code. All contractors on this list were found to have committed a "debarable offense" related to certain labor standard provisions bids from, negotiate with or award any contracts to or approve or allow any subcontracts with a debarred contractor, including all divisions, affiliates or debarred contractor must remain on this list for a period of three (3) years from the termination date indicated below. The contractor is, however, only other organizational elements of such contractor that are engaged in construction business activities, until the debarment is terminated. The name of each the department by calling its TDD number (608) 264-8752.

Name of Contractor	Address	<u>Effective</u>	<u>Termination</u>	Cause	Date of	Limitations/
A-1 Duran Roofing & Insulation Services, Inc.	3700 N Fratney St Milwaukee, WI 53212 or 8095 NW 64 th St Miami, FL 33166	<u>Uate</u> 11/1/14	10/31/17	1, 2 and 4	2011- 2012	None
Abel, Mike	See, Abel Electric, Inc			т		
Abel Electric, Inc	3385 Belmar Rd Green Bay, WI 54313	9/1/12	8/31/15	-	2011	None
Arnie Christiansen Mason Contractors, LLC	2304 65 th Dr Franksville, WI 53126	9/1/14	8/31/16	1, 2 and 4	2011	None
Atkins, Scott	See, Freedom Insulation, Inc					
Boecker, Roger	See, R-Way Pumping, Inc					
Brechtl, Mark G	See, Ecodec, Inc			·		
Cargill Heating and Air Conditioning Company, Inc	3049 Edgewater La La Crosse, WI 54603	3/1/14	2/28/17	1 and 2	2011	None
Castlerock Commercial Construction, Inc	PO Box 11699 Milwaukee, WI 53211-0699	2/1/12	1/31/15	1, 2 and 4	2009 & 2010	None

ERD-10908-P (R. 11/2014)

しからい しいちゅう ひょうひょう ひのい そうかんちょう アンド

lssue No. 63		Page 2 of 3				November 1, 2014
<u>Name of Contractor</u>	Address	<u>Effective</u>	<u>Termination</u> Date	<u>Cause</u>	<u>Date of</u> Violation(s)	Limitations/
Christiansen, Andy	See, Arnie Christiansen Mason Contractors, LLC			2000		
Christiansen, Arnold	See, Arnie Christiansen Mason Contractors, LLC					
Darnick, Gregory L	See, Darnick Trucking, LLC					
Darnick Trucking, LLC	W914 County Rd V Berlin, WI 54923	11/1/14	10/31/15	1, 2 and 4	2012 & 2013	None
Dem/Ex Group, Inc	805 S Adams St Manito, IL 61546	12/1/11	11/30/14	1 and 2	2010	None
Duran, Bernardo	<i>See</i> , A-1 Duran Roofing & Insulation Services and RRS2 Inc					
Ecodec, Inc	5106 Wintergreen Dr Madison, WI 53704	10/1/14	9/30/17	Ţ	2011 & 2012	None
Fisher, Ed &/or Fisher, Rhonda	See, Dem/Ex Group, Inc					
Freedom Insulation, Inc	117925 219th Ave Chippewa Falls, WI 54729	9/1/11	8/31/14		2008- 2010	None
Galstad, Michael E (aka Michael Earl Galstad)	See, Cargill Heating and Air Conditioning Company, Inc					
Gjolaj, Ded	See, Horizon Bros Painting Corp				·	
Horizon Bros Painting Corp	1053 Kendra La Howell, MI 48843	10/1/14	9/30/16	4	2012	None
JT Roofing, Inc	350 Tower Dr Saukville, WI 53080	6/1/12	5/31/15	1, 2 and 4	2007 & 2008	None

63
No.
lssue

Page 3 of 3

November 1, 2014

		0				,
Name of Contractor	Address	<u>Effective</u>	Termination	Cause	<u>Date of</u> Violation(s)	Limitations/
Jinkins, Richard	See, Castlerock Commercial Construction, Inc	nate		2006	1611019	Deviauons
Oden, Cassie	See, A-1 Duran Roofing & Insulation Services and RRS2 Inc					
Ofstie, Darin	See, Precision Excavating and Grading, LLC					
Peret, Robert	See, A-1 Duran Roofing & Insulation Services and RRS2 Inc					
Precision Excavating and Grading, LLC or Precision Excavating Enterprises, LLC	2104 Pierce Saint Croix Rd Baldwin, WI 54002	5/1/11	4/30/14	1, 2 and 4	2006- 2008	None
R-Way Pumping, Inc	3023 Lake Maria Rd Freeport, MN 56331	3/1/12	2/28/15	1, 2 and 4	2008	None
RRS2 Inc	133 N Jackson St, #427 Milwaukee, WI 53202 or 1313 N Franklin PI, #805 Milwaukee, WI 53202	11/1/14	10/31/17	1, 2 and 4	2011- 2012	None
Thull, Gerald T	See, JT Roofing, Inc					
Cause Code: 1 = Failure to P	1 = Failure to Pay Straight Time 2 = Failure to Pay Overtime	ay Overtime	3 = Kickback		4 = Payroll Records.	

Department of Workforce Development Equal Rights Division P.O. Box 8928 Madison, WI 53708-8928 Telephone: (608) 266-6860 Fax: (608) 267-4592 TTY: (608) 264-8752

STATE OF WISCONSIN

Scott Walker, Governor Reginald J. Newson, Secretary

PREVAILING WAGE – Contractors

Any public works project that has a total estimated project cost that equals or exceeds prevailing wage project thresholds requires a prevailing wage rate determination issued by the Department of Workforce Development (DWD). Public works include erecting, constructing, remodeling, repairing, demolishing, alterations, painting and decorating projects for a local governmental unit or state agency. State law excludes minor service or maintenance work, warranty work, or work under a supply-and-installation contract. There is a statutory definition for most of these exclusions. The prevailing wage laws that apply to local governmental units and their contractors are §§66.0903 and 103.503, Wis. Stats. The prevailing wage laws that apply to state agencies and their contractors are §§103.49 and 103.503, Wis. Stats. The applicable administrative rules for all prevailing wage projects are DWD 290 and DWD 294, Wis. Adm. Code. These laws include provisions that apply to all contractors and subcontractors working on prevailing wage projects.

Any contractor or subcontractor working on a local governmental unit or state agency's public works project that equals or exceeds current prevailing wage project thresholds must do all of the following:

- Receive and review the project's prevailing wage rate determination (i.e., white sheet).
- Tell subcontractors the project is subject to state prevailing wage law and include the prevailing wage rate determination in the construction contract, or if there is no written contract, provide a copy of the project determination to each subcontractor.
- Hire subcontractors who do not appear on the "Consolidated List of Debarred Contractors."
- Have a written substance abuse testing program in place that fulfills the requirements of §103.503, Wis. Stats., before commencing work on the project.

- Notify subcontractors that if DWD finds that a contractor or subcontractor violated the prevailing wage law, DWD will assess liquidated damages of 100% of the wages owed to employees.
- Apply to DWD for subjourney wage rates prior to employing these individuals on the project.
- Receive and retain a completed Affidavit of Compliance from each subcontractor brought on to the project before providing final payment to those subcontractors.
- Submit a completed Affidavit of Compliance to the contractor who brought the subcontractor on to the project before receiving final payment for the project.
- Maintain payroll records for 3 years that comply with §§66.0903(10)(a) or 103.49(5)(a), Stats. and DWD 274.06.
- Respond to requests from DWD or the project owner to provide payroll records and/or respond to prevailing wage complaints filed by employees or third parties.

For more information, visit the prevailing wage website: <u>http://dwd.wisconsin.gov/er/prevailing wage rate/default.htm</u>. For further assistance, call the Equal Rights Division at 608-266-6861 and ask for prevailing wage.

Contractors – 02/14-JE

State of Wisconsin Department of Workforce Development Equal Rights Division

Disclosure of Ownership

The statutory authority for the use of this form is prescribed in Sections 66.0903(12)(d), 66.0904(10)(d) and 103.49(7)(d), Wisconsin Statutes.

The use of this form is mandatory. The penalty for failing to complete this form is prescribed in Section 103.005(12), Wisconsin Statutes.

Personal information you provide may be used for secondary purposes [Privacy Law, s. 15.04(1) (m), Wisconsin Statutes].

- (1) On the date a contractor submits a bid to or completes negotiations with a state agency, local governmental unit, or developer, investor or owner on a project subject to Section 66.0903, 66.0904 or 103.49, Wisconsin Statutes, the contractor shall disclose to such state agency, local governmental unit, or developer, investor or owner, the name of any "other construction business," which the contractor, or a shareholder, officer or partner of the contractor, owns or has owned within the preceding three (3) years.
- (2) The term "other construction business" means any business engaged in the erection, construction, remodeling, repairing, demolition, altering or painting and decorating of buildings, structures or facilities. It also means any business engaged in supplying mineral aggregate, or hauling excavated material or spoil as provided by Sections 66.0903(3), 66.0904(2), 103.49(2) and 103.50(2), Wisconsin Statutes.
- (3) This form must ONLY be filed, with the state agency project owner, local governmental unit project owner, or developer, investor or owner of a publicly funded private construction project that will be awarding the contract, if **both** (A) and (B) are met.

(A) and (B) are met.

- (A) The contractor, or a shareholder, officer or partner of the contractor:
 - (1) Owns at least a 25% interest in the "other construction business," indicated below, on the date the contractor submits a bid or completes negotiations; or
 - (2) Has owned at least a 25% interest in the "other construction business" at any time within the preceding three
 (3) years.
- (B) The Wisconsin Department of Workforce Development (DWD) has determined that the "other construction business" has failed to pay the prevailing wage rate or time and one-half the required hourly basic rate of pay, for hours worked in excess of the prevailing hours of labor, to any employee at any time within the preceding three (3) years.

Other Construction Business

Business Name			
Street Address or P O Box	City	State	Zip Code
Business Name			
Street Address or P O Box	City	State	Zip Code
Business Name			
Street Address or P O Box	City	State	Zip Code
Business Name			
Street Address or P O Box	City	State	Zip Code
I hereby state under penalty of perjury that the in accurate according to my knowledge and belief.	formation, contained in this doc	ument, is tru	e and
Print the Name of Authorized Officer			
Authorized Officer Signature	Date Signed		
Corporation, Partnership or Sole Proprietorship Name	kum,		
Street Address or P O Box	City	State	Zip Code

If you have any questions call (608) 266-6861

State of Wisconsin Department of Workforce Development Equal Rights Division

Prime Contractor Affidavit of Compliance With Prevailing Wage Rate Determination

Authorization for this form is provided under Sections 66.0903(9)(c), 66.0904(7)(c) and 103.49(4r)(c) Wisconsin Statutes.

The use of this form is mandatory. The penalty for failing to complete this form is prescribed in Section 103.005(12), Wisconsin Statutes.

Personal information you provide may be used for secondary purposes [Privacy Law, s. 15.04(1)(m), Wisconsin Statutes].

This form must ONLY be filed with the Awarding Agency indicated below.

		Project Name	
State Of)	DWD Determination Number	Project Number (if applicable)
)SS	Date Determination Issued	Date of Contract
County Of)	Awarding Agency	
		Date Work Completed	

After being duly sworn, the person whose name and signature appears below hereby states under penalty of perjury that

- I am the duly authorized officer of the corporation, partnership, sole proprietorship or business indicated below and have recently completed all of the work required under the terms and conditions of a contract with the above-named awarding agency and make this affidavit in accordance with the requirements set forth in Section 66.0903(9)(c), 66.0904(7)(c) or 103.49(4r)(c), Wisconsin Statutes and Chapter DWD 290 of the Wisconsin Administrative Code in order to obtain FINAL PAYMENT from such awarding agency.
- I have fully complied with all the wage and hour requirements applicable to this project, including all of the requirements set forth in the prevailing wage rate determination indicated above which was issued for such project by the Department of Workforce Development on the date indicated above.
- I have received the required affidavit of compliance from each of my agents and subcontractors that performed work on this project and have listed each of their names and addresses on page 2 of this affidavit.
- I have full and accurate records that clearly indicate the name and trade or occupation of every worker(s) that I employed on this project, including an accurate record of the hours worked and actual wages paid to such worker(s).
- I will retain the records and affidavit(s) described above and make them available for inspection for a period of at least three (3) years from the completion date indicated above at the address indicated below and shall not remove such records or affidavit(s) without prior notification to the awarding agency indicated above.

Name of Corporation, Partnership, Sole Pro	prietorship, Business,	State Agency or Lo	cal Governm	iental Unit
Street Address	City	State	Zip Code	Telephone Number
Print Name of Authorized Officer			Date Sign	ed
Signature of Authorized Officer			I	

Name		Name			
Street Address			Street Address		
City	State	Zip Code	City	State	Zip Code
Telephone Number			Telephone Number		<u></u>
Name			Name		
Street Address		· · ·	Street Address		
City	State	Zip Code	City	State	Zip Code
Telephone Number			Telephone Number	, , , L	
Name			Name		
Street Address			Street Address		
City	State	Zip Code	City	State	Zip Code
Telephone Number	.	1	Telephone Number		
Name			Name		
Street Address			Street Address		
City	State	Zip Code	City	State	Zip Code
Telephone Number	- 	- 	Telephone Number		
Name			Name		
Street Address			Street Address		
City	State	Zip Code	City	State	Zip Code
Telephone Number			Telephone Number	<u> </u>	•
Name		· · ·	Name		
Street Address		99 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	Street Address		
City	State	Zip Code	City	State	Zip Code
Telephone Number	. I	1	Telephone Number	•	

State of Wisconsin Department of Workforce Development Equal Rights Division

Agent or Subcontractor Affidavit of Compliance With Prevailing Wage Rate Determination

Authorization for this form is provided under Sections 66.0903(9)(b), 66.0904(7)(b) and 103.49(4r)(9b), Wisconsin Statutes. The use of this form is mandatory. The penalty for failing to complete this form is prescribed in Section 103.005(12), Wisconsin Statutes.

Personal information you provide may be used for secondary purposes [Privacy Law, Section 15.04(1)(m), Wisconsin Statutes].

This form must ONLY be filed with the Awarding Contractor indicated below.

		Project Name		
State Of)	DWD Determination Number	Project Number (if applicable)	
)SS	Date Determination Issued	Date of Subcontract	
Country Of)00	Awarding Contractor		
County Of)	Date Work Completed		

After being duly sworn, the person whose name and signature appears below hereby states under penalty of perjury that

- I am the duly authorized officer of the corporation, partnership, sole proprietorship or business indicated below. We have recently completed all of the work required under the terms and conditions of a subcontract with the above-named awarding contractor. We make this affidavit in accordance with the requirements set forth in Section 66.0903(9)(b), 66.0904(7)(b) or 103.49(4r)(b), Wisconsin Statutes and Chapter DWD 290 of the Wisconsin Administrative Code in order to obtain FINAL PAYMENT from such awarding contractor.
- I have fully complied with the entire wage and hour requirements applicable to this project, including all of the requirements set forth in the prevailing wage rate determination indicated above which was issued for such project by the Department of Workforce Development on the date indicated above.
- I have received the required affidavit of compliance from each of my agents and subcontractors that performed work on this project and have listed each of their names and addresses on page 2 of this affidavit.
- I have full and accurate records that clearly indicate the name and trade or occupation of every worker(s) that I employed on this project, including an accurate record of the hours worked and actual wages paid to such worker(s).
- I will retain the records and affidavit(s) described above and make them available for inspection for a period of at least three (3) years from the completion date indicated above at the address indicated below and shall not remove such records or affidavit(s) without prior notification to the awarding contractor.

Name of Corporation, Partnership, Sole Proprie	etorship, Business, State Agency	or Local	Government	tal Unit
Street Address or PO Box	City	State	Zip Code	Telephone Number
Print Name of Authorized Officer Date Signed				
Authorized Officer Signature				

ERD-10584 (R. 11/2010)

	st	of	Agents	and	Subcontractors
--	----	----	--------	-----	-----------------------

Name			Name	······································	
Street Address			Street Address		
-		_			
City	State	Zip Code	City	State	Zip Code
Telephone Number			Telephone Number		
() Nove			() Na		
Name			Name		
Street Address			Street Address		
City	State	Zip Code	City	State	Zip Code
Telephone Number			Telephone Number		
() Name			() Name		
Street Address			Street Address		
City	State	Zip Code	City	State	Zip Code
Telephone Number			Telephone Number ()		-
Name			Name		
Street Address			Street Address	· · · ·	
City	State	Zip Code	City	State	Zip Code
Telephone Number ()	- J		Telephone Number ()	· · · · · · · · · · · · · · · · · · ·	
Name			Name		
Street Address			Street Address		
City	State	Zip Code	City	State	Zip Code
Telephone Number ()			Telephone Number ()		
Name			Name	<u></u>	
Street Address			Street Address		
City	State	Zip Code	City	State	Zip Code
Telephone Number		1	Telephone Number	<u> </u>	
()			()		

If you have any questions call (608) 266-6861

Equal Rights Division Labor Standards Bureau	request to Linplay Jubjourneyperson	inciadáaiiinnínno
The use of this form is mandatory. The penalty for failing to complete this form is prescribed in Section 103.005(12), Wisconsin Statutes. Personal information you provide may be used for secondary purposes (Privacy Law, s. 15.04(1)(m), Wisconsin Statutes]. The employer indicated below requests that the Department of Workforce Development (DWD) determine the prevailing wage rate(s) and related qualifications to enable such employer to use a subjourneyperson(s) on the following prevailing wage project, in accordance with the provisions of Section DWD 290.025, Wisconsin Administrative Code.	bed in Section 103.005(12), Wisconsin Statutes. Law, s. 15.04(1)(m), Wisconsin Statutes]. e Development (DWD) determine the prevailing w he following prevailing wage project, in accordanc	vage rate(s) and related ce with the provisions of
1. Name of Project Appearing on the Project Determination		
County	City, Village or Town	
DWD Project Determination Number	Project Number (if applicable)	
2. Job Classification(s) for which you request a subjourney rate (i.e., carpenter, electrician, plumber, etc.)	lectrician, plumber, etc.)	
σ	ġ	
ö	d.	
3. Employer Name (Print)	Requester Name (Print)	
Address	City State	Zip Code
Telephone Number ()	Requester Title	
Email address (if you prefer to receive your response via email)	Fax Number (if you prefer to receive your response via fax) (/ia fax)
READ CAREFULLY: I understand that this request is ONLY applicable to the project and job classification(s) listed above and that subjourney employees primarily work under the direction of and assist a skilled trade employee by frequently using the tools of a skilled trade and will NOT regularly perform the duties of a general laborer, heavy equipment operator or truck driver. If the subjourney employee regularly performs the work of a different trade or occupation, he/she will be compensated for such work at the applicable journeyperson prevailing wage rate. I agree to compensate subjourney employees in strict accordance with the directions received from the DWD.	the project and job classification(s) listed above a employee by frequently using the tools of a skillec or or truck driver. If the subjourney employee reg ork at the applicable journeyperson prevailing wag s received from the DVVD.	and that subjourney t trade and will NOT lularly performs the work je rate. I agree to
Requester Signature	Date Signed	
MAIL the completed request to: EQUAL RIGHTS DIVISION, LABOR STANDA PO BOX 8928, MADISON WI 537 OR FAX the completed request to: (608) 267-4592 / DO NC Call (608) 266-6861 for assistance in completi	MAIL the completed request to: EQUAL RIGHTS DIVISION, LABOR STANDARDS BUREAU PO BOX 8928, MADISON WI 53708 OR FAX the completed request to: (608) 267-4592 / DO NOT e-mail your request. Call (608) 266-6861 for assistance in completing this form.	
ERD-10880 (R. 6/2013)		

Request to Employ Subjourneyperson

State of Wisconsin Department of Workforce Development Equal Rights Division Labor Standards Bureau

AD		ERAL PREVAILING WAGE LAW INFORMATION is document updated February 2014)
For prevailing w	age laws and freq	uently asked questions, refer to the prevailing wage website at: onsin.gov/er/prevailing_wage_rate/default.htm
Торіс	Who's affected?	Brief description of requirement under §66.0903 or §103.49
Non-applicability	All public entities	Prevailing wage rates do not apply to minor service or maintenance work, warranty work, or work under a supply and installation contract.
Non-applicability: Minor service or maintenance work	Local governmental units & Contractors	 Minor service or maintenance work means a project of public works that is limited to minor crack filling, chip or slurry sealing, or other minor pavement patching, not including overlays, that has a projected life span of no longer than 5 years or that is performed for a TOWN and is not funded under §86.31, regardless of projected life span; the depositing of gravel on an existing gravel road applied solely to maintain the road; road shoulder maintenance; cleaning of drainage or sewer ditches or structures; or any other limited, minor work on public facilities or equipment that is routinely performed to prevent breakdown or deterioration.
Non-applicability: Minor service or maintenance work	State agencies	 Minor service or maintenance work means a project of public works that is limited to minor crack filling, chip or slurry sealing, or other minor pavement patching, not including overlays, that has a projected life span of no longer than 5 years; cleaning of drainage or sewer ditches or structures; or any other limited, minor work on public facilities or equipment that is routinely performed to prevent breakdown or deterioration.
Non-applicability: Supply & installation contract	All public entities	Supply and installation contract means a contract under which the material is installed by means of simple fasteners or connectors such as screws or nuts and bolts and no other work is performed on the site of the project of public works, and the total labor cost to install the material does not exceed 20 percent of the total cost of the contract.
Non-applicability: Work which a contractor or individual donates to a public entity	All public entities	Prevailing wage laws §§66.0903 & 103.49, Stats., do not apply to work performed on a project of public works for which the local governmental unit or the state or the state agency contracting for the project is not required to compensate any contractor, subcontractor, contractor's or subcontractor's agent, or individual for performing the work.

Topic	Who's affected?	Brief description of requirement under §66.0903 or §103.49
Non-applicability: Residential	All public entities	A prevailing wage rate determination is not required for the erection, construction, repair, remodeling, or demolition of a residential property containing 2 dwelling units or less.
Non-applicability: Residential subdivision infrastructure	All public entities	A prevailing wage rate determination is not required for a road, street, bridge, sanitary sewer, or water main project that is a part of a development in which at least 90 percent of the lots contain or will contain 2 dwelling units or less, as determined by the local governmental unit at the time of approval of the development, and that, on completion, is acquired by, or dedicated to, a local governmental unit (including under §236.13(2), Stats.), or the state, for ownership or maintenance by the local governmental unit or the state.
Electronic certified payroll record	Contractors	The requirement that every contractor on a prevailing wage project submit to DWD monthly a certified record of employees who worked on the project and that DWD post these certified records on its Internet website was discontinued effective July 1, 2011. Contractors are still required to maintain payroll records and provide them upon request from DWD &/or the project owner.
Payroll record inspection request by any person	Contractors & Complainants	Any person may request DWD to inspect the payroll records of any contractor working on a prevailing wage project. On receipt of such a request, the contractor must submit to DWD a certified record of its payroll records, other than personally identifiable information relating to an employee of the contractor, for no longer than a 4-week period. DWD may request records from a contractor under this provision no more than once per calendar quarter for each project of public works on which the contractor is performing work. The department may not charge a requester a fee for obtaining that information. DWD must make these certified records available for public inspection.
Statewide uniformity	Local govern- mental units	A local governmental unit may not enact & administer a prevailing wage ordinance/provision for public works or publicly funded private construction projects. Any extant laws to that effect are void.
Substance Abuse Testing	Contractors & Workers	Before commencing work on a prevailing wage project, a contractor must have a written substance abuse testing program in place that complies with §103.503, Wis. Stats. No employee may use, possess, attempt to possess, distribute, deliver, or be under the influence of a drug or under the influence of alcohol while performing work on a prevailing wage project.

Topic	Who's affected	Brief description of requirement under §66.0903 or §103.49
Covered employees	Who's affected Truck drivers & Other workers & Contractors	A laborer, worker, mechanic, or truck driver who is employed to process, manufacture, pick up, or deliver materials or products from a commercial establishment that has a fixed place of business from which the establishment supplies processed or manufactured materials or products or from a facility that is not dedicated exclusively, or nearly so, to a project of public works is NOT entitled to receive the prevailing wage rate UNLESS any of the following applies: 1) the laborer, worker, mechanic, or truck driver is
		employed to go to the source of mineral aggregate such as sand, gravel, or stone and deliver that mineral aggregate to the site of a project of public works by depositing the material directly in final place, from the transporting vehicle or through spreaders from the transporting vehicle. 2) the laborer, worker, mechanic, or truck driver is
		employed to go to the site of a project of public works, pick up excavated material or spoil from the site of the project, and transport that excavated material or spoil away from the
***	~~~~	site of the project.

SECTION 01 00 00

BASIC REQUIREMENTS

PART 1 GENERAL

1.1 SECTION SUMMARY

- A. Section Includes:
 - 1. Section Summary
 - 2. Summary of the Work
 - 3. Contractor Use of Premises
 - 4. Applications for Payment
 - 5. Change Procedures
 - 6. Coordination
 - 7. Conferences
 - 8. Progress Meetings
 - 9. Submittal Procedures
 - 10. Proposed Products List
 - 11. Product Data
 - 12. Samples
 - 13. Manufacturers' Instructions
 - 14. Manufacturers' Certificates
 - 15. Quality Assurance / Quality Control of Installation
 - 16. References
 - 17. Protection of Installed Work
 - 18. Parking
 - 19. Staging Areas
 - 20. Occupancy During Construction and Conduct of Work
 - 21. Protection
 - 22. Progress Cleaning
 - 23. Contract Closeout Procedures
 - 24. Final Cleaning

1.2 SUMMARY OF THE WORK

- A. Project Description: Perform the Work as specified and detailed in Construction Documents package. The project work includes grading services and prairie restoration (including a 3-year prairie maintenance program).
- B. Work by Owner:
 - 1. Owner will coordinate purchase and installation of informational and interpretive signage that is provided by Allowance included in the Base Bid.
- C. Permits: By Owner

1.3 CONTRACTOR USE OF PREMISES

A. Limit use of premises to allow work by Contractors or Subcontractors and access by Owner.

1.4 APPLICATIONS FOR PAYMENT

- A. Submit two (2) copies of each application on AIA G702TM and G703TM forms or approved contractors invoice form.
- B. Content and Format: Utilize Schedule of Values for listing items in Application for Payment.
- C. Payment Period: Monthly

1.5 CHANGE PROCEDURES

- A. Change Order Forms: Dane County Contract Change Order, Form 014-32-20 (latest issue).
- B. Contractor's costs for Products, delivery, installation, labor, insurance, payroll, taxes, bonding, equipment rental, overhead and profit will be included in Change Orders authorizing expenditure of funds from the contingency allowance.

1.6 COORDINATION

- A. Coordinate scheduling, submittals, and work of various sections of Specifications to assure efficient and orderly sequence of installation of interdependent construction elements.
- B. Verify utility requirement characteristics of operating equipment are compatible with building utilities.
- C. Coordinate space requirements and installation of mechanical and electrical work that are indicated diagrammatically on Drawings.

1.7 CONFERENCES

- A. Owner will schedule a preconstruction conference after Award of Contract for all affected parties.
- B. When required in individual Specification section, convene a pre-installation conference at project site prior to commencing work of the section.

1.8 PROGRESS MEETINGS

A. Schedule and administer meetings throughout progress of the Work at minimum of two meetings.

1.9 SUBMITTAL PROCEDURES

- A. Submittal form to identify Project, Contractor, Subcontractor or supplier; and pertinent Construction Documents references.
- B. Apply Contractor's stamp, signed or initialed, certifying that review, verification of Products required, field dimensions, adjacent construction work, and coordination of information is in accordance with requirements of the Work and Construction Documents.

1.10 PROPOSED PRODUCTS LIST

A. Within ten (10) days after date of Award of Contract, submit complete list of major Products proposed for use, with name of manufacturer, trade name, and model number of each Product.

1.11 PRODUCT DATA

- A. Submit number of copies that Contractor requires, plus two (2) copies that shall be retained by Public Works Project Manager.
- B. Mark each copy to identify applicable products, models, options, and other data. Supplement manufacturer's standard data to provide information unique to this Project.

1.12 SAMPLES

A. Submit samples to illustrate functional characteristics of the Product.

1.13 MANUFACTURERS' INSTRUCTIONS

- A. When specified in individual Specification sections, submit manufacturers' printed instructions for delivery, storage, assembly, installation, start-up, adjusting, and finishing, in quantities specified for Product Data.
- 1.14 MANUFACTURERS' CERTIFICATES
 - A. When specified in individual Specification sections, submit manufacturers' certificate to Public Works Project Manager for review, in quantities specified for Product Data.
 - B. Indicate material or Product conforms to or exceeds specified requirements. Submit supporting reference data, affidavits, and certifications as appropriate.

1.15 QUALITY ASSURANCE / QUALITY CONTROL OF INSTALLATION

- A. Monitor quality control over suppliers, manufacturers, Products, services, site conditions, and workmanship, to produce work of specified quality.
- B. Comply fully with manufacturers' instructions.

C. Comply with specified standards as minimum quality for the Work except when more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.

1.16 REFERENCES

- A. Conform to reference standard by date of issue current as of date for receiving bids.
- B. Should specified reference standard conflict with Construction Documents, request clarification from Public Works Project Manager before proceeding.

1.17 PROTECTION OF INSTALLED WORK

A. Protect installed work and provide special protection where specified in individual Specification sections.

1.18 PARKING

- A. Parking shall be available at the Work site by arrangement with the Public Works Project Manager. .
- 1.19 STAGING AREAS
 - A. Coordinate staging areas with Public Works Project Manager prior to starting the Work.
 - B. On-site space for use as staging areas and storage of materials will be available. Each Contractor shall be responsible for safety of equipment and materials that are stored on site.

1.20 OCCUPANCY DURING CONSTRUCTION AND CONDUCT OF WORK

- A. Areas of existing facility will be occupied during period when the Work is in progress. Work may be done during normal business hours (8:00 am to 4:30 pm), but confer with Owner, schedule work and store materials so as to interfere as little as possible with normal use of premises. Notify Owner when coring or similar noise making work is to be done and obtain Owner's written approval of schedule. If schedule is not convenient for Owner, reschedule and resubmit new times for Owner approval.
- B. Work shall be done so as not to interfere with access to any occupied area and so as to cause least possible interference with normal operation of facility or any essential service thereof.
- C. Contractor shall provide adequate protection for all parts of facility, its contents and occupants wherever the Work under this Contract is to be performed.
- D. Each Contractor shall be responsible for contacting Digger's Hotline before proceeding with work.

1.21 PROTECTION

A. Contractor shall protect from injury all trees, shrubs, hedges, walks and driveways and pay for any damage to same resulting from insufficient or improper protection.

1.22 PROGRESS CLEANING

A. Maintain site free of waste materials, debris, and rubbish. Maintain site in clean and orderly condition.

1.23 CONTRACT CLOSEOUT PROCEDURES

- A. Submit written certification that Construction Documents have been reviewed, the Work has been inspected, and the Work is complete in accordance with Construction Documents and ready for Public Works Project Manager's inspection.
- B. Submit final Application for Payment identifying total adjusted Contract Sum / Price, previous payments, and amount remaining due.

1.24 FINAL CLEANING

- A. Execute final site cleaning prior to final inspection.
- B. Remove waste and surplus materials, rubbish, and construction facilities from site.

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

Not Used.

END OF SECTION

SECTION 31 05 13 EARTHWORK

PART 1 GENERAL

1.1 DESCRIPTION

- A. Providing, moving, placing, and compacting fill materials in accordance with the lines, grades, thicknesses, and typical sections shown on the Drawings.
- B. Trenching, backfilling, compaction and grading for utility installation.
- C. Excavating, moving, loading, hauling, regrading, stockpiling, and/or disposal of excavation waste materials, including finish grading to the extent and elevations shown on the Drawings.

1.2 REFERENCES

- A. State of Wisconsin Department of Transportation (WI DOT):
 - 1. Standard Specifications for Highway and Structure Construction, latest edition.
 - B. Erosion Control Permit Application, Badger Prairie Health Care Center (SCS Engineers, May 2014).

1.3 SUBMITTALS

A. Submit engineered soil mix composition data 2 weeks prior to placement.

PART 2 PRODUCTS

- 2.1 FILL MATERIAL
 - A. USDA Sand:
 - 1. Meet one of the following gradations:
 - USDA Coarse Sand (0.02-0.04 inches)
 - ASTM C33 (Fine aggregate concrete sand)
 - Wisconsin Standard Specifications for Highway Construction, Section 501.2.5.3.4 (Fine Aggregate Sand) 2005 edition, or an equivalent as approved by Engineer
 - B. Engineered Soil:
 - 1. As specified on Drawings.
 - C. General Fill:
 - 1. Soil that is free of vegetation, ash, wood, organics, debris, refuse, masonry, metal, sharp objects, boulders, snow, and ice.
 - 2. No solid material larger than 4 inches in its largest dimension.

PART 3 EXECUTION

- 3.1 INSPECTION
 - A. Examine the areas and conditions where Work will be performed and notify the Engineer

in writing of conditions detrimental to the proper and timely completion of the Work. Do not proceed with the Work until unsatisfactory conditions have been corrected.

3.2 EXCAVATION

- A. General:
 - 1. Excavate to the limits and depths shown on the Drawings.
 - 2. Segregate and stockpile excavated materials.
 - 3. Removal of materials beyond the limits and depths shown on the Drawings without authorization of Engineer shall be at the Contractor's expense, including backfill and compaction.
- B. Trenching:
 - 1. Unauthorized trenching: Removal of materials beyond the elevations or dimensions indicated on the Drawings without authorization of Engineer shall be at the Contractor's expense, including backfill and compaction.
 - 2. Excavate to the dimensions and elevations shown on the Drawings to permit proper installation of utility piping.
 - 3. Grade bottom of trench so that pipes can be laid without sags or humps.
 - 4. Unsuitable soil: Remove unsuitable soils as required by pipe manufacturer's specifications. Replace the excavated material in accordance with manufacturer's recommendations.
- C. Do not backfill trenches until an inspection has been made and backfilling authorized by the Engineer.
- D. Proofrolling:
 - 1. Proofroll subgrade with a loaded triaxle dump truck or loaded scraper as directed by Engineer.
 - 2. Excavate or stabilize soft or loose soils, if any, as directed by Engineer.
 - 3. Stabilize a soft subgrade as provided in Geotechnical Exploration Report (GCG, Inc., September 2013).
- E. Re-establish subgrade elevation with backfill materials as recommended in Geotechnical Exploration Report (GCG, Inc., September 2013).
- F. Perform all Work in accordance with OSHA requirements.

3.3 PREPARATION AND RESTORATION

- A. Remove ice and snow before placing fill. Do not place fill on frozen subgrade.
- B. Cut out soft areas of unsuitable subgrade.
- C. Contractor is responsible for preparing, maintaining, and documenting proper subbase.

3.4 FILLING

- A. General:
 - 1. Clear trenches of trash and debris before backfilling.
 - 2. Carefully place fill material to protect underground structures and utilities.
 - 3. Do not fill with frozen material.

- 4. Inspect excavation prior to backfilling to ensure suitable for backfilling.
- 5. If fill settles below the adjacent ground surface, prior to one year following completion of Work, Contractor shall refill settled area and mechanically compact the surface. If backfill settlement damages structures, pavement, landscaping or buried utilities, Contractor shall repair damaged facilities to the satisfaction of the Owner.
- B. Fill in Non-Paved Area:
 - 1. Fill shall consist of non-organic general fill. Place in 10 inch lifts, mechanically compact to at least 85%, based on modified Proctor maximum dry density as defined by ASTM D 1557.
- C. Testing:
 - 1. Test backfill for compaction twice per every other lift in non-paved areas.
 - 2. Field density testing shall be in accordance with ASTM D 2922.
 - 3. Retest any failed tests after re-compaction.

3.5 GRADING

- A. Grade and finish to within 0.10 foot of grades provided.
- B. Uniformly grade areas within limits of backfilled trenches, including adjacent transition areas.
- C. Blend slopes with existing landscape features at the intersection of cuts and fills; provide gradual slope between new and existing construction.
- 3.6 EXCESS SOIL
 - A. Load, haul, and properly dispose off-site any excess fill material not usable or used during construction.

END OF SECTION

SECTION 31 25 13 EROSION CONTROL

PART 1 GENERAL

1.1 DESCRIPTION

A. Section includes silt fence, riprap, geotextile, erosion control mat, stabilized construction entrance, inlet protection, and mulch for site work erosion control.

1.2 REFERENCES

- A. State of Wisconsin Department of Transportation (WI DOT):
 - 1. Standard Specifications for Road and Bridge Construction, latest edition.
 - 2. Erosion Control Product Acceptability List, latest edition.
- B. State of Wisconsin Department of Natural Resources (WDNR)
 - 1. Stormwater Management Technical Standards, latest edition.
- C. Erosion Control Permit Application and WDNR Notice of Intent renewal, Badger Prairie Health Care Center (SCS Engineers, May 2014).

1.3 QUALITY ASSURANCE

- A. Geotextile:
 - 1. Geotextile shall be free of defects, rips, holes or flaws.
 - 2. It shall be manufactured in widths and lengths that will permit installation of geotextile with as few laps a possible.
 - 3. During shipment and storage, geotextile shall be wrapped in relatively impermeable and opaque protective covers.
 - 4. Geotextile shall be marked with Manufacturer's name, product identification, lot number, roll number and roll dimensions.
 - 5. Storage area shall be such that geotextile is protected from mud, dirt, dust, debris, moisture, and exposure to ultraviolet light and heat.
- B. General:
 - 1. Contractor shall repair any areas damaged by erosion for a period of one year following completion of construction.

1.4 SUBMITTALS

- A. Submit silt fence and geotextile product identification and material specifications 2 weeks prior to installation.
- B. Submit erosion control mat product identification and Manufacturer's installation recommendations 2 weeks prior to installation.

PART 2PRODUCTS

2.1 GEOTEXTILE

A. Conform to WI DOT Type HR geotextile.

2.2 RIPRAP

- A. Salvage and reuse existing riprap.
- B. New riprap shall conform to WI DOT Medium Riprap for culvert outlet protection.

2.3 EROSION CONTROL MAT

A. Class I, Type B erosion mat included on WI DOT Product Acceptability List (PAL).

2.4 STABILIZED CONSTRUCTION ENTRANCE

A. Stone shall consist of 3- to 6-inch clear or washed stone. All material shall be retained on a 3-inch sieve.

2.5 SILT FENCE

A. Comply with the requirements of WDNR Stormwater Management Technical Standard 1056 (Silt Fence).

2.6 INLET PROTECTION

A. Comply with the requirements of WDNR Stormwater Management Technical Standard 1060 (Storm Drain Inlet Protection for Construction Sites).

2.7 SEDIMENT LOG TEMPORARY DITCH CHECKS

- A. Temporary 12" ditch check included on WI DOT Product Acceptability List (PAL).
- B. Designed for channel applications.

2.8 TEMPORARY USE OF PERMANENT FEATURES

When the contract contains items of work, which are of an erosion control or storm water nature, and are intended to be a permanent installation, the Contractor may employ these items in his control of erosion and storm water during his construction activities.
 However, these items shall be fully cleaned, restored, and in every way fully functioning for its intended permanent use prior to acceptance of the work.

PART 3 EXECUTION

3.1 GENERAL

- A. Examine the areas and conditions where Work will be performed and notify Engineer in writing of conditions detrimental to proper and timely completion of Work. Do not proceed with Work until unsatisfactory conditions have been corrected.
- B. Minimize the amount of disturbed area open at a given time.
- C. Execute construction to minimize surface water runoff from or to disturbed areas.
- D. Avoid runoff or deposition of site materials into drainage features or off the property.

- E. Do no track or spill site materials off the property. Off-property tracking or spills must be cleaned up immediately by the Contractor.
- F. Contractor shall periodically inspect site work and erosion controls for erosion, sedimentation, or defects. Contractor is to correct deficiencies identified in a timely manner.
- G. Contractor is to replace or repair erosions controls affected by the construction. Erosion controls are to be returned to installed conditions or reinstalled to accommodate construction.
- H. Install erosion controls for soil stockpiled for seven or more days during the Work and/or when rain is expected.
- I. Alterations or additions to the existing erosion controls shall not affect the performance of the erosion control plan and must conform to WDNR best management practices.
- J. Remove temporary erosion control features once site is stabilized and with approval of Engineer.

3.2 GEOTEXTILE PLACEMENT AND HANDLING

- A. Installer shall handle all geotextiles in such a manner as to ensure they are not damaged in any way.
- B. Provide a minimum geotextile overlap width of 2 ft.
- C. Any holes or tears in geotextile shall be repaired using a patch made from same geotextile that is spot-seamed in place with a minimum of 24 in. overlap in all directions.
- D. Installer shall place all materials located on top of geotextile in such a manner as to ensure no damage of geotextile.

3.3 RIPRAP PLACEMENT

- A. Place riprap by hand using larger stones for lower courses. Lay stones perpendicular to slope with ends in contact. Chink spaces between stones with spalls firmly rammed into place.
- B. Compact riprap in place.
- C. Provide an even, tight finished riprap surface.
- D. Inspect weekly and within 24 hours after each rainfall.

3.4 EROSION CONTROL MAT PLACEMENT

- A. Install in accordance with Manufacturer's recommendations.
- B. Inspect weekly and within 24 hours after each rainfall.

3.5 STABILIZED CONSTRUCTION ENTRANCE

- A. Install in accordance with WDNR Technical Standard 1057 (Stone Tracking Pad and Tire Washing).
- B. Inspect weekly and within 24 hours after each rainfall.
- C. Remove sediment tracked onto public or private roads by street cleaning (not flushing) at the end of each working day.

3.6 SILT FENCE INSTALLATION AND MAINTENANCE

- A. Overlap ends of silt fence at joints for a length equal to distance between two stakes.
- B. Inspect weekly and within 24 hours after each rainfall.
- C. Repair or replace if silt fence is torn, sagging, overtopped, blown over (laying down), or in any way is not functioning for sediment containment.
- D. Remove sediment when sediment deposits reach no more than one half of silt fence height.
- E. Remove silt fence once contributing drainage area is stabilized with vegetation or impervious surface.

3.7 INLET PROTECTION PLACEMENT AND MAINTENANCE

- A. Install inlet protection as shown on Drawings prior to site disturbance.
- B. Maintain inlet protection throughout site construction duration.
- C. Inspect weekly and within 24 hours after each rainfall.
- D. Remove inlet protection once the contributing drainage area is stabilized with vegetation or impervious surface.

3.8 SEDIMENT LOG TEMPORARY DITCH CHECK PLACEMENT AND MAINTENANCE

- A. Install sediment logs as shown on Drawings
- B. Install in accordance with manufacturer's specifications.
- C. Inspect weekly and within 24 hours after each rainfall.
- D. Repair or replace if sediment log is damaged, washed away.
- E. Remove sediment when sediment deposits reach no more than one third of the sediment log height.

END OF SECTION

SECTION 32 90 10

RESTORATION

PART 1. GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Preparation of soil
 - 2. Herbicide application
 - 3. Seeding
 - 4. Maintenance
- B. Related Sections:
 - 1. Section 31 05 13 Earthwork
 - 2. Section 31 25 13 Soil Erosion
 - 3. Section 32 90 20 Native Vegetated Mat (NVM)
 - 4. Section 32 90 30 Prairie Seeding

1.2 DEFINITIONS

- A. Weeds: Vegetative species other than prairie species.
- B. Native Species: Prairie grasses and plants native to Wisconsin mesic prairies.

1.3 REFRENCES

A. ASTM D3385 - 09

1.4 SUBMITTALS

A. Product Data: Submit product data for seed mixture and herbicide.

1.5 QUALITY ASSURANCE

A. Perform all work in accordance with established practice.

1.6 QUALIFICATIONS

- A. Seed Producer: Company specializing in manufacturing seed mixture specified in this section shall have minimum of three (3) years documented experience.
- B. Herbicide Producer: Company specializing in manufacturing herbicide specified in this section shall have minimum of three (3) years documented experience.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Delivery of materials to site shall be governed by Construction Documents.
- B. Seed stored on site shall be covered and protected from animals.

1.8 COORDINATION

A. Coordinate with all marked and unmarked utilities that may exist.

1.9 MAINTENANCE

- A. Manage and maintain restored prairie areas and all restored areas of the project (including swales, stormwater basin, rain gardens, etc.) for three (3) years from Date of Substantial Completion.
- B. Provide Management Plan description and details following award of contract. A separate meeting shall be required with Contractor to review plan.

PART 2. PRODUCTS

2.1 NATIVE VEGETATED MAT (NVM)

- A. NVM shall be Agrecol Type B Native Vegetated Mat, or equal.
- B. Embedded seed mix shall be wet mesic / rainwater renewal native type.
- C. Refer to Section 32 90 20 Native Vegetated Mat (NVM)

2.2 SEEDS

- A. Seeds shall consist exclusively of diverse mixture of native Wisconsin prairie grasses. Mixture shall be a "low stature" mix designed for mesic soil. Seed shall be Agrecol, or equal.
- B. Refer to Section 32 90 30 Prairie Seeding

2.3 HERBICIDE

A. Herbicide shall be of a variety approved for use in Dane County.

PART 3. EXECUTION

3.1 EXAMINATION

A. Verify that area is ready for work to be performed.

B. Double ring infiltrometer shall be used to test infiltration rate in swales, infiltration rate shall meet requirements determined by Engineer.

3.2 PREPARATION OF SOIL

- A. Soil shall be prepared such that it is of sufficiently fine size and free of excessive clumps.
- B. Soil seedbed shall be prepared by tilling/raking the soil prior to seeding. In conjunction with the various grading repairs that may be required in the swale as well as the repairs to the outfall protection rip rap areas sub-soil ripping shall be included to scarf the surface top soils into inconsistent sub-soils to create a more consistent mesh between top soil and sub-soil. consistent mesh between the top soil and sub-soil.

3.3 HERBICIDE APPLICATION

- A. Prairie restoration area shall be treated with herbicide once before seeding shall occur. Herbicide was applied by the County in late fall of 2014. Herbicide application during the 3-year Management period shall be as follows; once in the summer, once in the fall, and once in the spring following Substantial Completion of the restoration.
- B. Localized herbicide treatment shall be sprayed on invasive plants as needed.

3.4 NATIVE VEGETATED MAT (NVM) INSTALLATION

A. NVM's shall be installed on the flat portion of the swale bottom and follow installation guidelines as set out in Section 32 90 20 Native Vegetated Mat.

3.5 SEEDING

A. See seeding Section 32 90 30 Prairie Seeding

3.6 MAINTENANCE ITEMS

- A. Control growth of weeds and non native species. Remedy damage resulting from improper use of herbicides.
- B. Mowing shall be done as follows:
 - 1.During the first year of growth, whenever average prairie grass height reaches ten to twelve (10-12") inches of growth, grass shall be mowed to height of six (6") inches.

2.During the second year of growth, mowing shall be done in the spring to a height of twelve (12") inches when prairie grass reaches an average height of two (2') feet.

SECTION 32 90 20

NATIVE VEGETATED MAT (NVM)

PART 1. GENERAL

1.1 SUMMARY

A. Section Includes:

- 1. Preparation of soil
- 2. Herbicide application
- 3. Seeding
- 4. Maintenance

B. Related Sections:

- 1. Section 31 30 00 Earthwork
- 2. Section 31 25 00 Soil Erosion
- 3. Section 32 90 20 Native Vegetated Mat (NVM)
- 4. Section 32 90 30 Prairie Seeding

1.2 DEFINITIONS

1. Native Vegetated Mat (NVM)-A pregrown mat of native prairie grasses, similar to traditional sod.

1.3 REFRENCES

- A. ASTM D3385 09
- B. ASTM D5338
- C. ASTM D5271

1.4 SUBMITTALS

A. Product Data: Submit product data and manufacturer for NVM.

1.5 QUALITY ASSURANCE

A. Perform all work in accordance with established practice.

1.6 QUALIFICATIONS

A. NVM Producer: Company specializing in growing NVM specified in this section shall have minimum of three (3) years documented experience.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Delivery of materials to site shall be governed by Construction Documents.
- B. NVM shall be kept in cool and moist environment during transportation and storage.

1.8 COORDINATION

A. Coordinate with all marked and unmarked utilities that may exist.

1.9 MAINTENANCE

A. Maintain NVM's and swales for three (3) years from Date of Substantial Completion.

PART 2. PRODUCTS

2.1 NATIVE VEGETATED MAT (NVM)

- A. NVM shall be Agrecol Type B Native Vegetated Mat, or equal.
- B. Embedded seed mix shall be wet mesic / rainwater renewal native type.
- C. Species distribution per area of NVM shall be as follows.

Black Eyed Susan	1%
Small Yellow Fox	
Sedge	4%
Common Bur Sedge	72%
Fox Sedge	4%
Prairie Dropseed	18%

2.2 BIODEGRADEABLE SOIL STAPLES

A. Contractor shall provide 6" long, 100% biodegradable anchoring staples, biodegradable from microbial activity in accordance with ASTM D5338 and ASTM D5271,shall be biodegradable in cold (43° F) and hot (180° F) soil conditions and shall be water resistant.

PART 3. EXECUTION

3.1 EXAMINATION

- A. Double ring infiltrometer shall be used to test infiltration rate in swales in accordance with ASTM D3385 09.
- B. Verify that area is ready for work to be performed.

3.2 NATIVE VEGITATED MAT (NVM) INSTALLATION

- A. NVM's shall be installed on the flat portion of the swale bottom.
- B. NVM shall be stapled with biodegradable anchoring staples using mechanical applicator.
- C. Supplemental water shall be provided in accordance with nursery suppliers recommendations for frequency, depth, and quality of water. Supplemental water shall be considered incidental to this item.

3.3 MAINTENANCE

- A. Control growth of weeds and non native species. Remedy damage resulting from improper use of herbicides.
- B. Mowing shall be done as follows:
 - 1.During the first year of growth, whenever average prairie grass height reaches ten to twelve (10-12") inches of growth, grass shall be mowed to height of six (6") inches.
 - 2.During the second year of growth, mowing shall be done in the spring to a height of twelve (12") inches when prairie grass reaches an average height of two (2') feet.

SECTION 32 90 30

PRAIRIE SEEDING

PART 1. GENERAL

1.1 SUMMARY

A. Section Includes:

- 1. Preparation of soil
- 2. Herbicide application
- 3. Seeding
- 4. Maintenance

B. Related Sections:

- 1. Section 31 30 00 Earthwork
- 2. Section 31 25 00 Soil Erosion
- 3. Section 32 90 10 Restoration
- 4. Section 32 90 20 Native Vegetated Mat (NVM)

1.2 DEFINITIONS

- A. Weeds: Vegetative species other than specified species to be established in given area.
- B. Native Species: Prairie grasses and plants native to Wisconsin mesic prairies.

1.3 REFRENCES

Not Used.

1.4 SUBMITTALS

A. Product Data: Submit product data for seed mixture and herbicide.

1.5 QUALITY ASSURANCE

A. Perform all work in accordance with established practice.

1.6 QUALIFICATIONS

A. Seed Producer: Company specializing in manufacturing seed mixture specified in this section shall have minimum of three (3) years documented experience.

B. Herbicide Producer: Company specializing in manufacturing herbicide specified in this section shall have minimum of three (3) years documented experience.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Delivery of materials to site shall be governed by Construction Documents.
- B. Seed stored on site shall be covered and protected from animals.

1.8 COORDINATION

A. Coordinate with all marked and unmarked utilities that may exist.

1.9 MAINTENANCE

A. Maintain restored prairie areas and swales for three (3) years from Date of Substantial Completion.

PART 2. PRODUCTS

2.1 SEEDS

- A. Seeds shall consist exclusively of diverse mixture of native Wisconsin prairie grasses. Mixture shall be a "low stature" mix designed for mesic soil.
- B. Conform to the Wisconsin Statutes and Wisconsin Administrative code Chapter ATCP 20 regarding noxious weed seed content and labeling.

2.2 COVER CROP

A. Suggested cover crop is oats, winter wheat and glyphosate based herbicide tolerant soybeans. Ideal cover crop must be glyphosate based herbicide tolerant. If cover crop is not tolerant to the herbicide, re-seeding will take place after each herbicidal application. Cover crops must not include alleopathic responses to native prairie species.

2.3 HERBICIDE

A. Herbicide shall be of a variety approved for use in Dane County.

PART 3. EXECUTION

3.1 SEEDING

- A. Seeding shall occur in the fall or spring after summer herbicide treatment.
- B. Seeds shall be planted at an average depth of one eighth to one half (1/8-1/2) of an inch below soil surface.
- C. Mechanical seeders and seed drills may be used. Hand powered broadcasters shall be used as necessary where obstacles limit access of mechanical seeders.
- D. Density of seeding shall not be less than 120 seeds per square foot.

3.2 MAINTENANCE

- A. Control growth of weeds and non native species. Remedy damage resulting from improper use of herbicides.
- B. Mowing shall be done as follows:
 - 1. During the first year of growth, whenever average prairie grass height reaches ten to twelve (10-12") inches of growth, grass shall be mowed to height of six (6") inches.
 - 2. During the second year of growth, mowing shall be done in the spring to a height of twelve (12") inches when prairie grass reaches an average height of two (2') feet.